## **CN-15MP & CN-20MP**

## Contractor Series MiniPorts



## **Features**

 Provides AC control for equipment located away from system racks with primary power conditioners/ sequencers (i.e. powered speakers).

• Sequencing of duplex initiated remotely by standard analog triggering (remote terminal) or digital link (SmartSequencing from CN-1800S or CN-2400S).

• SmartSequencing Technology allows multiple units to be daisy chained at runs of over 1,000' between units with bi-directional communications between units for sequencing on and off large and/or complex systems.

• IP Control (Telnet or cloud-based BlueBOLT) via SmartSequencing (when connected to CN-1800S/ CN-2400S with BB-RS232 Adaptor.

 Remote terminal supports connections to legacy Furman (non-Contractor Series) and third party power sequencers for maximum installation flexibility.

• DIP switches and potentiometer allows customization of settings such as sequencing delays, 12V on/ off, and more.

• Extreme Voltage Shutdown (EVS) safeguards from catastrophic under-voltage (under 80V sustained) or over-voltage (over 145V sustained) conditions. Circuit may be set to auto-reset when voltage returns to normal or manual reset after an event is detected.

· Security covers prevent unauthorized personnel from tampering with DIP switches.

· Fire alarm shut off.


• Available with 15 amp capacity (CN-15MP) or 20 amp capacity (CN-20MP).

Safety agency listed (CSA).

15 Year Limited Product Warranty.

See warranty policy documentation for terms and conditions.





Specifications subject to change due to product upgrades and improvements.

## **Dimensions and Weight**

