
# Panasonic®

# **Operating Instructions** Functional Manual

DLP<sup>™</sup> Projector Commercial Use

Model No. PT-RQ32K



The projection lens is sold separately.

Thank you for purchasing this Panasonic product.

- The Operating Instructions correspond to the firmware's main version 4.00 and higher.
- This manual is common to all the models regardless of suffixes of the Model No.
  - for Taiwan
  - PT-RQ32KT
  - for India
  - PT-RQ32KD
    for other countries or regions
  - PT-RQ32K
- Before operating this product, please read the instructions carefully and save this manual for future use.
- Before using this product, be sure to read "Read this first!" (→ pages 5 to 13).







ENGLISH DPQP1094ZF

# **Contents**

Deed this	finati	-
Read this	first!	5

### Chapter 1 Preparation

Precautions for use	17
Cautions when transporting	17
Cautions when installing	17
Cautions when setting up the projector	18
Security	21
QUAD PIXEL DRIVE	22
DIGITAL LINK	22
Art-Net	22
Early Warning Software	22
Storing	22
Disposal	22
Cautions on use	22
Accessories	24
Optional accessories	26
About your projector	28
Remote control	28
Projector body	29
Names and functions of the Interface Board (optional)	33
Preparing the remote control	
Inserting and removing the batteries	
When using the multiple projectors	
Connecting the remote control to the projector with a cable	

### Chapter 2 Getting Started

Setting up	
Usable outlet	
Installation mode	
Interface Board (optional)	40
Projected image and throw distance	41
Adjusting adjustable feet	49
Attaching/removing the projection lens	
(optional)	50
Attaching the projection lens	
Removing the projection lens	
Connecting	53
Before connecting	53
Connecting example: AV equipment	53
Connecting example: Computers	57
Connecting example using DIGITAL LINK	
Connecting example when using the contrast synchronization function/shutter	50
synchronization function	

### Chapter 3 Basic Operations

Switching on/off the projector	62
Connecting the power cord	62
Power indicator	63
Switching on the projector	64
When the initial setting screen is displayed	65
Making adjustments and selections	71
Switching off the projector	72
Projecting	73
Selecting the input signal	73
Adjusting the focus, zoom, and lens shift	75
Adjusting the focus when the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is	
Setting the lens type	
Executing the lens calibration	
Moving the projection lens to the home position	79
Lens shift range	
Adjusting the lens mounter when the focus is unbalanced	
Operating with the remote control	83
Using the shutter function	83
Using the on-screen display function	83
Using the automatic setup function	84
Switching the image aspect ratio	84
Using the function button	84
Displaying internal test pattern	85
Using the status function	85
Using the AC voltage monitor function	86
Setting ID number of the remote control	.86

### Chapter 4 Settings

Menu navigation	
Navigating through the menu	
Main menu	
Sub-menu	90

[PICTURE] menu	93
[PICTURE MODE]	
[CONTRAST]	93
[BRIGHTNESS]	94
[COLOR]	94
[TINT]	
[COLOR TEMPERATURE]	94
[GAMMA]	96
[SYSTEM DAYLIGHT VIEW]	
[SHARPNESS]	97
[NOISE REDUCTION]	98
[DYNAMIC CONTRAST]	98
[COLOR SPACE]	
[SYSTEM SELECTOR]	100
sRGB-compliant video	100
[POSITION] menu	102
[SHIFT]	102
[ASPECT]	102
[ZOOM]	103
[GEOMETRY]	104
[ADVANCED MENU] menu	107
[DIGITAL CINEMA REALITY]	
[BLANKING]	107
[EDGE BLENDING]	108
[FRAME RESPONSE]	110
[FRAME CREATION]	
[QUAD PIXEL DRIVE]	
[RASTER POSITION]	112
[DISPLAY LANGUAGE] menu	
Changing the display language	
[DISPLAY OPTION] menu	114
[COLOR MATCHING]	114
[LARGE SCREEN CORRECTION]	
[SCREEN SETTING]	115
[AUTO SIGNAL]	
[AUTO SETUP]	
[BACKUP INPUT SETTING]	117
[SIMUL INPUT SETTING]	118
[SDI IN]	119
[DIGITAL LINK IN]	122
[SLOT IN]	124
[ON-SCREEN DISPLAY]	139
[BACK COLOR]	141
[STARTUP LOGO]	141
[UNIFORMITY]	
[SHUTTER SETTING]	
[FREEZE]	145
[WAVEFORM MONITOR]	145
[CUT OFF]	147

[PROJECTOR SETUP] menu	
[PROJECTOR ID]	148
[PROJECTION METHOD]	148
[LENS]	149
[OPERATION SETTING]	161
[LIGHT OUTPUT]	163
[BRIGHTNESS CONTROL]	
[STANDBY MODE]	168
[NO SIGNAL SHUT-OFF]	168
[NO SIGNAL LIGHTS-OUT]	
[INITIAL STARTUP]	169
[STARTUP INPUT SELECT]	
[DATE AND TIME]	170
[SCHEDULE]	171
[MULTI PROJECTOR SYNC]	173
[RS-232C]	175
[REMOTE2 MODE]	176
[FUNCTION BUTTON]	176
[STATUS]	177
[AC VOLTAGE MONITOR]	179
[FILTER SETTING]	180
[SAVE ALL USER DATA]	181
[LOAD ALL USER DATA]	181
[INITIALIZE]	181
[SERVICE PASSWORD]	182
[MULTI DISPLAY] menu	183
Using the multi-display function	
[TEST PATTERN] menu	
[TEST PATTERN]	
[SIGNAL LIST] menu	
Registering new signals	
Renaming the registered signal	
Deleting the registered signal	
Protecting the registered signal	
Expanding signal lock-in range	
Sub memory	
[SECURITY] menu	
[SECURITY PASSWORD]	
[SECURITY PASSWORD CHANGE]	
[DISPLAY SETTING]	
[TEXT CHANGE]	
[CONTROL DEVICE SETUP]	
[CONTROL DEVICE PASSWORD CHANGE]	
	194

[NETWORK] menu	
[DIGITAL LINK MODE]	
[DIGITAL LINK STATUS]	
[NETWORK SETUP]	
[NETWORK CONTROL]	
[NETWORK STATUS]	
[DIGITAL LINK MENU]	
[Art-Net SETUP]	
[Art-Net CHANNEL SETTING]	
[Art-Net STATUS]	

### Chapter 5 Operations

Network connection	
Connecting to the network	
Web control function	
Computer that can be used for setting	
Accessing from the web browser	

### Chapter 6 Maintenance

Light source/temperature/filter indicators	222
When an indicator lights up	222
Maintenance/replacement	225
Before performing maintenance/replacement	225
Maintenance	225
Maintenance of filter	225
Replacing the unit	231
Troubleshooting	233
Self-diagnosis display	235

### Chapter 7 Appendix

Technical information	239
PJLink protocol	239
Using Art-Net function	240
Control commands via LAN	246
<serial in="">/<serial out=""> terminal</serial></serial>	249
<remote 2="" in=""> terminal</remote>	253
Control device password	254
Upgrade Kit	254
List of compatible signals	255
Specifications	276
Dimensions	279
Attaching the Long Life Filter Unit (optional)	281
Removing the air filter unit	281
Attaching the long life filter mount clasp	282
Attaching the air filter unit	282
Attaching the long life filter cover	283
Setting the filter	283

# Attaching the Smoke Cut Filter Unit (optional) 284 Removing the air filter unit 284 Attaching the Smoke Cut Filter 285 Setting the filter 285 Installing the Interface Board (optional) 287 Before installing or removing 287 How to install the Interface Board 287 How to remove the Interface Board 288 Index 289

# Read this first!

WARNING: THIS APPARATUS MUST BE EARTHED.

**WARNING:** To prevent damage which may result in fire or shock hazard, do not expose this appliance to rain or moisture.

This device is not intended for use in the direct field of view at visual display workplaces. To avoid incommoding reflexions at visual display workplaces this device must not be placed in the direct field of view.

The equipment is not intended for used at a video workstation in compliance BildscharbV.

The sound pressure level at the operator position is equal or less than 70 dB (A) according to ISO 7779.

### WARNING:

- 1. Remove the plug from the mains socket when this unit is not in use for a prolonged period of time.
- 2. To prevent electric shock, do not remove cover. No user serviceable parts inside. Refer servicing to qualified service personnel.
- 3. Do not remove the earthing pin on the mains plug. This apparatus is equipped with a three prong earthingtype mains plug. This plug will only fit an earthing-type mains socket. This is a safety feature. If you are unable to insert the plug into the mains socket, contact an electrician. Do not defeat the purpose of the earthing plug.

### WARNING:

This equipment is compliant with Class A of CISPR32. In a residential environment this equipment may cause radio interference.

**CAUTION:** To assure continued compliance, follow the attached installation instructions. This includes using the provided power cord and shielded interface cables when connecting to computer or peripheral devices. Also, any unauthorized changes or modifications to this equipment could void the user's authority to operate this device.

This is a device to project images onto a screen, etc., and is not intended for use as indoor lighting in a domestic environment.

Directive 2009/125/EC

# **WARNING:** TO REDUCE THE RISK OF FIRE OR ELECTRIC SHOCK, DO NOT EXPOSE THIS PRODUCT TO RAIN OR MOISTURE.



Indicated on the projector



The lightning flash with arrowhead symbol, within an equilateral triangle, is intended to alert the user to the presence of uninsulated "dangerous voltage" within the product's enclosure that may be of sufficient magnitude to constitute a risk of electric shock to persons.



The exclamation point within an equilateral triangle is intended to alert the user to the presence of important operating and maintenance (servicing) instructions in the literature accompanying the product.


WARNING: Do not look at the light emitted from the lens while the projector is being used.




Indicated on the projector

### Notice on laser

### (for USA and Canada)



### (for India)



### (for other countries or regions)

This projector is the Class 1 laser product that complies with IEC/EN 60825-1:2014.






**CAUTION:** Use of controls or adjustments or performance of procedures other than those specified herein may result in hazardous radiation exposure.

### WARNING (North America)

This projector would become Class IIIb laser product when an interchangeable projection lens is used under the condition that throw ratio is greater than 3.0, and if used without lens hood mounted over the long lens. If you use under this condition, you must receive variance approval letter from FDA before usage. Class IIIb levels of laser radiation are considered to be an acute hazard to the skin and eyes from direct radiation.

### CAUTION (North/Middle/South America)

This equipment is equipped with a three-pin grounding-type power plug. Do not remove the grounding pin on the power plug. This plug will only fit a grounding-type power outlet. This is a safety feature. If you are unable to insert the plug into the outlet, contact an electrician. Do not defeat the purpose of the grounding plug.



### WARNING (USA and Canada)

- Not for use in a computer room as defined in the Standard for the Protection of Electronic Computer/Data Processing Equipment, ANSI/NFPA 75.
- For permanently connected equipment, a readily accessible disconnect device shall be incorporated in the building installation wiring.
- For pluggable equipment, the socket-outlet shall be installed near the equipment and shall be easily accessible.

### **NOTIFICATION** (Canada)

This class A digital apparatus complies with Canadian ICES-003.

### For USA-California Only

This product contains a CR Coin Cell Lithium Battery which contains Perchlorate Material – special handling may apply.

See www.dtsc.ca.gov/hazardouswaste/perchlorate

### FCC NOTICE (USA)

Model Number:	PT-RQ32K
Trade Name:	Panasonic
Responsible Party:	Panasonic Corporation of North America
Address:	Two Riverfront Plaza, Newark, NJ 07102-5490
General Contact:	http://www.panasonic.com/support
Projector Contact:	https://panasonic.net/cns/projector/

This device complies with Part 15 of the FCC Rules.

Operation is subject to the following two conditions:

(1) This device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation.

### Caution:

This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

### FCC Warning:

To assure continued compliance, follow the attached installation instructions. This includes using the provided power cord and shielded interface cables when connecting to computer or peripheral devices. Also, any unauthorized changes or modifications to this equipment could void the user's authority to operate this device.

Importer's name and address within the European Union

Panasonic Marketing Europe GmbH

**Panasonic Testing Centre** 

Winsbergring 15, 22525 Hamburg, Germany

### WARNING:

### POWER

# The wall outlet or the circuit breaker shall be installed near the equipment and shall be easily accessible when problems occur. If the following problems occur, cut off the power supply immediately.

Continued use of the projector in these conditions will result in fire or electric shock, or will cause visual impairment.

- If foreign objects or water get inside the projector, cut off the power supply.
- If the projector is dropped or the cabinet is broken, cut off the power supply.
- If you notice smoke, strange smells or noise coming from the projector, cut off the power supply. Please contact an Authorized Service Center for repairs, and do not attempt to repair the projector yourself.

### During a thunderstorm, do not touch the projector or the cable.

Electric shocks can result.

### Do not do anything that might damage the power cord, the power plug, or the power connector.

If the power cord is used while damaged, electric shocks, short-circuits or fire will result.

• Do not damage the power cord, make any modifications to it, disassemble it, place it near any hot objects, bend it excessively, twist it, pull it, place heavy objects on top of it or wrap it into a bundle.

Consult an Authorized Service Center for any repairs to the power cord, the power plug, or the power connector that might be necessary.

### Do not use anything other than the provided power cord.

Failure to observe this will result in electric shocks or fire. Please note that if you do not use the provided power cord to ground the device on the side of the outlet, this may result in electric shocks.

### Completely insert the power plug into the wall outlet.

If the plug is not inserted correctly, electric shocks or overheating will result.

• Do not use plugs which are damaged or wall outlets which are coming loose from the wall.

### Fully attach the power connector (projector-side) to the <AC IN> terminal.

A power connector that is not completely attached may result in fires caused by electric shocks or heat generation.

### Do not handle the power plug and power connector with wet hands.

Failure to observe this will result in electric shocks.

Use an outlet supporting 30 A independently when using the projector with 200 V to 240 V alternating current.

# Use an outlet supporting 15 A independently when using the projector with 100 V to 120 V alternating current.

Using an outlet together with another device may result in fires due to heat generation.

### Do not overload the wall outlet.

If the power supply is overloaded (ex., by using too many adapters), overheating may occur and fire will result.

### Clean the power plug regularly to prevent it from becoming covered in dust.

Failure to observe this will cause a fire.

- If dust builds up on the power plug, the resulting humidity can damage the insulation.
- If not using the projector for an extended period of time, pull the power plug out from the wall outlet.
- Pull the power plug out from the wall outlet and wipe it with a dry cloth regularly.

### ON USE/INSTALLATION

Do not place the projector on soft materials such as carpets or sponge mats.

Doing so will cause the projector to overheat, which can cause burns, fire or damage to the projector.

# Do not set up the projector in humid or dusty places or in places where the projector may come into contact with oily smoke or steam.

Using the projector under such conditions will result in fire, electric shocks or deterioration of components. Oil may also distort the plastic and the projector could fall such as when mounted on the ceiling.

# Do not install this projector in a place which is not strong enough to take the full weight of the projector or on top of a surface which is sloped or unstable.

Failure to observe this will cause projector to fall down or tip over the projector, and severe injury or damage could result.

### WARNING:

### Do not cover the air intake/exhaust ports or place anything within 500 mm (19-11/16") of them.

Doing so will cause the projector to overheat, which can cause fire or damage to the projector.

- Do not place the projector in narrow, badly ventilated places.
- Do not place the projector on cloth or papers, as these materials could be drawn into the air intake port.

### Do not look at or place your skin into the light emitted from the lens while the projector is being used. Do not enter the projection luminous flux using an optical device (such as magnifier or mirror). Doing so can cause burns or loss of sight.

- Strong light is emitted from the projector's lens. Do not look at or place your hands directly into this light.
- Be especially careful not to let young children look into the lens. In addition, turn off the power and switch off the main power when you are away from the projector.

### **Do not project an image with the lens cover of the projection lens (optional) attached.** Doing so can cause fire.

### Never attempt to remodel or disassemble the projector.

High voltages can cause fire or electric shocks.

• For any inspection, adjustment and repair work, please contact an Authorized Service Center.

### Do not touch the top surface of the projector during use.

Doing so may result in burns, as the top surface is hot during use and for a while after use.

# Do not allow metal objects, flammable objects, or liquids to enter inside of the projector. Do not allow the projector to get wet.

Doing so may cause short circuits or overheating, and result in fire, electric shock, or malfunction of the projector.

- Do not place containers of liquid or metal objects near the projector.
- If liquid enters inside of the projector, consult your dealer.
- Particular attention must be paid to children.

# Installation work such as mounting the projector on the ceiling should only be carried out by a qualified technician.

If installation is not carried out and secured correctly, it can cause injury or accidents, such as electric shocks.

### ACCESSORIES

### Do not use or handle the batteries improperly, and refer to the following.

Failure to observe this will cause burns, batteries to leak, overheat, explode or catch fire.

- Do not use unspecified batteries.
- Do not charge dry cell batteries.
- Do not disassemble dry cell batteries.
- Do not heat the batteries or place them into water or fire.
- Do not allow the + and terminals of the batteries to come into contact with metallic objects such as necklaces or hairpins.
- Do not store or carry batteries together with metallic objects.
- Store the batteries in a plastic bag and keep them away from metallic objects.
- Make sure the polarities (+ and –) are correct when inserting the batteries.
- Do not use a new battery together with an old battery or mix different types of batteries.
- Do not use batteries with the outer cover peeling away or removed.

### If the battery fluid leaks, do not touch it with bare hands, and take the following measures if necessary.

- Battery fluid on your skin or clothing could result in skin inflammation or injury. Rinse with clean water and seek medical advice immediately.
- Battery fluid coming in contact with your eyes could result in loss of sight.
  - In this case, do not rub your eyes. Rinse with clean water and seek medical advice immediately.

# Do not allow children to reach the lens fixing screw, the lens hood screws, and the knurled head screws.

Accidentally swallowing them can cause physical harm.

• If swallowed, seek medical advice immediately.

### Remove the depleted batteries from the remote control promptly.

• Leaving them in the unit may result in fluid leakage, overheating, or explosion of the batteries.

### CAUTION:

### POWER

### When disconnecting the power cord, be sure to hold the power plug and power connector.

If the power cord itself is pulled, the lead will become damaged, and fire, short-circuits or serious electric shocks will result.

# When not using the projector for an extended period of time, disconnect the power plug from the wall outlet.

Failure to do so may result in fire or electric shock.

# Before replacing the projection lens, be sure to turn off the power and disconnect the power plug from the wall outlet.

- Unexpected projection of light may cause injury to eyes.
- Replacing the projection lens without removing the power plug may result in electric shock.

# Disconnect the power plug from the wall outlet before attaching or removing the Interface Board (optional), performing maintenance, and replacing the unit.

Failure to do so may result in electric shock.

### Do not remove the power connector (projector-side) while current is running.

Removing the power connector while current is running may result in fires caused by sparks.

### ON USE/INSTALLATION

### Do not place heavy objects on top of the projector.

Failure to observe this will cause the projector to become unbalanced and fall, which could result in damage or injury. The projector will be damaged or deformed.

### Do not put your weight on this projector.

You could fall or the projector could break, and injury will result.

• Be especially careful not to let young children stand or sit on the projector.

### Do not place the projector in extremely hot locations.

- Doing so will cause the outer casing or internal components to deteriorate, or result in fire.
- Take particular care in locations exposed to direct sunlight or near heaters.

### **Do not place your hands in the openings beside the optical lens, while shifting the lens.** Failure to observe this could cause injury.

**Do not install the projector in a location where salt pollution or corrosive gas may occur.** Doing so may result in falling due to corrosion. Also, it may result in malfunctions.

### Do not stand in front of the lens while the projector is being used.

Doing so can cause damage and burns to clothing.

• Strong light is emitted from the projector's lens.

### Do not place objects in front of the lens while the projector is being used.

Doing so can cause fire, damage to an object, or malfunction of the projector.

• Strong light is emitted from the projector's lens.

### The projector must be carried or installed by four or more people. Failure to do so may cause falling accidents.

### Always disconnect all cables before moving the projector.

Moving the projector with cables still attached can damage the cables, which will cause fire or electric shocks to occur.

### CAUTION:

### ACCESSORIES

# When not using the projector for an extended period of time, remove the batteries from the remote control.

Failure to observe this will cause the batteries to leak, overheat, catch fire or explode, which may result in fire or contamination of surrounding area.

### MAINTENANCE

### Do not attach the air filter unit while it is wet.

Doing so may result in electric shock or malfunctions.

• After you clean the air filter units, dry them thoroughly before reattaching them.

# Ask your dealer about cleaning inside the projector every 20 000 hours of usage as an estimated duration.


Continuous use while dust is accumulated inside the projector may result in fire.

• For cleaning fee, ask your dealer.


### To remove the battery

### **Remote Control Battery**

### 1. Press the guide and lift the cover.



2. Remove the batteries.



### Brazil Only Brasil Apenas

### Manuseio de baterias usadas




### BRASIL

Após o uso, as pilhas e/ou baterias deverão ser entregues ao estabelecimento comercial ou rede de assistência técnica autorizada.

Cobrir os terminais positivo (+) e negativo (-) com uma fita isolante adesiva, antes de depositar numa caixa destinada para o recolhimento. O contato entre partes metálicas pode causar vazamentos, gerar calor, romper a blindagem e produzir fogo. (Fig. 1)

Fig. 1 Como isolar os terminais




Não desmonte, não remova o invólucro, nem amasse a bateria. O gás liberado pela bateria pode irritar a garganta, danificar o lacre do invólucro ou o vazamento provocar calor, ruptura da blindagem e produzir fogo devido ao curto circuito dos terminais. Não incinere nem aqueça as baterias, elas não podem ficar expostas a temperaturas superiores a 100 °C (212 °F). O gás liberado pela bateria pode irritar a garganta, danificar o lacre do invólucro ou o vazamento provocar calor, ruptura da blindagem e produzir fogo devido ao curto circuito dos terminais.


Evite o contato com o liquido que vazar das baterias. Caso isto ocorra, lave bem a parte afetada com bastante água. Caso haja irritação, consulte um médico.

### Remoção das baterias

1. Pressione a guia e levante a tampa.



2. Remova as baterias.



### Trademarks

- SOLID SHINE is a trademark of Panasonic Corporation.
- Windows, Internet Explorer, and Microsoft Edge are registered trademarks or trademarks of Microsoft Corporation in the United States and other countries.
- Mac, macOS, and Safari are trademarks of Apple Inc., registered in the United States and other countries.
- PJLink™ is a registered trademark or pending trademark in Japan, the United States, and other countries and regions.
- DLP and the DLP logo are registered trademarks or trademarks of Texas Instruments.
- The terms HDMI and HDMI High-Definition Multimedia Interface, and the HDMI Logo are trademarks or registered trademarks of HDMI Licensing Administrator, Inc. in the United States and other countries.
- Crestron Connected, the Crestron Connected logo, Fusion RV, Crestron RoomView, and RoomView are either trademarks or registered trademarks of Crestron Electronics, Inc. in the United States and/or other countries.
- HDBaseT™ is a trademark of HDBaseT Alliance.
- Art-Net™ Designed by and Copyright Artistic Licence Holdings Ltd
- DisplayPort™ is a trademark owned by the Video Electronics Standards Association (VESA®) in the United States and other countries.
- Adobe, Adobe Flash Player, and Adobe Reader are trademarks or registered trademarks of Adobe Systems Inc. in the United States and/or other countries.
- Some of the fonts used in the on-screen menu are Ricoh bitmap fonts, which are manufactured and sold by Ricoh Company, Ltd.
- All other names, company names, and product names mentioned in this manual are trademarks or registered trademarks of their respective owners.

Please note that the <sup>®</sup> and <sup>™</sup> symbols are not specified in this manual.

### Illustrations in this manual

- Illustrations of the projector, screen, and other parts may vary from the actual product.
- Illustrations of the projector with the power cord attached are only examples. The shape of the supplied power cords varies depending on the country where you purchased the product.

### Reference pages

Reference pages in this manual are indicated as (
 page 00).

### Term

• In this manual, the "Wireless/wired remote control unit" accessory is referred to as "Remote control".

### Features of the Projector

### High picture quality

- In addition to high luminance exceeding 26 000 Im and high contrast of 20 000:1\*1, high-density image exceeding 4K is realized with the unique QUAD PIXEL DRIVE technology, providing a high realistic sensation image.
- \*1 When [DYNAMIC CONTRAST] is set to [3]

### Easy and highly flexible setup

In addition to the DIGITAL LINK support, Art-Net support, and abundant lineup of optional lenses, application to wide range of usage is possible with support of all 360° direction projection utilizing the characteristics of solid-state light source. Furthermore, the projector is equipped with the slots for mounting the Interface Boards, providing the flexibility to support various signal input structures.

### Long life and high reliability

The maintenance cost for long-term operation is reduced by the unique light source cooling control technology and improvement of the dust resistance. Also, it will contribute to the stable operation by implementation of the backup function that will continue the projection by switching to the backup input signal immediately even when the input signal is discontinued, in addition to adopting solid-state light source which has long life. Quick Steps

For details, refer to the corresponding pages.

- Set up the projector.
   (⇒ page 39)
- 2. Attach the projection lens (optional).(⇒ page 50)
- Connect with external devices.
   (⇒ page 53)
- 4. Connect the power cord.(⇒ page 62)
- 5. Switch on the projector.(⇒ page 64)
- 6. Make initial settings.
  (⇒ page 65)
  Set the lens type.
  - (⇒ page 77)
  - Execute the lens calibration.
  - (**⇒** page 77)
  - Take this step when you switch on the power for the first time after purchasing the projector.
- 7. Select the input signal.(⇒ page 73)
- Adjust the image.
   (⇒ page 75)

# Chapter 1 **Preparation**

This chapter describes things you need to know or check before using the projector.

### **Precautions for use**

### Cautions when transporting

- Transport the projector with four or more people. Failure to do so may drop the projector, which may result in damage or deformation of the projector, or injury.
- When transporting the projector, hold it securely by its front side and back side handles and avoid excessive vibration and impacts. Failure to do so may cause a failure due to the damaged internal components.
- Do not transport the projector with the adjustable feet extended. Doing so may damage the adjustable feet.

### **Cautions when installing**

### Do not set up the projector outdoors.

The projector is designed for indoor use only.

### Do not set up the projector in the following locations.

- Places where vibration and impacts occur such as in a car or vehicle: Doing so may cause damage to internal components or malfunction.
- Location close to sea or where corrosive gas may occur: The projector may fall due to corrosion. Also, failure to do so may shorten the life of the components and result in malfunctions.
- Near the exhaust of an air conditioner: Depending on the conditions of use, the screen may fluctuate in rare cases due to the heated air from the air exhaust port or the hot or cooled air. Make sure that the exhaust from the projector or other equipment, or the air from the air conditioner does not blow toward the front of the projector.
- Places with sharp temperature fluctuations such as near lights (studio lamps): Doing so may shorten the life of the light source, or result in deformation of the projector due to heat, which may cause malfunctions. Follow the operating environment temperature of the projector.
- Near high-voltage power lines or near motors: Doing so may interfere with the operation of the projector.
- Places where there is high-power laser equipment: Directing a laser beam onto the projection lens surface causes damage to the DLP chips.

### Ask a qualified technician or your dealer to do installation work such as mounting the projector on the ceiling, including installation work that uses eyebolts.

To ensure projector performance and security, ask a qualified technician or your dealer when installing the projector in a method other than the floor installation or when installing the projector in a high place.

# Ask a qualified technician or your dealer to install the cable wiring for DIGITAL LINK connection.

Image and sound may be disrupted if cable transmission characteristics cannot be obtained due to inadequate installation.

### The projector may not work properly due to strong radio wave from the broadcast station or the radio.

If there is any facility or equipment which outputs strong radio waves near the installation location, install the projector at a location sufficiently far from the source of the radio waves. Or, wrap the LAN cable connected to the <DIGITAL LINK/LAN> terminal using a piece of metal foil or a metal pipe which is grounded at both ends.

### Focus adjustment

The high clarity projection lens is thermally affected by the light from the light source, making the focus unstable in the period just after switching on the power.

It is recommended to perform the focus adjustment after 30 minutes have elapsed with the focus test pattern displayed. For details of the test pattern, refer to "[TEST PATTERN] menu" (→ page 185).

### Do not install the projector at an altitude of 4 200 m (13 780') or higher above sea level.

# Do not use the projector in a location that the ambient temperature exceeds 45 °C (113 °F).


Using the projector in a location that the altitude is too high or the ambient temperature is too high may reduce the life of the components or result in malfunctions.

The upper limit of the operating environment temperature differs depending on the altitude or the setting of the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING] ( $\Rightarrow$  page 161)  $\rightarrow$  [OPERATING MODE].

	Setting for [OPERATING MODE]		
Altitude above sea level	[HIGH], [NORMAL], [USER1], [USER2], [USER3]	[LONG LIFE1], [LONG LIFE2], [LONG LIFE3]	
Altitude of 0 m (0') or higher to lower than 1 400 m (4 593')	0 °C (32 °F) to 45 °C (113 °F)		
Altitude of 1 400 m (4 593') or higher to lower than 2 700 m (8 858')		0 °C (32 °F) to 40 °C (104 °F)	
Altitude of 2 700 m (8 858') or higher to lower than 4 200 m (13 780')	0 °C (32 °F) to 40 °C (104 °F)	The projector cannot be used.	

When the Smoke Cut Filter is used, the operating environment temperature should be between 0  $^{\circ}$ C (32  $^{\circ}$ F) and 40  $^{\circ}$ C (104  $^{\circ}$ F) regardless of the [OPERATING MODE] setting. It cannot be used at an altitude of 1 400 m (4 593') or higher above sea level.

### ■ Projection in all 360° direction is possible.



360° vertically

360° horizontally

360° tilted (combination of vertical and horizontal)

# The geometric adjustment is disabled when projecting an image in simultaneous format.

The geometric adjustment function cannot be used when the video signal in simultaneous format is input. When installing the projector, follow the instructions below so that distortion does not occur in the projected image.

- Use a flat screen.
- Install the projector so that the front side of the projector is parallel to the screen.
- Install the projector so that the image can be projected within the lens shift adjustment range.

### Cautions when setting up the projector

- Install the projector in a place or with a mount that can sufficiently tolerate the weight. The position of the
  projected image may shift if the strength is not sufficient.
- Use the adjustable feet only for the floor standing installation and for adjusting the angle. Using them for other purposes may damage the projector.
- The adjustable feet can be removed if not needed in the installation. However, do not use the screw holes where the adjustable feet were removed to fix the projector to a mount. Also, do not insert any screws other than the eyebolts for the installation work into the screw holes of the adjustable feet. Do not insert the removed adjustable feet into other M10 screw holes.
- Do not fix the projector to a mount with the screw holes for eyebolts (4 locations on each side) on the top side, right and left sides, and back side.


### 18 - ENGLISH

• When installing and using the projector in a method other than the floor installation using the adjustable feet, remove the adjustable feet (4 locations) and use the six screw holes to fix the projector to a mount (as shown in the figure).

For the screws to fix the projector, use commercially available ISO 898-1 standard screws (made of carbon steel or alloy steel).

(Screw diameter: M10, thread engagement length: 18 mm (23/32") or more, tapping depth inside the projector: 30 mm (1-3/16"))


 Use a torque screwdriver or Allen torque wrench to tighten the fixing screws to their specified tightening torques. Do not use electric screwdrivers or impact screwdrivers. (Screw tightening torque: 20 ± 1 N·m)



### Position of screw holes to fix projector and adjustable feet


- Do not stack three or more projectors.
- Do not use the projector supporting it by the top.
- Do not block the ventilation ports (intake and exhaust) of the projector.

 Prevent hot and cool air from the air conditioning system to blow directly to the ventilation ports (intake and exhaust) of the projector.





When the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached




100 mm (3-15/16") or longer

- Do not install the projector in a confined space.
   When installing the projector in a confined space, provide air conditioning or ventilation separately. Exhaust heat may accumulate when the ventilation is not enough, triggering the protection circuit of the projector.
- Panasonic takes no responsibility for any damage to the product caused by an inappropriate choice of location for installing the projector, even if the warranty period of the product has not expired.

### Cautions when conducting lifting work

- Use the eyebolts only when temporarily lifting the projector such as when installing the projector.
- Use ISO 3266 standard eyebolts (commercially available) for the M10 with an underhead length of 18 mm
- (23/32") to 30 mm (1-3/16"). Also use ISO standard parts for other components to lift the projector (wires, etc.).
- Lift the projector using the eyebolts attached to 4 locations on the same plane.
- Set the lifting angle to 60° or more.



### Security

When using this product, take safety measures against the following incidents.

- Personal information being leaked via this product
- Unauthorized operation of this product by a malicious third party
- Interfering or stopping of this product by a malicious third party

Take sufficient security measures.

- Make your password difficult to guess as much as possible.
- Change your password periodically. A password can be set in the [SECURITY] menu → [SECURITY PASSWORD CHANGE].
- Panasonic Corporation or its affiliate companies will never ask for your password directly. Do not divulge your
  password in case you receive such inquiries.
- The connecting network must be secured by a firewall, etc.

• Set a password for the web control and restrict the users who can log in. A password for the web control can be set in the [Change password] page of the web control screen.

### **QUAD PIXEL DRIVE**

"QUAD PIXEL DRIVE" is a technology unique to Panasonic that will enhance the resolution of the projected image with the signal processing for the high resolution of up to 5 120 x 3 200 dots and quadrupling the resolution by shifting the image pixels in horizontal and vertical directions.

A high-density "4K+" image exceeding 4K is displayed by this QUAD PIXEL DRIVE technology.

### **DIGITAL LINK**

"DIGITAL LINK" is a technology to transmit the video, audio, Ethernet, and serial control signals using a twisted pair cable by adding unique functions by Panasonic to the HDBaseT™ communication standard formulated by HDBaseT Alliance.

This projector supports the optional Panasonic DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) and peripheral devices by other manufacturers (twisted-pair-cable transmitters such as the "XTP transmitter" of Extron Electronics) that use the same HDBaseT<sup>TM</sup> standard. For the devices of other manufacturers that the operation has been verified with this projector, visit the Panasonic website (https:// panasonic.net/cns/projector/). Note that the verification for devices of other manufacturers has been made for the items set by Panasonic Corporation, and not all the operations have been verified. For operation or performance problems caused by the devices of other manufacturers, contact the respective manufacturers. This projector does not support audio transmission because it is not equipped with audio function.

### **Art-Net**

"Art-Net" is an Ethernet communication protocol based on the TCP/IP protocol.

By using the DMX controller and the application software, illumination and stage system can be controlled. Art-Net is made based on DMX512 communication protocol.

### **Early Warning Software**

The projector supports "Early Warning Software", which monitors the status of the display (projector or flat panel display) and the peripheral devices inside an intranet, and notifies of abnormality of such equipment and detects signs of possible abnormality. Also, maintenance can be performed in advance, because this software gives notification of approximate time to replace consumables of the display, to clean each part of the display, and to replace the components of the display.

Depending on the type of license, the number of displays that can be registered for monitoring varies. Limited to the first 90 days after installation in a computer, it is possible to register up to 2048 units of displays free of charge. Download the software from the Panasonic website (https://panasonic.net/cns/projector/pass/). It is necessary to register and login to PASS<sup>\*1</sup> to download.

\*1 PASS: Panasonic Professional Display and Projector Technical Support Website

Visit the Panasonic website (https://panasonic.net/cns/projector/pass/) for details.

### Storing

To store the projector, store in a dry room.

### Disposal

To dispose of the product, ask your local authorities or dealer for correct methods of disposal. Also, dispose of the product without disassembling.

### **Cautions on use**

### To get a good picture quality

In order to view a beautiful image in higher contrast, prepare an appropriate environment. Draw curtains or blinds over windows and turn off any lights near the screen to prevent outside light or light from indoor lamps from shining onto the screen.

### Do not touch the surface of the projection lens with your bare hands.

If the surface of the projection lens becomes dirty from fingerprints or anything else, this will be magnified and projected onto the screen.

Attach the supplied lens cover to the optional projection lens when not using the projector.

### 22 - ENGLISH

### DLP chips

- The DLP chips are precision-made. Note that in rare cases, pixels of high precision could be missing or always lit. Such a phenomenon does not indicate malfunction.
- Directing a high-power laser beam onto the projection lens surface can damage the DLP chips.

### Do not move the projector or subject it to vibration or impact while it is operating.

Doing so may shorten the life of the built-in motor.

### Light source

The light source of the projector uses lasers, and has the following characteristics.

- Depending on the operating environment temperature, the luminance of the light source will decrease. The higher the temperature becomes, the more the luminance of the light source decreases.
- The luminance of the light source will decrease by duration of usage.

If brightness is noticeably reduced and the light source does not turn on, ask your dealer to clean inside the projector or replace the light source unit.

### Computer and external device connections

When connecting a computer or an external device, read this manual carefully regarding the use of power cords and shielded cables as well.

### Slot


This projector is equipped with two SLOT NX-specification slots.

There are four SDI input terminals and one DIGITAL LINK input terminal equipped on this projector as the standard video input terminals. The input for HDMI, DVI-D, and SDI can be added by installing the optional Interface Board in the slot.

"SLOT NX" is a name of the slot unique to Panasonic supporting the signal input for the 4K image.

### Accessories

Make sure that the following accessories are provided with your projector. Numbers enclosed in < > show the number of accessories.



24 - ENGLISH

### Attention

- After unpacking the projector, discard the power cord cap and packaging material properly.
- Do not use the supplied power cord for devices other than this projector.
- For missing accessories, consult your dealer.
- Store small parts in an appropriate manner, and keep them away from small children.

### Note

• The lens hood needs to be mounted to the projector when an interchangeable projection lens is used under the condition that throw ratio is greater than 3.0 in the North America region. Always ask a qualified technician or your dealer to mount the lens hood.

The throw ratio described here is a value calculated by dividing the actual projection distance by the projected image width. The lens hood is assembled and mounted to the projector using the following supplied components.

Lens hood 1, Lens hood 2, Lens hood mounting plate 1, Lens hood mounting plate 2, Lens hood screws, Knurled head screws

For the assembly and attachment, refer to the separate document "Mounting the lens hood". The components and document of the lens hood may not be supplied depending on the country or region where you purchased the product.

- The type and number of the supplied power cords vary depending on the country or region where you purchased the product.
- The air filter unit is already attached to the projector at the time of purchase. Four Replacement Filter Units (Model No.: ET-EMF330) are supplied.
- The model numbers of accessories are subject to change without prior notice.

### Contents of the supplied CD-ROM

The contents of the supplied CD-ROM are as follows.

Instruction/list (PDF)	Operating Instructions		
	Multi Monitoring & Control Software Operating Instructions		
	Logo Transfer Software Operating Instructions		
	List of Compatible Device Models	This is a list of projectors that are compatible with the software contained in the CD-ROM and their restrictions.	
Software	Multi Monitoring & Control Software (Windows)	This software allows you to monitor and control multiple displays (projector or flat panel display) connected to the LAN.	
	Logo Transfer Software (Windows)	This software allows you to transfer original images, such as company logos to be displayed when projection starts, to the projector.	

### Note

 The "List of Compatible Device Models" for the flat panel display compatible with the "Multi Monitoring & Control Software" can be downloaded from the Panasonic website (https://panasonic.net/cns/prodisplays/).

### **Optional accessories**

Optional accessories (product name)		Model No.
Projection lens	Zoom Lens	ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40
	Fixed-focus Lens	ET-D75LE50, ET-D75LE95
Stepping Motor Kit		ET-D75MKS10
Lens Fixed Attachment		ET-PLF10
Interface Board	Interface Board for HDMI 2 input	ET-MDNHM10
	Interface Board for DVI-D 2 input	ET-MDNDV10
	Interface Board for DisplayPort 2 input	ET-MDNDP10
	3G-SDI Terminal Board with Audio	TY-TBN03G
	Interface Board for 12G-SDI	ET-MDN12G10
	Interface Board for 12G-SDI Optical	ET-MDNFB10
Replacement Filter Unit		ET-EMF330
Long Life Filter Unit		ET-EMFU330
Smoke Cut Filter		ET-SFR330
Early Warning Software (Basic license/3-year license)		ET-SWA100 Series*1
Upgrade Kit		ET-UK20
Auto Screen Adjustment Upgrade Kit		ET-CUK10
Auto Screen Adjustment Upgrade Kit (PC)		ET-CUK10P
Digital Interface Box		ET-YFB100G
DIGITAL LINK Switcher		ET-YFB200G

\*1 The suffix of the Model No. differs according to the license type.

### Note

 The Fixed-focus Lens (Model No.: ET-D75LE90) (production discontinued) can also be used. However, considering the focus quality, use it by setting the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] to 77.0 % or less. The luminance when [LIGHT OUTPUT] is set to 77.0 % is 20 000 lm (approximate).

• The Stepping Motor Kit (Model No.:ET-D75MKS10) is a product to replace the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40) with the stepping motor unit. For how to replace the motor of the Zoom Lens, refer to the Operating Instructions of the Stepping Motor Kit.

• To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (➡ page 35).


- When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware. For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (
  page 35).
- For detailed operations and compatible signals when the Interface Board for 12G-SDI Optical (Model No.: ET-MDNFB10) is installed in the projector, refer to the "Operating Instructions Functional Manual" (PDF) of the Interface Board for 12G-SDI Optical. For downloading the "Operating Instructions Functional Manual", visit the following URL. https://panasonic.net/cns/projector/
- The expansion function by applying the optional Upgrade Kit (Model No.: ET-UK20) cannot be used when the video signal in simultaneous format is input.
- For details on how to attach the Long Life Filter Unit (Model No.: ET-EMFU330), refer to "Attaching the Long Life Filter Unit (optional)" (→ page 281).
- For details on how to attach the Smoke Cut Filter (Model No.: ET-SFR330), refer to "Attaching the Smoke Cut Filter Unit (optional)" (→ page 284).
- The model numbers of optional accessories are subject to change without prior notice.

• The optional accessories compatible with the projector may be added or changed without prior notice. The optional accessories described in this document are as of March 2020. However, the projection lenses released after September 2018 are not described.

For the latest information, visit the Panasonic website (https://panasonic.net/cns/projector/).

# About your projector

### Remote control



<AUTO SETUP> button 6

> Automatically adjusts the image display position while projecting the image.

[PROGRESS] is displayed while in automatic adjustment. (> page 84)

<ASPECT> button 7

1

2

3

5

Switches the aspect ratio of the image. (→ page 84)

Number (<0> - <9>) buttons 8

> Used for entering an ID number or a password in a multiple projector environment.

### <STATUS> button

Displays the projector information.

### 10 <LIGHT> button

Pressing this button lights up the remote control buttons. The lights will go off when the remote control operation goes idle for 10 seconds

#### <INPUT MENU> button 11

Displays the input selection screen. (
page 75)

12 Input selection buttons (<DIGITAL LINK>, <DVI-D>, <HDMI>, <DISPLAYPORT>, <SLOT 1>, <SLOT 2>, <SDI>) Switches the input signal to project. (
page 73) <DVI-D> button, <HDMI> button, <DISPLAYPORT> button, <SLOT 1> button, and <SLOT 2> button can be used when the optional Interface Board equipped with corresponding input is Following buttons are not used with this projector. <RGB1> button, <RGB2> button, <VIDEO> button, <S-VIDEO

Used to temporarily turn off the image. (→ page 83)

- Adjusts the focus, zoom, and lens shift. (+ page 75)

### 16 <FUNCTION> button

Assigns a frequently used operation as a shortcut button. (> page 84)

17 <DEFAULT> button

Resets the content of the sub-menu to the factory default. (> page 89)

18 <ID SET> button

Sets the ID number of the remote control in a multiple projector environment. (⇒ page 36)

### 19 <ID ALL> button

Used to simultaneously control all the projectors with a single remote control in a multiple projector environment. (> page 36)

### 20 <LOCK> button

Used to prevent unintended operation by careless pressing of the buttons and prevent draining the remote control batteries. Operation of each button on the remote control is disabled by sliding the <LOCK> button toward the arrow.

### 21 Remote control signal transmitter

### 22 Remote control wired terminal

This is a terminal used to connect to the projector via a cable when the remote control is used as a wired remote control. (⇒ page 37)

### 28 - ENGLISH

### 23 Strap hole

### Attention

- Do not drop the remote control.
- Avoid contact with liquids or moisture.
- Do not attempt to modify or disassemble the remote control.
- · Do not swing the remote control holding onto the strap when a strap is attached.
- Observe the following instructions that are indicated on the caution label at the back of the remote control:
  - Do not use old battery with new one
  - Do not use batteries other than the type specified.
  - Be sure the batteries are inserted properly.
  - For other instructions, read the instructions related to batteries that are described in "Read this first!".




Caution label at the back of the remote control

### Note

- When operating the remote control by directly pointing the remote control signal receiver of the projector, operate the remote control at a distance approx. 30 m (98'5") or shorter from the remote control signal receiver. The remote control can control at angles of up to ±15° vertically and ±30° horizontally, but the effective control range may be reduced.
- If there are any obstacles between the remote control and the remote control signal receiver, the remote control may not operate properly.
- The signal will be reflected off the screen. However, the operating range may be limited from light reflection loss due to the screen material.
- If the remote control signal receiver directly receives strong light, such as fluorescent light, the remote control may not operate properly. Use it in a place distant from the light source.
- The power indicator <ON (G)/STANDBY (R)> will blink if the projector receives a remote control signal.

### **Projector body**




- 1 Remote control signal receiver (front)
- 2 Power indicator <ON (G)/STANDBY (R)> Indicates the status of the power.
- 3 Light source indicator <LIGHT1> Indicates the status of light source 1.

- 4 Light source indicator <LIGHT2> Indicates the status of light source 2.
- 5 Temperature indicator <TEMP> Indicates the internal temperature status.
- 6 Filter indicator <FILTER> Indicates the status of the air filter unit.

- 7 Adjustable feet
- Adjusts the projection angle.
- 8 Air intake port9 Screw holes for evebo
- 9 Screw holes for eyebolts Screw diameter: M10, tapping depth inside the projector: 35 mm (1-3/8")
- **10 Air filter cover** The air filter unit is inside.
- 11 Remote control signal receiver (rear)
- 12 Air exhaust port

### ■ Тор





: Projection direction

### WARNING

Do not touch the top surface of the projector during use.


 Doing so may result in burns, as the top surface is hot during use and for a while after use.

### Attention

· Do not block the ventilation ports (intake and exhaust) of the projector.

- 13 Control panel (⇒ page 31)
- 14 Connecting terminals (⇒ page 32)
- 15 Security slot
  - This security slot is compatible with the Kensington security cables.
- 16 <AC IN> terminal Connect the supplied power cord.
- 17 <MAIN POWER> switch Turns on/off the main power.

### Bottom



### 1 Screw holes for eyebolts


Screw diameter: M10, tapping depth inside the projector: 35 mm (1-3/8")

### 2 Handle

Hold the handle with your hand when carrying the projector.

3 Screw holes to fix the projector Screw diameter: M10, tapping depth inside the projector: 30 mm (1-3/16")

### Control panel



### 1 Power on <|> button

Sets the projector to projection mode when the <MAIN POWER> switch on the projector is set to <ON> and the power is turned off (standby mode).

2 Power standby <⊍> button Sets the projector to the state where the projector is turned off (standby mode) when the <MAIN POWER> switch on the projector is set to <ON> and in projection mode.

### 3 Input selection buttons (<SDI 1/2>, <SDI 3/4>, <DIGITAL LINK>, <SLOT 1>, <SLOT 2>)

Switches the input signal to project. (→ page 73) <SLOT 1> button and <SLOT 2> button can be used when the optional Interface Board is installed in the slot on the projector.

### 4 Input selection terminal indicator

Indicator that shows the selected input terminal. This indicator lights up when a video signal is being input to the selected terminal, and blinks when there is no video signal being input.

### 5 <INPUT MENU> button

Displays the input selection screen. ( page 75) The indicator of the button is lit while this button is pressed.

### 6 <AUTO SETUP> button

Automatically adjusts the image display position while the image is projected. [PROGRESS] is displayed while in automatic adjustment. (
page 84)

### 7 <MENU> button

Displays or hides the main menu. (→ page 88) Returns to the previous menu when a sub-menu is displayed. If you press the <MENU> button on the control panel for at least three seconds while the on-screen display is off (hidden), the on-screen display is turned on.

### 8 <LENS> button

Adjusts the focus, zoom, and lens shift.

### 9 <ENTER> button

Determines and executes an item in the menu screen.

### 10 <SHUTTER> button

Used to temporarily turn off the image. (→ page 83)

### 11 ▲▼◀▶ buttons

Used to select items in the menu screen, change settings, and adjust levels.

Also used to enter a password in [SECURITY] or enter characters.

### 12 <LIGHT> switch


This is a light switch for the connecting terminals and control panel.

### 13 Self-diagnosis display

Automatically displays the value of the input supply voltage, or the alphanumeric symbols of errors or warnings when they occur.

(> pages 86, 235)

### Connecting terminals



### 1 <DC OUT 1> terminal/<DC OUT 2> terminal

This is the USB terminal dedicated for power supply. (DC 5 V, maximum 900 mA)  $\,$ 

Use this terminal when a power supply is required to wireless display adapters and wireless LAN Ethernet converters, etc.

- 2 <REMOTE 1 IN> terminal/<REMOTE 1 OUT> terminal These are terminals to connect the remote control for serial control in a multiple projector environment.
- 3 <REMOTE 2 IN> terminal This is a terminal to remotely control the projector using the external control circuit.
- 4 **<SERIAL IN> terminal** This is the RS-232C compatible terminal to externally control the projector by connecting a computer.
- 5 <SERIAL OUT> terminal This is a terminal to output the signal connected to the <SERIAL IN> terminal.

### 6 <MULTI PROJECTOR SYNC IN> terminal/<MULTI PROJECTOR SYNC OUT> terminal This terminal is used to connect multiple projectors when

In sterminal is used to connect multiple projectors when balancing the contrast as a combined screen or synchronizing the effects using the shutter function including the fade in/fade out with a system using multiple projectors.

7 Slots (<SLOT 1>, <SLOT 2>) There are SLOT NX-specification slots to install the optional Interface Board internally.

### 8 Slot cover

9

#### <DIGITAL LINK/LAN> terminal This is the LAN terminal to connect to the network. This is also used when connecting a video signal transmission device via the LAN terminal.

10 <SDI IN 1> terminal/<SDI IN 2> terminal/<SDI IN 3> terminal/<SDI IN 4> terminal These are terminals to input SDI signals.

### Attention

- When a LAN cable is directly connected to the projector, the network connection must be made indoors.
- When the [PROJECTOR SETUP] menu → [STANDBY MODE] is set to [NORMAL], power can be supplied by using the <DC OUT 1> terminal or the <DC OUT 2> terminal even while the projector is in standby mode. If [ECO] is set, power cannot be supplied in standby mode.

### Names and functions of the Interface Board (optional)


This projector is equipped with two SLOT NX-specification slots.

There are four SDI input terminals and one DIGITAL LINK input terminal equipped on this projector as the standard video input terminals. The input for HDMI, DVI-D, and SDI can be added by installing the optional Interface Board in the slot.

The terminal name of the optional Interface Board is described with different terminal name in this document when it is installed in <SLOT 1> and when it is installed in <SLOT 2>. Refer to following information for details.

### Interface Board for HDMI 2 input (Model No.: ET-MDNHM10)

This board supports the HDMI signal.



2

- <HDMI IN 1> terminal (when installed in <SLOT 1>), <HDMI IN 3> terminal (when installed in <SLOT 2>) This is a terminal to input HDMI signal.
- <HDMI IN 2> terminal (when installed in <SLOT 1>), <HDMI IN 4> terminal (when installed in <SLOT 2>) This is a terminal to input HDMI signal.

3 Handle


### Note

• When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).

### Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10)

This board supports the DVI-D signal.




- 1 <DVI-D IN 1> terminal (when installed in <SLOT 1>), <DVI-D IN 3> terminal (when installed in <SLOT 2>) This is a terminal to input DVI-D signal.
- 2 <DVI-D IN 2> terminal (when installed in <SLOT 1>), <DVI-D IN 4> terminal (when installed in <SLOT 2>) This is a terminal to input DVI-D signal.

### 3 Handle

### 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G)

This board supports the SD-SDI signal, HD-SDI signal, and 3G-SDI signal.



- 1 <3G-SDI 2 OUT> terminal (when installed in <SLOT 1>), <3G-SDI 4 OUT> terminal (when installed in <SLOT 2>) This is an active through terminal to output the SDI signal input to the <3G-SDI 2 IN> terminal/<3G-SDI 4 IN> terminal of this board.
- 2 <3G-SDI 2 IN> terminal (when installed in <SLOT 1>), <3G-SDI 4 IN> terminal (when installed in <SLOT 2>) This is a terminal to input SDI signal.
- 3 <3G-SDI 1 OUT> terminal (when installed in <SLOT 1>), <3G-SDI 3 OUT> terminal (when installed in <SLOT 2>) This is an active through terminal to output the SDI signal input to the <3G-SDI 1 IN> terminal/<3G-SDI 3 IN> terminal of this board.
- 4 <3G-SDI 1 IN> terminal (when installed in <SLOT 1>), <3G-SDI 3 IN> terminal (when installed in <SLOT 2>) This is a terminal to input SDI signal.
- 5 Handle


### Note

- This projector does not support audio output because it is not equipped with audio function. However, when SDI signal with audio is input to the <3G-SDI 1 IN>/<3G-SDI 2 IN>/<3G-SDI 3 IN>/<3G-SDI 4 IN> terminal, a signal with audio is output from the <3G-SDI 1 OUT>/<3G-SDI 2 OUT>/<3G-SDI 3 OUT>/<3G-SDI 4 OUT> terminal.
- To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Confirm the firmware version of the 3G-SDI Terminal Board with Audio when it does not operate after installing to the projector.

Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00. For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" ( $\Rightarrow$  page 35).

### Interface Board for 12G-SDI (Model No.: ET-MDN12G10)

This board supports the SD-SDI signal, HD-SDI signal, 3G-SDI signal, 6G-SDI signal, and 12G-SDI signal.



### 1 <SDI 1 IN> terminal

This is a terminal to input SDI signal (SD-SDI/ HD-SDI/3G-SDI/6G-SDI/12G-SDI).

2 <SDI 2 IN/1 OUT> terminal

This is a terminal to input SDI signal (SD-SDI/HD-SDI/3G-SDI). This is also an active through terminal to output the SDI signal (SD-SDI/HD-SDI/3G-SDI/6G-SDI/12G-SDI) input to the <SDI 1 IN> terminal of this board.

### 3 <SDI 3 IN> terminal This is a terminal to input SDI signal (SD-SDI/

HD-SDI/3G-SDI/6G-SDI/12G-SDI).

#### <SDI 4 IN/3 OUT> terminal This is a terminal to input SDI signal (SD-SDI/HD-SDI/3G-SDI). This is also an active through terminal to output the SDI signal (SD-SDI/HD-SDI/3G-SDI/6G-SDI/12G-SDI) input to the <SDI 3 IN> terminal of this board.


5 Handle

### Note

- The <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal do not support the input of the 6G-SDI signal or the 12G-SDI signal.
- To use the <SDI 2 IN/1 OUT> terminal or the <SDI 4 IN/3 OUT> terminal as an output terminal, set the [DISPLAY OPTION] menu → [SLOT IN] → [SDI MODE] to [OUTPUT].
- When the projector is in standby mode, a signal is not output from the <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal.
- Install this board in either <SLOT 1> or <SLOT 2>. When these boards are installed in both <SLOT 1> and <SLOT 2>, only the board installed in <SLOT 1> can be used.

### Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10)

This board supports the DisplayPort signal.




- 1 <DisplayPort IN 1> terminal (when installed in <SLOT 1>), <DisplayPort IN 3> terminal (when installed in <SLOT 2>) This is a terminal to input DisplayPort signal.
- 2 <DisplayPort IN 2> terminal (when installed in <SLOT 1>), <DisplayPort IN 4> terminal (when installed in <SLOT 2>) This is a terminal to input DisplayPort signal.
- 3 Handle

### How to confirm the firmware version of the Interface Board (optional)

### ■ Interface Board for HDMI 2 input (Model No.: ET-MDNHM10)

The Interface Board for HDMI 2 input with the firmware version 2.00 or later has the version displayed on the product.


The firmware version can also be confirmed in the **[STATUS]** screen. ( page 177)



### ■ 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G)


The 3G-SDI Terminal Board with Audio with the firmware version 2.00 or later has the version displayed on the product.

The firmware version can also be confirmed in the **[STATUS]** screen. ( page 177)



### **Preparing the remote control**

### Inserting and removing the batteries



- 1) Open the cover. (Fig. 1)
- 2) Insert the batteries and close the cover (insert the 🖨 side first). (Fig. 2)
  - When removing the batteries, perform the steps in reverse order.

### When using the multiple projectors

When you use the multiple projectors together, you can operate all the projectors simultaneously or each projector individually using single remote control, if a unique ID number is assigned to each projector.

When using the projectors by setting the ID numbers, set the ID number of the projector body after initial settings have been completed. Then, set the ID number of the remote control. For initial settings, refer to "When the initial setting screen is displayed" ( $\Rightarrow$  page 65).

The factory default ID number of the projector (projector body and remote control) is set to [ALL], so you can use it as it is. Set the ID numbers of the projector body and remote control as necessary.

For details on setting the ID number of the remote control, refer to "Setting ID number of the remote control" (→ page 86).


### Note

• Set the ID number of the projector body from the [PROJECTOR SETUP] menu → [PROJECTOR ID].

## Connecting the remote control to the projector with a cable

If you control the multiple projectors with a single remote control, use commercially available M3 stereo mini jack cables to connect to the <REMOTE 1 IN>/<REMOTE 1 OUT> terminals of the projectors.

The remote control is effective even in places where an obstacle stands in the light path or where devices are susceptible to outside light.



#### Connecting terminals

#### Attention

• Use a cable that is 15 m (49'3") or shorter, with 2 core shielded. The remote control may not operate when the length of the cable exceeds 15 m (49'3") or when the shielding of the cable is inadequate.

# Chapter 2 Getting Started

This chapter describes things you need to do before using the projector such as the setup and connections.

## Setting up

## Usable outlet

This projector supports AC 100 V to AC 120 V, and AC 200 V to AC 240 V as the power supply. A grounded outlet supporting 30 A is required when using the projector with AC 200 V to AC 240 V. A grounded outlet supporting 15 A is required when using the projector with AC 100 V to AC 120 V.

The shape of the usable outlet differs depending on the power supply. Following illustrations are examples.





2P/3W 30 A 250 V Clock position 6h



2P/3W 15 A 125 V

#### Attention

- Use the supplied power cord and ground at the outlet.
- Use the power cord matching the used power supply voltage and outlet shape.


#### Note


- The light output will decrease to approximately 1/3 when using the projector with AC 100 V to AC 120 V.
- The supplied power cords vary depending on the country or region where you purchased the product.

### Installation mode

The installation modes of the projector are as follows. Set [FRONT/REAR]/[FLOOR/CEILING] in the [PROJECTOR SETUP] menu  $\rightarrow$  [PROJECTION METHOD] ( $\Rightarrow$  page 148) depending on the installation mode.

Setting on a desk/floor and proje	Acting forward	Setting on a desk/floor and projection (Using the translucent screen)	ecting from rear
Menu item	Setting value	Menu item	Setting value
[FRONT/REAR]	[FRONT]	[FRONT/REAR]	[REAR]
[FLOOR/CEILING]	[AUTO] or [FLOOR]	[FLOOR/CEILING]	[AUTO] or [FLOOR]






#### Note

- In the portrait setting, the on-screen menu is displayed sideways.
- To display the on-screen menu vertically, change the [OSD ROTATION] setting in the [DISPLAY OPTION] menu  $\rightarrow$  [ON-SCREEN DISPLAY] ( $\Rightarrow$  page 139).
- The projector has a built-in angle sensor. The attitude of the projector is automatically detected by setting [FLOOR/CEILING] to [AUTO] in the [PROJECTOR SETUP] menu → [PROJECTION METHOD].

#### Angle sensor

The range of the installation attitude that is detected by the angle sensor built-in the projector is as follows.



### Interface Board (optional)

This projector is equipped with two SLOT NX-specification slots.

There are four SDI input terminals and one DIGITAL LINK input terminal equipped on this projector as the standard video input terminals. The input for HDMI, DVI-D, and SDI can be added by installing the optional Interface Board in the slot.


#### Attention

• Requesting a qualified technician to install or remove the optional Interface Board is recommended. A malfunction may occur due to static electricity. Consult your dealer.

## Projected image and throw distance

Install the projector referring to the projected image size and projection distance. Image size and image position can be adjusted in accordance with the screen size and screen position. When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, the projection relation between the screen and the projector differs from that of other lenses. Refer to "Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90)" (+ page 42) for details.

• Following illustration is prepared on the assumption that the projected image size and position have been aligned to fit full in the screen.



(Unit: m)


L (LW/LT)*1	Projection distance
L1	Lens protrusion dimension
SH	Projected image height
SW	Projected image width
SD	Projected image size

\*1 LW: Minimum projection distance when the Zoom Lens is used LT: Maximum projection distance when the Zoom Lens is used

(Unit: m)

Projection lens Model No.	Dimension for L1 (approximate value)
ET-D75LE6	0.182
ET-D75LE8	0.232
ET-D75LE10	0.095
ET-D75LE20	0.091
ET-D75LE30	0.091
ET-D75LE40	0.094
ET-D75LE50	0.173

#### Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90)



(Unit: m)

SH	Projected image height
SW	Projected image width
SD	Projected image size
L1	Projection distance (from the screen to the mirror reflection surface*1)
L2	Distance between the projector and the screen (from the screen to the tip of the lens)
L3	Distance between the projector and the screen (from the screen to the front surface of the projector)
L4	Distance between the projector and the screen (from the screen to the rear surface of the projector)
A1	Distance between the projector and the screen (from the screen bottom edge to the projector top)
A2	Distance between the projector and the screen (from the screen bottom edge to the projector bottom)

\*1 The mirror reflection surface cannot be seen from the outside, because it is located inside the Fixed-focus Lens.

(Unit: m)

Distance between projector	Formula								
and screen	ET-D75LE95	ET-D75LE90							
L2	= L1 <sup>*1</sup> + 0.029	$= L1^{*1} + 0.029$							
L3	= L1 <sup>*1</sup> – 0.262	= L1 <sup>*1</sup> – 0.247							
L4	= L1*1 – 1.332	= L1*1 – 1.317							
A2	= A1*1 + 0.419	= A1*1 + 0.419							

\*1 For details of calculating values, refer to "Formula for calculating the projection distance per projection lens" (+ page 48).

#### Attention

Before setting up, read "Precautions for use" (
 page 17).

Especially when the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, install the projector so that its back plane is parallel to the screen, making the projected image rectangular.

The vertical keystone distortion in moderate range can be corrected with the [POSITION] menu  $\rightarrow$  [GEOMETRY]  $\rightarrow$  [KEYSTONE]  $\rightarrow$  [VERTICAL KEYSTONE] ( $\Rightarrow$  page 104) even after the projector is installed. For the range that can be corrected, refer to "[GEOMETRY] projection range" ( $\Rightarrow$  page 43).

• The geometric adjustment function cannot be used when the video signal in simultaneous format is input. When installing the projector, follow the instructions below so that distortion does not occur in the projected image.

- Use a flat screen.
- Install the projector so that the front side of the projector is parallel to the screen.


- Install the projector so that the image can be projected within the lens shift adjustment range.

• Do not use the projector and the high-powered laser equipment in the same room. The DLP chips can be damaged if a laser beam hits the projection lens surface.

• The dimension of L4 is not the distance between the rear of the projector body and the wall, but the distance between the rear of the projector body and the screen surface. Install the projector with 500 mm (19-11/16") or larger space between the rear of the projector body and the wall or any object so that the ventilation is not obstructed.

When installing the projector in a confined space, provide air conditioning or ventilation separately. Exhaust heat may accumulate when the ventilation is not enough, triggering the protection circuit of the projector.

## [GEOMETRY] projection range



#### Standard status

Projection	Only [KEYS]	[ONE] used*1	[KEYSTO	NE] and [CUR\ toge	Only [CURVED CORRECTION] used			
Projection lens Model No.	Vertical keystone correction angle α (°)	Horizontal keystone correction angle β (°)	Vertical keystone correction angle α (°)	Horizontal keystone correction angle β (°)	Min. value of R2/L2	Min. value of R3/L3	Min. value of R2/L2	Min. value of R3/L3
ET-D75LE6	±28	±15	±10	±10	1.6	3.9	0.9	2.3
ET-D75LE8	±40	±15	±20	±15	0.2	0.4	0.2	0.3
ET-D75LE10	±40	±15	±10	±10	1.1	2.6	0.6	1.5
ET-D75LE20	±40	±15	±15	±10	0.9	1.7	0.5	1.0
ET-D75LE30	±40	±15	±20	±10	0.6	0.6 1.2		0.7
ET-D75LE40	±40	±15	±20	±15	0.4	0.7	0.2	0.4
ET-D75LE50	±22	±15	±8	±8	2.0	4.9	1.2	2.9
ET-D75LE95*2	+5 / -0	0	_	_	_	_	—	_
ET-D75LE90*2	+5 / -0	0	_	_	_	_	—	_

\*1 When [VERTICAL KEYSTONE] and [HORIZONTAL KEYSTONE] are used simultaneously, correction cannot be made exceeding total of 30°.

\*2 Only the vertical keystone correction angle can be corrected in the direction in which the projector body moves away from the screen.

#### When using the optional Upgrade Kit (Model No.: ET-UK20)

Dreigetion	Only [KEYS]	ſONE] used⁺¹	[KEYSTONE]	and [CURVED	Only [CURVED CORRECTION] used			
Projection lens Model No.	Vertical keystone correction angle α (°)	Horizontal keystone correction angle β (°)	Vertical keystone correction angle α (°)	Horizontal keystone correction angle β (°)	Min. value of R2/L2	Min. value of R3/L3	Min. value of R2/L2	Min. value of R3/L3
ET-D75LE6	±28	±15	±10	±10	1.2	3.0	0.7	1.7
ET-D75LE8	±45	±40	±20	±15	0.2	0.3	0.1	0.2
ET-D75LE10	±40	±15	±10	±10	0.9	2.0	0.5	1.1
ET-D75LE20	±40	±20	±15	±10	0.7	1.3	0.4	0.7
ET-D75LE30	±45	±25	±20	±10	0.5	0.9	0.3	0.5
ET-D75LE40	±45	±30	±20	±15	0.3	0.5	0.2	0.3
ET-D75LE50	±22	±15	±8	±8	1.5	3.7	0.9	2.2
ET-D75LE95*2	+5 / -0	0			—	_	—	—
ET-D75LE90*2	+5 / -0	0	—	—	—		—	—

\*1 When [VERTICAL KEYSTONE] and [HORIZONTAL KEYSTONE] are used simultaneously, correction cannot be made exceeding total of 30°.
 \*2 Only the vertical keystone correction angle can be corrected in the direction in which the projector body moves away from the screen.

Note

• When [GEOMETRY] is used, the focus of the entire screen may be lost as correction increases.

• Make the curved screen a circular arc shape with one part of a perfect circle removed.

• Adjustment range of the [GEOMETRY] items may not match the listed projection range depending on the projection lens. Use this projector within the projection range, otherwise the correction may not work.

• The expansion function by applying the optional Upgrade Kit (Model No.: ET-UK20) cannot be used when the video signal in simultaneous format is input.

#### Projection distance of each projection lens

A ±5 % error in listed projection distances may occur. When [GEOMETRY] is used, distance is corrected to become smaller than the specified image size.

### When the image aspect ratio is 16:10

(Unit: m)

Le	ns type		Zoom Lens											
Projection	lens Model	No.	ET-D7	75LE6	ET-D7	5LE10	ET-D75LE20		ET-D75LE30		ET-D7	5LE40	ET-D7	75LE8
Thro	ow ratio <sup>*1</sup>		1.00-1.18:1 1.39-1.79:1				1.79-2	2.59:1	2.58-	5.00:1	4.95-7.91:1		7.87-14.8:1	
Projecte	d image siz	e		Projection distance (L)										
Height			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.
Diagonal (SD)	(SH)	Width (SW)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)
1.78 (70")	0.942	1.508	1.46	1.75	2.05	2.65	2.64	3.85	3.82	7.45	7.37	11.85	11.65	22.20
2.03 (80")	1.077	1.723	1.68	2.01	2.35	3.04	3.03	4.41	4.38	8.54	8.45	13.56	13.37	25.42
2.29 (90")	1.212	1.939	1.90	2.27	2.65	3.43	3.42	4.98	4.94	9.63	9.52	15.28	15.09	28.64
2.54 (100")	1.346	2.154	2.11	2.53	2.96	3.83	3.81	5.54	5.51	10.72	10.60	16.99	16.81	31.86
3.05 (120")	1.615	2.585	2.55	3.05	3.57	4.61	4.59	6.67	6.63	12.90	12.75	20.42	20.25	38.31
3.81 (150")	2.019	3.231	3.20	3.83	4.48	5.79	5.76	8.37	8.32	16.17	15.98	25.57	25.41	47.97
5.08 (200")	2.692	4.308	4.29	5.13	6.00	7.76	7.71	11.20	11.12	21.62	21.36	34.14	34.01	64.08
6.35 (250")	3.365	5.385	5.37	6.43	7.52	9.73	9.65	14.03	13.93	27.07	26.74	42.72	42.61	80.19
7.62 (300")	4.039	6.462	6.46	7.73	9.05	11.70	11.60	16.86	16.74	32.51	32.12	51.30	51.21	96.31
8.89 (350")	4.712	7.539	7.54	9.03	10.57	13.66	13.55	19.69	19.55	37.96	37.50	59.87	59.81	112.42
10.16 (400")	5.385	8.616	8.63	10.33	12.09	15.63	15.50	22.52	22.36	43.41	42.88	68.45	68.40	128.53
12.70 (500")	6.731	10.770	10.80	12.93	15.13	19.56	19.39	28.18	27.98	54.31	53.63	85.60	85.60	160.75
15.24 (600")	8.077	12.923	12.97	15.53	18.18	23.50	23.29	33.84	33.60	65.21	64.39	102.75	102.80	192.97
25.40 (1000")	13.462	21.539	21.66	25.94	30.35	39.24	38.86	56.48	56.08	108.79	107.43	171.36	171.59	—

Le	Lens type Fixed-focus Lens								
Projection	lens Model	No.		ET-D7	5LE95/ET-D75LE90*2		ET-D75LE50		
Thre	ow ratio*1				0.390:1		0.746:1		
Projecte	Projected image size Projection Distance between projector and so								
Diagonal (SD)	Height (SH)	Width (SW)	distance (L1)	(L4)	ET-D75LE95 (A1)	ET-D75LE90 (A1)	Fixed		
1.78 (70")	0.942	1.508	_	—	—	—	1.09		
2.03 (80")	1.077	1.723	_	—	—	—	1.25		
2.29 (90")	1.212	1.939	_	_	_	_	1.42		
2.54 (100")	1.346	2.154	_	_	_	_	1.58		
3.05 (120")	1.615	2.585	1.01	-0.32	0.19 - 0.42	0.27 - 0.42	1.91		
3.81 (150")	2.019	3.231	1.26	-0.07	0.27 - 0.56	0.37 - 0.56	2.41		
5.08 (200")	2.692	4.308	1.67	0.34	0.41 - 0.79	0.53 - 0.79	3.23		
6.35 (250")	3.365	5.385	2.08	0.75	0.54 - 1.01	0.70 - 1.01	4.06		
7.62 (300")	4.039	6.462	2.50	1.16	0.67 - 1.24	0.86 - 1.24	4.89		
8.89 (350")	4.712	7.539	2.91	1.58	0.81 - 1.47	1.03 - 1.47	5.71		
10.16 (400")	5.385	8.616	3.32	1.99	0.94 - 1.70	1.19 - 1.70	6.54		
12.70 (500")	6.731	10.770	4.15	2.81	1.21 - 2.15	1.52 - 2.15	8.19		
15.24 (600")	8.077	12.923	4.97	3.64	1.47 - 2.61	1.85 - 2.61	9.84		
25.40 (1000")	13.462	21.539	_	_	_	_	16.45		

\*1 The throw ratio is based on the value during projection with the projected image size of 3.81 m (150").
\*2 When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, the projection relation between the screen and the projector differs from that of other lenses. Refer to "Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90)" (+ page 42) for details.

#### When the image aspect ratio is 16:9

(Unit: m)

Le	Lens type					Zoom Lens										
Projection	lens Model	No.	ET-D7	75LE6	ET-D7	75LE10 ET-D75LE20		ET-D75LE30		ET-D7	5LE40	ET-D7	75LE8			
Thro	ow ratio <sup>*1</sup>		1.00-1.18:1 1.39-1.79:1 1.79					2.59:1	2.58-	5.00:1	4.95-7.91:1		7.87-14.8:1			
Projecte	d image siz	е		Projection distance (L)												
Diagonal (SD) Height Width (S)			Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.		
Diagonal (SD)	(SH)	Width (SW)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)		
1.78 (70")	0.872	1.550	1.51	1.80	2.10	2.72	2.72	3.96	3.93	7.66	7.58	12.18	11.99	22.82		
2.03 (80")	0.996	1.771	1.73	2.07	2.42	3.13	3.12	4.54	4.51	8.78	8.69	13.94	13.75	26.13		
2.29 (90")	1.121	1.992	1.95	2.33	2.73	3.53	3.52	5.12	5.08	9.90	9.79	15.70	15.52	29.45		
2.54 (100")	1.245	2.214	2.18	2.60	3.04	3.94	3.92	5.70	5.66	11.02	10.90	17.47	17.29	32.76		
3.05 (120")	1.494	2.657	2.62	3.13	3.67	4.74	4.72	6.86	6.82	13.26	13.11	20.99	20.82	39.38		
3.81 (150")	1.868	3.321	3.29	3.94	4.61	5.96	5.92	8.61	8.55	16.62	16.43	26.28	26.13	49.32		
5.08 (200")	2.491	4.428	4.41	5.27	6.17	7.98	7.92	11.52	11.44	22.22	21.96	35.10	34.97	65.88		
6.35 (250")	3.113	5.535	5.52	6.61	7.74	10.00	9.92	14.43	14.32	27.82	27.49	43.91	43.80	82.43		
7.62 (300")	3.736	6.641	6.64	7.95	9.30	12.02	11.93	17.33	17.21	33.42	33.01	52.73	52.64	98.99		
8.89 (350")	4.358	7.748	7.75	9.28	10.86	14.05	13.93	20.24	20.10	39.02	38.54	61.54	61.48	115.55		
10.16 (400")	4.981	8.855	8.87	10.62	12.43	16.07	15.93	23.15	22.99	44.62	44.07	70.36	70.32	132.11		
12.70 (500")	6.226	11.069	11.10	13.30	15.56	20.11	19.93	28.97	28.76	55.82	55.13	87.98	87.99	165.23		
15.24 (600")	7.472	13.283	13.33	15.97	18.69	24.16	23.94	34.78	34.54	67.02	66.19	105.61	105.67	198.35		
25.40 (1000")	12.453	22.138	22.26	26.66	31.20	40.33	39.95	58.05	57.64	111.82	110.42	176.13	176.37	—		

Lens type Fixed-focus Lens										
Projection	lens Model	No.		ET-D7	5LE95/ET-D75LE90*2		ET-D75LE50			
Thre	ow ratio*1			0.746:1						
Projecte	ed image siz	e	Projection distance							
Diagonal (SD)	Height (SH)	Width (SW)		(L4)	ET-D75LE95 (A1)	ET-D75LE90 (A1)	Fixed			
1.78 (70")	0.872	1.550	—		_	_	1.12			
2.03 (80")	0.996	1.771	—	_	—	—	1.29			
2.29 (90")	1.121	1.992	—	_	_	—	1.46			
2.54 (100")	1.245	2.214	—	_	_	_	1.63			
3.05 (120")	1.494	2.657	1.04	-0.29	0.20 - 0.52	0.36 - 0.52	1.97			
3.81 (150")	1.868	3.321	1.29	-0.04	0.28 - 0.68	0.49 - 0.68	2.48			
5.08 (200")	2.491	4.428	1.72	0.38	0.42 - 0.95	0.69 - 0.95	3.33			
6.35 (250")	3.113	5.535	2.14	0.81	0.56 - 1.22	0.89 - 1.22	4.17			
7.62 (300")	3.736	6.641	2.56	1.23	0.69 - 1.49	1.10 - 1.49	5.02			
8.89 (350")	4.358	7.748	2.99	1.66	0.83 - 1.76	1.30 - 1.76	5.87			
10.16 (400")	4.981	8.855	3.41	2.08	0.97 - 2.02	1.51 - 2.02	6.72			
12.70 (500")	6.226	11.069	4.26	2.93	1.24 - 2.56	1.91 - 2.56	8.42			
15.24 (600")	7.472	13.283	5.11	3.78	1.52 - 3.10	2.32 - 3.10	10.12			
25.40 (1000")	12.453	22.138	_				16.91			

\*1 The throw ratio is based on the value during projection with the projected image size of 3.81 m (150").
\*2 When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, the projection relation between the screen and the projector differs from that of other lenses. Refer to "Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90)" (→ page 42) for details.

#### When the image aspect ratio is 4:3

(Unit: m)

Le	ns type							Zoom	Lens						
Projection	lens Model	No.	ET-D7	75LE6	ET-D7	ET-D75LE10 E		ET-D75LE20		ET-D75LE30		5LE40	ET-D7	ET-D75LE8	
Thro	ow ratio <sup>*1</sup>		1.20-1.42:1 1.67-2.15:1 2.				2.15-3	3.11:1	3.10-0	6.01:1	5.95-9.50:1		9.46-17.8:1		
Projecte	d image siz	e		Projection distance (L)											
Disconal (SD)	Discussel (CD) Height			Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	
Diagonal (SD)	(SH)	Width (SW)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	(LW)	(LT)	
1.78 (70")	1.067	1.422	1.66	1.99	2.33	3.01	3.00	4.37	4.34	8.46	8.37	13.43	13.24	25.18	
2.03 (80")	1.219	1.626	1.91	2.28	2.67	3.46	3.44	5.01	4.98	9.69	9.59	15.37	15.19	28.83	
2.29 (90")	1.372	1.829	2.16	2.58	3.02	3.90	3.89	5.65	5.61	10.93	10.80	17.32	17.14	32.47	
2.54 (100")	1.524	2.032	2.40	2.87	3.36	4.35	4.33	6.29	6.25	12.16	12.02	19.26	19.08	36.12	
3.05 (120")	1.829	2.438	2.89	3.46	4.05	5.24	5.21	7.57	7.52	14.63	14.46	23.14	22.98	43.42	
3.81 (150")	2.286	3.048	3.63	4.34	5.08	6.57	6.53	9.49	9.43	18.33	18.11	28.97	28.82	54.36	
5.08 (200")	3.048	4.064	4.86	5.82	6.81	8.80	8.74	12.70	12.61	24.50	24.20	38.68	38.56	72.60	
6.35 (250")	3.810	5.080	6.09	7.29	8.53	11.03	10.94	15.90	15.79	30.67	30.29	48.39	48.29	90.84	
7.62 (300")	4.572	6.096	7.32	8.76	10.25	13.26	13.15	19.11	18.97	36.84	36.38	58.10	58.03	109.08	
8.89 (350")	5.334	7.112	8.55	10.23	11.98	15.48	15.35	22.31	22.15	43.00	42.47	67.81	67.76	127.32	
10.16 (400")	6.096	8.128	9.78	11.71	13.70	17.71	17.56	25.51	25.33	49.17	48.56	77.52	77.50	145.57	
12.70 (500")	7.620	10.160	12.24	14.65	17.15	22.16	21.96	31.92	31.69	61.51	60.75	96.94	96.97	182.05	
15.24 (600")	9.144	12.192	14.69	17.60	20.59	26.62	26.37	38.33	38.06	73.85	72.93	116.36	116.44	218.53	
25.40 (1000")	15.240	20.320	24.53	29.38	34.38	44.44	44.01	63.96	63.50	123.20	121.65	194.04	194.32	—	

Lens type			Fixed-focus Lens				
Projection lens Model No.			ET-D75LE95/ET-D75LE90*2				ET-D75LE50
Throw ratio*1					0.467:1		0.898:1
Projected image size			Projection Distance between projector and screen			Projection distance (L)	
Diagonal (SD)	Height (SH)	Width (SW)	distance (L1)	(L4)	ET-D75LE95 (A1)	ET-D75LE90 (A1)	Fixed
1.78 (70")	1.067	1.422	—	_	—	_	1.24
2.03 (80")	1.219	1.626	—	—	—	—	1.43
2.29 (90")	1.372	1.829	—	—	—	_	1.61
2.54 (100")	1.524	2.032	—	—	—	_	1.80
3.05 (120")	1.829	2.438	1.14	-0.19	0.23 - 0.49	0.32 - 0.49	2.17
3.81 (150")	2.286	3.048	1.42	0.09	0.33 - 0.65	0.43 - 0.65	2.73
5.08 (200")	3.048	4.064	1.89	0.56	0.48 - 0.91	0.62 - 0.91	3.67
6.35 (250")	3.810	5.080	2.36	1.02	0.63 - 1.16	0.81 - 1.16	4.61
7.62 (300")	4.572	6.096	2.82	1.49	0.78 - 1.42	0.99 - 1.42	5.54
8.89 (350")	5.334	7.112	3.29	1.96	0.93 - 1.68	1.18 - 1.68	6.48
10.16 (400")	6.096	8.128	3.76	2.42	1.08 - 1.94	1.37 - 1.94	7.41
12.70 (500")	7.620	10.160	4.69	3.36	1.38 - 2.46	1.74 - 2.46	9.28
15.24 (600")	9.144	12.192	5.62	4.29	1.68 - 2.97	2.11 - 2.97	11.15
25.40 (1000")	15.240	20.320		_			18.64

\*1 The throw ratio is based on the value during projection with the projected image size of 3.81 m (150").
\*2 When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, the projection relation between the screen and the projector differs from that of other lenses. Refer to "Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90)" (⇒ page 42) for details.

### Formula for calculating the projection distance per projection lens

To use a projected image size not listed in this manual, check the projected image size SD (m) and use the respective formula to calculate projection distance.

The unit of all the formulae is m. (Values obtained by the following calculation formulae contain a slight error.) When calculating a projection distance using image size designation (value in inches), multiply the value in inches by 0.0254 and substitute it into SD in the formula for calculating the projection distance.

### Zoom Lens

Projection lens Model No.	Throw ratio	Aspect ratio	Projection dista	ance (L) formula
Projection lens model No.	mowratio	Aspect ratio	Min. (LW)	Max. (LT)
	1.00 - 1.18:1	16:10	= 0.8549 x SD - 0.0566	= 1.0242 x SD - 0.0736
ET-D75LE6	1.00 - 1.18:1	16:9	= 0.8786 x SD - 0.0566	= 1.0527 x SD - 0.0736
	1.20 - 1.42:1	4:3	= 0.9679 x SD - 0.0566	= 1.1596 x SD - 0.0736
	1.39 - 1.79:1	16:10	= 1.1985 x SD – 0.0857	= 1.5490 x SD - 0.1085
ET-D75LE10	1.39 - 1.79:1	16:9	= 1.2318 x SD – 0.0857	= 1.5921 x SD - 0.1085
	1.67 - 2.15:1	4:3	= 1.3569 x SD – 0.0857	= 1.7538 x SD - 0.1085
	1.79 - 2.59:1	16:10	= 1.5334 x SD – 0.0832	= 2.2280 x SD - 0.1162
ET-D75LE20	1.79 - 2.59:1	16:9	= 1.5760 x SD - 0.0832	= 2.2900 x SD - 0.1162
	2.15 - 3.11:1	4:3	= 1.7361 x SD - 0.0832	= 2.5226 x SD - 0.1162
	2.58 - 5.00:1	16:10	= 2.2121 x SD - 0.1131	= 4.2901 x SD - 0.1765
ET-D75LE30	2.58 - 5.00:1	16:9	= 2.2736 x SD - 0.1131	= 4.4094 x SD - 0.1765
	3.10 - 6.01:1	4:3	= 2.5046 x SD - 0.1131	= 4.8573 x SD - 0.1765
	4.95 - 7.91:1	16:10	= 4.2356 x SD - 0.1577	= 6.7529 x SD - 0.1615
ET-D75LE40	4.95 - 7.91:1	16:9	= 4.3534 x SD – 0.1577	= 6.9406 x SD - 0.1615
	5.95 - 9.50:1	4:3	= 4.7955 x SD – 0.1577	= 7.6456 x SD - 0.1615
	7.87 - 14.8:1	16:10	= 6.7707 x SD - 0.3862	= 12.6858 x SD - 0.3598
ET-D75LE8	7.87 - 14.8:1	16:9	= 6.9590 x SD - 0.3862	= 13.0385 x SD - 0.3598
	9.46 - 17.8:1	4:3	= 7.6658 x SD – 0.3862	= 14.3627 x SD - 0.3598

### Fixed-focus Lens


Projection lens Model No.	Throw ratio	Aspect ratio	Projection distance (L1) formula		between projector and n (A1)
			(LT) Iomula	Min.	Max.
	0.390:1	16:10	= 0.325 x SD + 0.020	= 0.198 x SH – 0.128	= 0.339 x SH – 0.128
ET-D75LE95	0.390:1	16:9	= 0.334 x SD + 0.020	= 0.220 x SH – 0.128	= 0.432 x SH – 0.128
	0.467:1	4:3	= 0.368 x SD + 0.020	= 0.198 x SH – 0.128	= 0.339 x SH – 0.128
	0.390:1	16:10	= 0.325 x SD + 0.020	= 0.245 x SH – 0.128	= 0.339 x SH – 0.128
ET-D75LE90	0.390:1	16:9	= 0.334 x SD + 0.020	= 0.328 x SH – 0.128	= 0.432 x SH – 0.128
	0.467:1	4:3	= 0.368 x SD + 0.020	= 0.245 x SH – 0.128	= 0.339 x SH - 0.128

Projection lens Model No.	Throw ratio	Aspect ratio	Projection distance (L) formula
	0.746:1	16:10	= 0.6505 x SD - 0.0713
ET-D75LE50	0.746:1	16:9	= 0.6686 x SD - 0.0713
	0.898:1	4:3	= 0.7365 x SD - 0.0713

## Adjusting adjustable feet

Install the projector on a flat surface so that the front of the projector is parallel to the screen surface and the projection screen is rectangular.

If the screen is tilted downward, extend the front adjustable feet so that the projected image becomes rectangular. The adjustable feet can also be used to adjust the projector to be level when it is tilted in the horizontal direction. Adjustable feet can be extended by turning them as shown in the figure. Turning them in the opposite direction will return them to the original position.



Maximum adjustable range Adjustable feet: 20 mm (25/32") each

## Attention

 Be careful not to block the intake/exhaust ports with your hands or any objects when adjusting the adjustable feet while the light source is on. (+ page 29)

## Attaching/removing the projection lens (optional)

Move the projection lens to the home position before replacing or removing the projection lens. (+ page 79)

#### Attention

- Replace the projection lens after turning off the power of the projector.
- Do not touch the electric contacts of the projection lens. Dust or dirt may cause poor contact.
- Do not touch the surface of the projection lens with your bare hands.
- Before attaching the projection lens, remove the lens cover attached to the projection lens.
- Do not touch any area other than specified in "Adjusting the lens mounter when the focus is unbalanced" (
   page 81) with the projection lens removed. Touching around the projection lens mount inside the projector may result in malfunction.
- Do not install the Fixed-focus Lens (Model No.: ET-D75LE5 (production discontinued)) on the projector. Installing by mistake will cause malfunction of the projector.
- Panasonic takes no responsibility for any damage or malfunction of the product resulting from the use of projection lenses which are not
  manufactured by Panasonic. Be sure to use the specified projection lenses.

#### Note

 The precautions for handling the lens are different for the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90). For details, refer to the Operating Instructions of ET-D75LE95 or ET-D75LE90.

## Attaching the projection lens

Attach the projection lens using the following procedure. Start from Step 3) when the lens hole cover is already removed.




Fig. 3

Fig. 4

## 1) Loosen the screw fixing the lens hole cover. (Fig. 1)

• Use a Phillips screwdriver to turn the screw fixing the lens hole cover counterclockwise until it turns freely.

#### 2) Remove the lens hole cover. (Fig. 2)

- While pressing the lens release button, turn the lens hole cover counterclockwise until the mark on the lens hole cover ( $\bigcirc$ ) aligns with the mark on the projector ( $\bigcirc$  on the left side of LOCK).
- 3) Insert the projection lens by aligning the mark on the projection lens (orange) with the mark on the projector (○ on the left side of LOCK) and turn clockwise until it clicks. (Fig. 3)
- 4) Secure the projection lens with the supplied lens fixing screw. (Fig. 4)
  - Use a Phillips screwdriver to secure it in screw hole A located to the right of mark on the projection lens (orange).
  - Some lenses may not have a screw hole A for securing the projection lens.

#### Attention

- Turn the projection lens counterclockwise to confirm that it does not come out.
- Store the removed lens hole cover in a safe place.
- After attaching the projection lens, turn on the projector and confirm the [LENS TYPE] setting. Change the setting if the type is different from the projection lens attached to the projector. (+ page 77)
- Continue to execute the lens calibration after confirming the [LENS TYPE] setting. (+ page 77)
- The lens hood needs to be mounted to the projector when an interchangeable projection lens is used under the condition that throw ratio is greater than 3.0 in the North America region. Always ask a qualified technician or your dealer to mount the lens hood.


The throw ratio described here is a value calculated by dividing the actual projection distance by the projected image width.

The lens hood is assembled and mounted to the projector using the following supplied components.

Lens hood 1, Lens hood 2, Lens hood mounting plate 1, Lens hood mounting plate 2, Lens hood screws, Knurled head screws For the assembly and attachment, refer to the separate document "Mounting the lens hood". The components and document of the lens hood may not be supplied depending on the country or region where you purchased the product.

## Removing the projection lens

Remove the projection lens using the following procedure.



#### 1) Remove the lens fixing screw.

• Use a Phillips screwdriver to remove the first screw to the right of the mark on the projection lens (orange).

## 2) Remove the projection lens by turning it counterclockwise while pressing the lens release button. (Fig. 1)

- Turn the projection lens counterclockwise until the mark on the projection lens (orange) is aligned with the mark on the projector ( $\bigcirc$  on the left side of LOCK).
- Proceed to Step 3) when carrying or storing the projector.

#### 3) Attach the supplied lens hole cover. (Fig. 2)

• Insert the lens hole cover by aligning the mark on the lens hole cover (○) with the mark on the projector (○ on the left side of LOCK) and turn clockwise until it clicks.

#### 4) Secure the lens hole cover. (Fig. 3)

• Use a Phillips screwdriver to tighten the screw fixing the lens hole cover.

#### Note

Some lenses may not have a screw hole to use to secure the projection lens.

#### Attention

- Store the removed projection lens where it will be free from vibration and impact.
- Store the removed lens fixing screw in a safe place.

## Connecting

## Before connecting

- Before connecting, carefully read the operating instructions for the external device to be connected.
- Turn off the power of all devices before connecting cables.
- Take note of the following points before connecting the cables. Failure to do so may result in malfunctions.
- When connecting a cable to a device connected to the projector or the projector itself, touch any nearby metallic objects to eliminate static electricity from your body before performing work.
- Do not use unnecessarily long cables to connect a device to the projector or to the projector body. The longer the cable, the more susceptible to noise it becomes. Since using a cable while it is wound makes it act like an antenna, it is more susceptible to noise.
- When connecting cables, connect GND first, then insert the connecting terminal of the connecting device in a straight manner.
- Acquire any connection cable necessary to connect the external device to the system that is neither supplied with the device nor available as an option.
- Install the optional Interface Board necessary for the video equipment to connect with the projector to the slot in advance.


Requesting a qualified technician to install or remove the optional Interface Board is recommended. A malfunction may occur due to static electricity. Consult your dealer.

For details on how to install the optional Interface Board, refer to "Installing the Interface Board (optional)" (→ page 287).

- Some computer models or graphic cards are not compatible with the projector.
- Connect using an extension device, etc., when installing the projector away from the video equipment. The projector may not display the image properly when it is connected directly using a long cable.
- For details of the types of video signals that can be used with the projector, refer to "List of compatible signals" (⇒ page 255).

## Connecting example: AV equipment

#### For <SDI IN 1>/<SDI IN 2>/<SDI IN 3>/<SDI IN 4> terminals



Quad link HD-SDI signal or quad link 3G-SDI signal


- Use a 5C-FB or higher (such as 5C-FB, or 7C-FB) or a Belden 1694A or higher connection cable to properly transmit images. Use a connection cable of 100 m (328'1") length or less.
- Setting the [DISPLAY OPTION] menu [SDI IN] is required depending on the connected external device or the input signal.
- Setting the [DISPLAY OPTION] menu  $\rightarrow$  [SDI IN]  $\rightarrow$  [SDI LINK] is required when the dual link signal or the quad link signal is input.
- To input the dual link signal, use the cable with same length and same type for connecting to the <SDI IN 1> terminal and the <SDI IN 2> terminal, or the <SDI IN 3> terminal and the <SDI IN 4> terminal. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.
- To input the quad link signal, use the cable with same length and same type for connecting to each of <SDI IN 1>/<SDI IN 2>/<SDI IN 3>/<SDI IN 4> terminals. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.

- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting
  dual link signals. A phase difference is generated between the LINK-A signal and the LINK-B signal, and the image may not be projected
  correctly.
- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting quad link signals. A phase difference is generated between the signals of Link 1, Link 2, Link 3, and Link 4, and the image may not be projected correctly.
- An error in signal detection may occur when an unsteady signal is input to the projector. In such case, set the [DISPLAY OPTION] menu → [SDI IN] to the content corresponding to the input signal.

## For <3G-SDI 1 IN>/<3G-SDI 2 IN> terminals and <3G-SDI 3 IN>/<3G-SDI 4 IN> terminals of the Interface Board

This is an example when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in <SLOT 1>.

SDI input compatible flat panel display




SD-SDI signal, HD-SDI signal, or 3G-SDI signal

- To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00.
- For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).
- Use a 5C-FB or higher (such as 5C-FB, or 7C-FB) or a Belden 1694A or higher connection cable to properly transmit images. Use a connection cable of 100 m (328'1") length or less.
- Setting the [DISPLAY OPTION] menu → [SLOT IN] is required depending on the connected external device or the input signal. Setting the [DISPLAY OPTION] menu → [SLOT IN] → [SDI LINK] is required when the dual link signal or the quad link signal is input.
- To input the dual link signal, use the cable with same length and same type for connecting to the <3G-SDI 1 IN> terminal and the <3G-SDI 2 IN> terminal, or the <3G-SDI 3 IN> terminal and the <3G-SDI 4 IN> terminal. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.
- To input the quad link signal, use the cable with same length and same type for connecting to each of <3G-SDI 1 IN>/<3G-SDI 2 IN>/<3G-SDI 3 IN>/<3G-SDI 4 IN> terminals. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.
- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting
  dual link signals. A phase difference is generated between the LINK-A signal and the LINK-B signal, and the image may not be projected
  correctly.
- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting quad link signals. A phase difference is generated between the signals of Link 1, Link 2, Link 3, and Link 4, and the image may not be projected correctly.
- An error in signal detection may occur when an unsteady signal is input to the projector. In such case, set the [DISPLAY OPTION] menu → [SLOT IN] to the content corresponding to the input signal.

#### For <SDI 1 IN>/<SDI 2 IN/1 OUT>/<SDI 3 IN>/<SDI 4 IN/3 OUT> terminals of the Interface Board

This is an example when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1>.


12G-SDI signal output compatible device



- Use a connection cable of 5C-FB or higher (such as 5C-FB, or 7C-FB), Belden 1694A or higher, or L-5.5CUHD manufactured by Canare Electric Co., Ltd. to properly transmit images. The maximum cable length that can be used is as follows. However, this maximum cable length is a rough guideline, and does not guarantee the transmission distance.
  - SD-SDI signal, HD-SDI signal, 3G-SDI signal: 150 m (492'2")
- 6G-SDI signal: 80 m (262'6") (When L-5.5CUHD is used, the cable length should be 110 m (360'11").)
- For 12G-SDI signal, the cable length will differ depending on the setting in the [DISPLAY OPTION] menu → [SLOT IN] → [SDI MODE].
   When [SDI MODE] is set to [INPUT]: 50 m (164'1") (When L-5.5CUHD is used, the cable length should be 100 m (328'1").)
   When [SDI MODE] is set to [OUTPUT]: 50 m (164'1") (When L-5.5CUHD is used, the cable length should be 90 m (295'3").)
- When the [DISPLAY OPTION] menu  $\rightarrow$  [SLOT IN]  $\rightarrow$  [SDI MODE] is set to [OUTPUT], attach a terminating resistor (75  $\Omega$ ) to the terminal with no device connected as an output destination.
- Use the BNC connector that is compatible with the coaxial cable and type of the signal to be used.
- Setting of the [DISPLAY OPTION] menu → [SLOT IN] is required depending on the connected external device or the input signal.
- Setting of the [DISPLAY OPTION] menu → [SLOT IN] → [SDI LINK] is required when the dual link signal or the quad link signal is input.
- To input the dual link signal, use the cable with same length and same type for connecting to the <SDI 1 IN> terminal and the <SDI 3 IN> terminal. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.
- To input the quad link signal, use the cable with same length and same type for connecting to each of <SDI 1 IN>/<SDI 2 IN/1 OUT>/<SDI 3 IN>/<SDI 4 IN/3 OUT> terminals. The image may not be projected correctly when the difference of the cable length is 4 m (13'1") or more.
- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting
  dual link signals. A phase difference is generated between the LINK-A signal and the LINK-B signal, and the image may not be projected
  correctly.
- Directly connect the projector with the external device that will output the signal without going through a distributor, etc., when inputting quad link signals. A phase difference is generated between the signals of Link 1, Link 2, Link 3, and Link 4, and the image may not be projected correctly.
- An error in signal detection may occur when an unsteady signal is input to the projector. In such case, set the [DISPLAY OPTION] menu → [SLOT IN] to the content corresponding to the input signal.
- The <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal do not support the input of the 6G-SDI signal or the 12G-SDI signal.
- To use the <SDI 2 IN/1 OUT> terminal or the <SDI 4 IN/3 OUT> terminal as an output terminal, set the [DISPLAY OPTION] menu → [SLOT IN] → [SDI MODE] to [OUTPUT].
- Install this board in either <SLOT 1> or <SLOT 2>. When these boards are installed in both <SLOT 1> and <SLOT 2>, only the board installed in <SLOT 1> can be used.

## For <HDMI IN 1>/<HDMI IN 2> terminals and <HDMI IN 3>/<HDMI IN 4> terminals of the Interface Board

This is an example when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in <SLOT 1>.



#### Note

• For the HDMI cable, use an HDMI High Speed cable that conforms to the HDMI standards. However, when the following 4K video signal exceeding the supported transmission speed of the HDMI High Speed cable is to be input, use the HDMI cable supporting the high speed transmission of 18 Gbps such as the one with Premium HDMI cable authentication.

A video signal with high specification color depth and gradation such as 3840 x 2160/60p 4:2:2/36-bit or 3840 x 2160/60p 4:4:4/24-bit
 Images may be disrupted or may not be projected when a video signal exceeding the supported transmission speed of the HDMI cable is used.


- Setting the [DISPLAY OPTION] menu → [SLOT IN] is required depending on the connected external device or the input signal. Setting the [DISPLAY OPTION] menu → [SLOT IN] → [HDMI LINK] is required when the dual link signal or the quad link signal is input.
- The <HDMI IN 1>/<HDMI IN 2>/<HDMI IN 3>/<HDMI IN 4> terminals can be connected to the external device with a DVI-D terminal by
- using the HDMI/DVI conversion cable. However, this may not function properly for some external devices, and image may not be displayed.
  When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).

The projector does not support VIERA Link (HDMI).

## For <DVI-D IN 1>/<DVI-D IN 2> terminals and <DVI-D IN 3>/<DVI-D IN 4> terminals of the Interface Board

This is an example when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in <SLOT 2>.




#### Note

- Setting the [DISPLAY OPTION] menu  $\rightarrow$  [SLOT IN] is required depending on the connected external device or the input signal.
- Setting the [DISPLAY OPTION] menu → [SLOT IN] → [DVI-D LINK] is required when the dual link signal or the quad link signal is input.
  The <DVI-D IN 1>/<DVI-D IN 2>/<DVI-D IN 3>/<DVI-D IN 4> terminals can be connected with the HDMI and DVI-D compatible device. However, some external devices may not be able to project images properly, such as the image not displaying.

### **Connecting example: Computers**

This is an example of installing the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) to <SLOT 1>, and the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) to <SLOT 2>.



#### Attention


• When connecting the projector to a computer or an external device, use the power cord supplied with each device and commercially available shielded cables.

Setting the [DISPLAY OPTION] menu → [SLOT IN] is required depending on the connected external device or the input signal.

- For the HDMI cable, use an HDMI High Speed cable that conforms to the HDMI standards. However, when the following 4K video signal
  exceeding the supported transmission speed of the HDMI High Speed cable is to be input, use the HDMI cable supporting the high speed
  transmission of 18 Gbps such as the one with Premium HDMI cable authentication.
- A video signal with high specification color depth and gradation such as 3840 x 2160/60p 4:2:2/36-bit or 3840 x 2160/60p 4:4:4/24-bit
   Images may be disrupted or may not be projected when a video signal exceeding the supported transmission speed of the HDMI cable is used.
- The <HDMI IN 1>/<HDMI IN 2>/<HDMI IN 3>/<HDMI IN 4> terminals can be connected to the external device with a DVI-D terminal by
- using the HDMI/DVI conversion cable. However, this may not function properly for some external devices, and image may not be displayed.
  The <DVI-D IN 1>/<DVI-D IN 2>/<DVI-D IN 3>/<DVI-D IN 4> terminals support the single link for DVI 1.0. They do not support the dual link for DVI 1.0.
- If you operate the projector using the computer with the resume feature (last memory), you may have to reset the resume feature to operate the projector.

### Connecting example using DIGITAL LINK

Twisted-pair-cable transmitter based on the communication standard HDBaseT<sup>™</sup> such as the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) uses the twisted pair cable to transmit input images, Ethernet, and serial control signal, and the projector can input such digital signal to the <DIGITAL LINK/LAN> terminal.



\*1 Control target is the projector or the twisted-pair-cable transmitter. The control itself may not be possible depending on the twisted-pair-cable transmitter. Check the operating instructions of the device to be connected.

#### Attention

- Always use one of the following when connecting a VCR.
- Use a VCR with built-in time base corrector (TBC).
- Use a time base corrector (TBC) between the projector and the VCR.
- If nonstandard burst signals are connected, the image may be disrupted. In such a case, connect the time base corrector (TBC) between the projector and the external devices.
- Ask a qualified technician or your dealer to install the cable wiring between the twisted-pair-cable transmitter and the projector. Image may be disrupted if cable transmission characteristics cannot be obtained due to inadequate installation.
- For the LAN cable between the twisted-pair-cable transmitter and the projector, use a cable that meets the following criteria:
- Conforming to CAT5e or higher standards
- Shielded type (including connectors)
- Straight-through
- Single wire
- When laying cables between the twisted-pair-cable transmitter and the projector, confirm that cable characteristics are compatible with CAT5e or higher using tools such as a cable tester or cable analyzer.
- When a relay connector is used, include it in the measurement.
- Do not use a hub between the twisted-pair-cable transmitter and the projector.
- When connecting to the projector using a twisted-pair-cable transmitter (receiver) of other manufacturers, do not place another twisted-paircable transmitter between the twisted-pair-cable transmitter of other manufacturers and the projector. This may cause image to be disrupted.
- Do not pull cables forcefully. Also, do not bend or fold cables unnecessarily.
- To reduce the effects of noise as much as possible, stretch out the cables between the twisted-pair-cable transmitter and the projector without any loops.
- Lay the cables between the twisted-pair-cable transmitter and the projector away from other cables, particularly power cables.
- When laying multiple cables, run them side by side along the shortest distance possible without bundling them together.

## 58 - ENGLISH

 After laying the cables, go to the [NETWORK] menu → [DIGITAL LINK STATUS] and confirm that the value of [SIGNAL QUALITY] is displayed in green which indicates normal quality. (⇒ page 195)

#### Note

- For the HDMI cable, use an HDMI High Speed cable that conforms to the HDMI standards. If a cable that does not conform to the HDMI standards is used, images may be interrupted or may not be projected.
- The projector does not support VIERA Link (HDMI).
- The optional Digital Interface Box (Model No.: ET-YFB100G) and the optional DIGITAL LINK Switcher (Model No.: ET-YFB200G) do not support the input and output of the 4K video signal.
- The maximum transmission distance between the twisted-pair-cable transmitter and the projector is 100 m (328'1") for the signal with resolution of 1 920 x 1 200 dots or less. It is possible to transmit up to 150 m (492'2") if the twisted-pair-cable transmitter supports the long-reach communication method. However, the signal that the projector can receive is only up to 1080/60p (1 920 x 1 080 dots, dot clock frequency 148.5 MHz) for the long-reach communication method. For the signal with the resolution exceeding 1 920 x 1 200 dots, the maximum transmission distance will be 50 m (164'1"). If these distances are exceeded, image may be disrupted or a malfunction may occur in LAN communication. Please note that Panasonic does not support the use of the projector outside the maximum transmission distance. When connecting with the long reach, video signal or distance that can be transmitted may be restricted, depending on the specification of the twisted-pair-cable transmitter.
- For twisted-pair-cable transmitters of other manufacturers of which the operation has been verified with the projector, visit the Panasonic website (https://panasonic.net/cns/projector/). Note that the verification for devices of other manufacturers has been made for the items set by Panasonic Corporation, and not all the operations have been verified. For operation or performance problems caused by the devices of other manufacturers, contact the respective manufacturers.

## Connecting example when using the contrast synchronization function/shutter synchronization function

In a case to construct a multi-display by linking projected images from multiple projectors, following functions can be used by synchronizing multiple projectors using the <MULTI PROJECTOR SYNC IN> terminal and the <MULTI PROJECTOR SYNC OUT> terminal.

Contrast synchronization function

A linked screen with balanced contrast can be displayed by sharing the brightness level of the video signal being input to each projector.

To use this function, set the [PROJECTOR SETUP] menu  $\rightarrow$  [MULTI PROJECTOR SYNC] for each synchronized projector as follows.

- Set [MULTI PROJECTOR SYNC] → [MODE] to anything other than [OFF].
   Set [MODE] to [MASTER] only on one projector that is synchronized. Set [MODE] to [SLAVE] for all other projectors.
- Set [MULTI PROJECTOR SYNC] → [CONTRAST SYNC] to [ON].


#### Shutter synchronization function

This is a function to synchronize the shutter operation of the specified projector to other projectors, and the effect using the shutter function including the fade in/fade out operation can be synchronized. To use this function, set the [PROJECTOR SETUP] menu  $\rightarrow$  [MULTI PROJECTOR SYNC] for each synchronized projector as follows.

- Set [MULTI PROJECTOR SYNC] → [MODE] to anything other than [OFF].
   Set [MODE] to [MASTER] only on one projector that becomes the synchronization source within the linked projectors. Set [MODE] to [SLAVE] for all other projectors.
- Set [MULTI PROJECTOR SYNC]  $\rightarrow$  [SHUTTER SYNC] to [ON].

#### Connecting example

Connect all the projectors to be linked in a loop by daisy chain connection when using the contrast synchronization function/shutter synchronization function. The number of linked projectors is limited to the maximum of 64 projectors.



- The contrast synchronization function and the shutter synchronization function can be used simultaneously.
- For details on the settings of the contrast synchronization function and the shutter synchronization function, refer to the [PROJECTOR SETUP] menu → [MULTI PROJECTOR SYNC] (
   → page 173).
- The menu items in the [PROJECTOR SETUP] menu → [MULTI PROJECTOR SYNC] is the same as the following setting items.
   The [PICTURE] menu → [DYNAMIC CONTRAST] → [USER] → [MULTI PROJECTOR SYNC]
- The [DISPLAY OPTION] menu  $\rightarrow$  [SHUTTER SETTING]  $\rightarrow$  [MULTI PROJECTOR SYNC]
- If there are any projectors which you do not want to synchronize within the linked projectors, set [CONTRAST SYNC] and [SHUTTER SYNC] to [OFF] individually.

# Chapter 3 Basic Operations

This chapter describes basic operations to start with.

## Switching on/off the projector

## Connecting the power cord

Confirm that the <MAIN POWER> switch is on the <OFF> side before connecting the supplied power cord. Use the power cord matching with the power supply voltage and the shape of the outlet. For details of power cord handling, refer to "Read this first!" (➡ page 5). For the shape of the outlet, refer to "Usable outlet" (➡ page 39).


#### Attention

The <AC IN> terminal on the side of the projector and the connector of the supplied power cord are not hot swapping compatible. When
removing the power cord from the projector, first make sure to remove the power plug from the outlet.

#### Note


- The light output will decrease to approximately 1/3 when using the projector with AC 100 V to AC 120 V.
- The supplied power cords vary depending on the country or region where you purchased the product.

#### How to attach the power cord



- 1) Check the shapes of the <AC IN> terminal on the side of the projector and the power cord connector, and insert the connector completely in the correct direction. (Fig. 1)
- 2) While inserting the power cord connector into the projector, turn clockwise until it clicks. (Fig. 2)


#### How to remove the power cord



- 1) Confirm that the <MAIN POWER> switch on the side of the projector is on the <OFF> side, and remove the power plug from the outlet.
- 2) Turn the power cord connector counterclockwise while sliding the lock lever forward (Fig. 1), and remove the connector from the <AC IN> terminal on the projector (Fig. 2).

#### **Power indicator**

Indicate the status of the power. Check the status of the power indicator <ON (G)/STANDBY (R)> before operating the projector.



Indicator status		Projector status
Off		The main power is switched off.
Red	Lit	<ul> <li>The power is switched off. (standby mode)</li> <li>Projection will start when the power on &lt;1&gt; button is pressed.</li> <li>The projector may not operate when the light source indicators <light1>/<light2> or the temperature indicator <temp> are blinking. (➡ page 222)</temp></light2></light1></li> </ul>
Green	Lit	Projecting.
Orange	Lit	The projector is preparing to switch off the projector. The power is switched off after a while. (Changes to the standby mode.)

#### Note

• While the power indicator <ON (G)/STANDBY (R)> lights in orange, the fan is running to cool the projector.

- For approximately 15 seconds after the projector is switched off, the indicator does not light up even if the power is switched on. Turn on the
  power again after the power indicator <ON (G)/STANDBY (R)> lights in red.
- The projector consumes power even in standby mode (power indicator <ON (G)/STANDBY (R)> lit in red). Refer to "Power consumption"
   (+ page 276) for the power consumption.
- When the projector receives the signal from the remote control, the power indicator <ON (G)/STANDBY (R)> will blink in the following color according to the status of the projector.

- When the projector is in projection mode: Green

- When the projector is in standby mode: Orange


However, if the [PROJECTOR SETUP] menu  $\rightarrow$  [STANDBY MODE] is set to [ECO], the indicator will stay lit in red and will not blink if the projector is in standby mode.

• The power indicator <ON (G)/STANDBY (R)> will blink slowly in green while the shutter function is in use (shutter: closed), or while the

function of the [PROJECTOR SETUP] menu  $\rightarrow$  [NO SIGNAL LIGHTS-OUT] ( $\Rightarrow$  page 168) is operating and the light source is turned off. • If the power indicator <ON (G)/STANDBY (R)> is blinking in red, consult your dealer.

### Switching on the projector

Install the projection lens before switching on the projector. Remove the lens cover first.



- 1) Connect the power cord to the projector.
- 2) Connect the power plug to an outlet.
- 3) Press the <ON> side of the <MAIN POWER> switch to turn on the power.
  - The power indicator <ON (G)/STANDBY (R)> lights in red, and the projector enters the standby mode.
- 4) Press the power on <|> button.
  - The power indicator <ON (G)/STANDBY (R)> lights in green and the image is soon projected on the screen.

#### Attention

• Always remove the lens cover before starting the projection. Projecting continuously while the lens cover is attached may cause the lens cover to heat up and result in a fire.

#### Note

A warm-up period of up to approximately five minutes may be necessary until an image is displayed when the projector is switched on at around 0 °C (32 °F).

The temperature indicator <TEMP> lights during the warm-up period. When the warm-up is completed, the temperature indicator <TEMP> turns off and the projection starts. Refer to "When an indicator lights up" ( page 222) for the indicator status display.

- If the operating environment temperature is low and warm-up takes more than five minutes, the projector will judge that a problem has
  occurred and the power will automatically be set to standby mode. In such case, increase the operating environment temperature to 0 °C
  (32 °F) or higher, turn off the main power, and then turn on the power again.
- It may take longer to start the projection when the [PROJECTOR SETUP] menu → [STANDBY MODE] is set to [ECO] compared to the time when it is set to [NORMAL].
- If the power was turned off at the previous use by pressing the <OFF> side of the <MAIN POWER> switch or by using the breaker directly while projecting, the power indicator <ON (G)/STANDBY (R)> lights up in green and an image is projected after a while when the power is turned on by pressing the <ON> side of the <MAIN POWER> switch or by turning the breaker on with the power plug connected to the outlet. This applies only when the [PROJECTOR SETUP] menu → [INITIAL STARTUP] is set to [LAST MEMORY].
- The light output will decrease to approximately 1/3 when using the projector with AC 100 V to AC 120 V.

### When the initial setting screen is displayed

When the projector is switched on for the first time after purchase, as well as when the [PROJECTOR SETUP] menu  $\rightarrow$  [INITIALIZE]  $\rightarrow$  [ALL USER DATA] is executed, the focus adjustment screen is displayed after projection starts, and then the **[INITIAL SETTING]** screen is displayed. Set them according to the circumstances. In other occasions, you can change the settings by menu operations.

If you press the <MENU> button while the **[INITIAL SETTING]** screen is displayed, you can go back to the previous screen.

#### Focus adjustment

Adjust the focus to display the menu screen clearly. You may also need to adjust the zoom and lens shift. Refer to "Adjusting the focus, zoom, and lens shift" (➡ page 75) for details.

1) Press ▲▼◀▶ to adjust the focus.

52+
<b>FO</b>
52 ••

2) Press the <MENU> button to proceed to the initial setting.

#### Initial setting (display language)

Select the language to show on the screen.

After completed the initial setting, you can change the display language from the [DISPLAY LANGUAGE] menu.

#### 1) Press $\blacktriangle \forall$ to select the display language.


INITIAL SETTING	1/7
ENGLISH	
DEUTSCH	
FRANÇAIS	
ESPAÑOL	
ITALIANO	
PORTUGUÊS	
日本語	
中文	
РУССКИЙ	
한국어	
Please select DISPLAY LANGUAGE.	
SELECT	
ENTER SET	

2) Press the <ENTER> button to proceed to the initial setting.

#### Initial setting (operation setting)

Set the items for the operating method depending on the projector's application and duration of usage. After completed the initial setting, you can change the settings of each item from the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]. If you change the settings while using the projector, the duration until the luminance of the light source decreases by half may shorten or the luminance may decrease.

This initial setting (operation setting) is prepared to complete the settings at once during the installation when the operation of the projector is predetermined. When the [PROJECTOR SETUP] menu  $\rightarrow$  [INITIALIZE]  $\rightarrow$  [ALL USER DATA] is executed, do not change the setting in the initial setting (operation setting), but press the <ENTER> button and proceed to next initial setting (installation setting). If you need to change the setting, ask the person responsible for this projector (such as a person in charge of equipment or operation).



#### Note

- The preceding initial setting screen is displayed when the projector is switched on for the first time after purchase. If the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed, the settings before execution are displayed in [OPERATING MODE] and [MAX LIGHT OUTPUT LEVEL].
- For the relationship between the luminance and the runtime, refer to "Interrelation of luminance and runtime" (> page 67).
- For details on each setting item, refer to the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING].

#### 1) Press ▲▼ to select [OPERATING MODE].

#### 2) Press **I** to switch the item.

- The items will switch each time you press the button.
- Set [OPERATING MODE] to anything other than [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when using the projector at an altitude of 2 700 m (8 858') or higher above sea level.
- Set [OPERATING MODE] to anything other than [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when using the optional Smoke Cut Filter (Model No.: ET-SFR330).

[HIGH] <sup>*1</sup>	The life of the light source will shorten compared to [NORMAL], but set this item when a higher luminance than [NORMAL] is required. The estimated runtime is approximately 8 000 hours.
[NORMAL]*1	Set this item when high luminance is required. The estimated runtime is approximately 20 000 hours. (Factory default setting)
[LONG LIFE1] <sup>•1</sup>	The luminance will decrease compared to [NORMAL], but set this item to increase the expected life of the light source. The estimated runtime is approximately 43 000 hours.
[LONG LIFE2]*1	The luminance will decrease compared to [LONG LIFE1], but set this item to increase the expected life of the light source. The estimated runtime is approximately 61 000 hours.
[LONG LIFE3]*1	The luminance will decrease compared to [LONG LIFE2], but set this item to increase the expected life of the light source. The estimated runtime is approximately 87 000 hours.
[USER1]	
[USER2]	Set [MAX LIGHT OUTPUT LEVEL] and [LIGHT OUTPUT] individually.
[USER3]	

\*1 The runtime is an estimation when the [PICTURE] menu  $\rightarrow$  [DYNAMIC CONTRAST] is set to [3].

• Proceed to Step 5) when [NORMAL], [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] is selected.

#### 3) Press ▲▼ to select [MAX LIGHT OUTPUT LEVEL].

#### 4) Press **♦** to adjust.

Operation	Operation Adjustment	
Press ▶.	Increases the maximum level of brightness correction.	
Press ◀.		

#### 5) Press $\blacktriangle \blacksquare$ to select [LIGHT OUTPUT].

#### 6) Press **♦** to adjust.

• When the Fixed-focus Lens (Model No.: ET-D75LE90) is used, set [LIGHT OUTPUT] to 77.0 % or less considering the focus quality. The luminance when [LIGHT OUTPUT] is set to 77.0 % is 20 000 lm (approximate).

Operation	Adjus	Dense of editorment		
Operation	Brightness	Runtime	Range of adjustment	
Press ▶.	The screen becomes brighter.	The runtime becomes shorter.		
Press ◀.	The screen becomes darker.	The runtime becomes longer.	8.0 % - 100.0 %*1	

\*1 The upper limit of the adjustment range is the value of [MAX LIGHT OUTPUT LEVEL] set in Step 4).

#### 7) Press the <ENTER> button to proceed to the initial setting.

#### Interrelation of luminance and runtime

The projector can be operated at arbitrary brightness and duration of use by combining the settings of [MAX LIGHT OUTPUT LEVEL] and [LIGHT OUTPUT].

Interrelation of luminance and runtime is as follows. Make the initial setting (operation setting) depending on your desired duration of use and brightness of the projected image.

Values of the luminance and runtime are rough estimations.

#### To set the projector based on the duration of use

Duration of use (hour)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT] <sup>*1</sup> (%)	Luminance (Im)
5 000	100.0	100.0	26 000
10 000	100.0	100.0	26 000
20 000	83.3	83.3	21 600
24 000	83.3	53.6	13 900
48 000	83.3	_	—
63 000	83.3	_	—
87 000	83.3		

\*1 The upper limit of the adjustment range is the value described in the [MAX LIGHT OUTPUT LEVEL] column in the table.

#### To set the projector based on luminance

Luminance (Im)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT] <sup>∗</sup> 1 (%)	Runtime (hour)
26 000	100.0	100.0	18 000
21 000	83.3	80.8	20 000
17 000	83.3	65.4	22 100
13 000	83.3	50.0	24 500
9 000	83.3	_	
7 000	83.3		
4 000	83.3	_	—

\*1 The upper limit of the adjustment range is the value described in the [MAX LIGHT OUTPUT LEVEL] column in the table.


- Under influence of characteristics of each light source, conditions of use, installation environment, etc., the runtime may be shorter than the estimation.
- The duration of use is referred to as the runtime when you use the projector successively. The duration of use is an estimated duration and is not the warranty period.
- The estimated runtime is the time until when the luminance decreases approximately by half, except when [OPERATING MODE] is set to [HIGH].
- If the consolidated runtime of the projector exceeds 20 000 hours, replacement of the components inside the projector may be required. The consolidated runtime can be confirmed in the [STATUS] screen. Refer to the [PROJECTOR SETUP] menu → [STATUS] for details.
- After completed the initial setting, the wider the combination of luminance and runtime becomes by setting the [PROJECTOR SETUP] menu → [BRIGHTNESS CONTROL] → [BRIGHTNESS CONTROL SETUP] → [CONSTANT MODE] to [AUTO] or [PC]. Refer to the [PROJECTOR SETUP] menu → [BRIGHTNESS CONTROL] for details.

#### Initial setting (installation setting)

Set [FRONT/REAR] and [FLOOR/CEILING] in [PROJECTION METHOD] depending on the installation mode. Refer to "Installation mode" (+ page 39) for details.

After completed the initial setting, you can change the setting from the [PROJECTOR SETUP] menu  $\rightarrow$  [PROJECTION METHOD].

#### 1) Press **♦** to switch the setting.



#### 2) Press the <ENTER> button to proceed to the initial setting.

#### Initial setting (standby mode)

Set the operation mode during standby. The factory default setting is [NORMAL], which allows you to use the network function during standby. To keep power consumption low during standby, set this item to [ECO]. After completed the initial setting, you can change the setting from the [PROJECTOR SETUP] menu  $\rightarrow$  [STANDBY MODE].

#### 1) Press **♦** to switch the setting.

INITIAL SETTING			4/7
STANDBY MODE	4	NORMAL	•
When set to ECO, network terminal, and some RS-232 available during standby.			UT
♦ CHANGE			
ENTER SET			

2) Press the <ENTER> button to proceed to the initial setting.

<sup>•</sup> The preceding initial setting screen is displayed when the projector is switched on for the first time after purchase. When the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed, the [STANDBY MODE] setting before execution is displayed.

#### Initial setting (screen setting)


Set the screen format (aspect ratio) and display position of the image. After completed the initial setting, you can change the settings of each item from the [DISPLAY OPTION] menu  $\rightarrow$  [SCREEN SETTING].

- 1) Press **♦** to switch the setting.
  - The setting will change each time you press the button.



#### 2) Press $\blacktriangle \forall$ to select [SCREEN POSITION].

- [SCREEN POSITION] cannot be selected or adjusted when [SCREEN FORMAT] is set to [16:10].
- 3) Press **♦** to adjust.



4) Press the <ENTER> button to proceed to the initial setting.

#### Initial setting (time zone)

Set [TIME ZONE] in accordance with the country or region where you use the projector. After completed the initial setting, you can change the setting from the [PROJECTOR SETUP] menu  $\rightarrow$  [DATE AND TIME]. The current settings are displayed in [LOCAL DATE] and [LOCAL TIME].

1) Press  $\triangleleft$  to switch the setting.

INITIAL SETTING	6/7
TIME ZONE	+09:00 ►
LOCAL DATE	20XX/01/01
LOCAL TIME	12:34:56
Please set up a time zone accor country or region.	rding to the area of your
◆ CHANGE	
ENTER SET	

#### 2) Press the <ENTER> button to proceed to the initial setting.

#### Note

 In the factory default setting, the time zone of the projector is set to +09:00 (Japan and Korea Standard Time). Change the setting of the [PROJECTOR SETUP] menu → [DATE AND TIME] → [TIME ZONE] to the time zone of the region where you use the projector.

#### Initial setting (date and time)

Set the local date and time. After completed the initial setting, you can change the setting from the [PROJECTOR SETUP] menu  $\rightarrow$  [DATE AND TIME].

To set the date and time automatically, refer to "Setting the date and time automatically" (> page 170).

#### 1) Press $\blacktriangle \lor$ to select an item.

INITIAL SETTING		7/7
YEAR	20XX	÷
MONTH	1	
DAY	1	
HOUR	12	
MINUTE	34	
SECOND	56	
Please set the date and time of t projector.	CHANGE	ne


#### 2) Press $\triangleleft$ to switch the setting.

#### 3) Press the <ENTER> button.

Confirm the setting value and complete the initial setting.

### Making adjustments and selections

It is recommended to perform the focus adjustment after 30 minutes have elapsed with the focus test pattern displayed. For details of the test pattern, refer to "[TEST PATTERN] menu" ( $\Rightarrow$  page 185). To use the active focus optimizer function, set the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [ACTIVE FOCUS OPTIMIZER]  $\rightarrow$  [ACTIVE FOCUS] to [ON], and then adjust the focus. ( $\Rightarrow$  page 154)



- 1) Press the <FOCUS> button to roughly adjust the focus of the projected image. (→ page 75)
- 2) Change the setting of the [PROJECTOR SETUP] menu → [PROJECTION METHOD] depending on the installation mode. (→ page 39)
  - Refer to "Navigating through the menu" (+ page 88) for the operation of the menu screen.

#### 3) Set [LENS TYPE].

 Confirm the setting of the lens type when using the projector for the first time after attaching the projection lens. (➡ page 77)

#### 4) Execute the lens calibration.

- Execute the lens calibration when using the projector for the first time after attaching the projection lens.
   (⇒ page 77)
- 5) Select the input by pressing the input selection button on the remote control or the control panel.

## • The buttons that can be used on the remote control or the control panel are as follows. **Remote control:**

<DIGITAL LINK> button, <DVI-D> button, <HDMI> button, <DISPLAYPORT> button, <SLOT 1> button, <SLOT 2> button, <SDI> button


#### Control panel:

<SDI 1/2> button, <SDI 3/4> button, <DIGITAL LINK> button, <SLOT 1> button, <SLOT 2> button
• For details of operation for input selection, refer to "Selecting the input signal." (+ page 73).

- 6) Adjust the front, back and sideway tilt of the projector with the adjustable feet. (+ page 49)
- 7) Press the <SHIFT> button to adjust the position of the projected image.
- 8) If the input signal is DVI-D/HDMI/DisplayPort signal, press the <AUTO SETUP> button.
- 9) Press the <ZOOM> button to match the projected image size to the screen.
- 10) Press the <FOCUS> button again to adjust the focus.
- 11) Press the <ZOOM> button again to adjust the zoom and match the projected image size to the screen.

When the projector is switched on for the first time after purchase, as well as when the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed, the focus adjustment screen is displayed after projection starts, and then the [INITIAL SETTING] screen is displayed. Refer to "When the initial setting screen is displayed" (→ page 65) for details.

## Switching off the projector



- 1) Press the power standby  $\langle 0 \rangle$  button.
  - The [POWER OFF(STANDBY)] confirmation screen is displayed.
- 2) Press **♦** to select [OK], and press the **<**ENTER> button.

#### (Or press the power standby <⊕> button again.)

- Projection of the image will stop, and the power indicator <ON (G)/STANDBY (R)> on the projector body lights in orange. (The fan keeps running.)
- 3) Wait for a few seconds until the power indicator <ON (G)/STANDBY (R)> of the projector body lights up in red (fan is stopped).
- 4) Press the <OFF> side of the <MAIN POWER> switch to turn off the power.

#### Attention

• When switching off the projector, make sure to follow the procedures described. Failure to do so may damage the internal components and result in malfunctions.

#### Note

- For approximately 15 seconds after the projector is switched off, the indicator does not light up even if the power is switched on.
- Even when the power standby <0> button is pressed and the projector is switched off, the projector consumes power if the main power of the projector is on.

When the [PROJECTOR SETUP] menu  $\rightarrow$  [STANDBY MODE] is set to [ECO], use of some functions is restricted, but the power consumption during standby can be conserved.

• The <MAIN POWER> switch of the projector is equipped with an overcurrent protection function. When current exceeding 25 A is detected, the overcurrent is automatically disconnected and the projector will go into the state that the <OFF> side is pressed. Consult your dealer when the overcurrent protection function is operated.


## Projecting

Check the projection lens attachment ( $\Rightarrow$  page 50), external device connection ( $\Rightarrow$  page 53), power cord connection ( $\Rightarrow$  page 62), switch on the power ( $\Rightarrow$  page 64) to start projecting. Select the video for projection, and adjust appearance of the projected image.

## Selecting the input signal.

The input of the image to project can be switched. Method to switch the input is as follows.

- Press the input selection button on the remote control and directly specify the input of the image to project.
- Press the input selection button on the control panel and directly specify the input of the image to project.
- Display the input selection screen and select the input of the image to project from the list.



#### Switching the input directly with the remote control

The input of the image to project can be switched by directly specifying it with the input selection button on the remote control.

1) Press the input selection button (<DIGITAL LINK>, <DVI-D>, <HDMI>, <DISPLAYPORT>, <SLOT 1>, <SLOT 2>, <SDI>).

<digital link=""></digital>	Switches the input to DIGITAL LINK. The image of the signal input to the <digital lan="" link=""> terminal is projected.</digital>		
<dvi-d></dvi-d>	Switches the input to DVI-D. This can be operated when the optional Interface Board equipped with the DVI-D input is installed in the slot. The input is switched every time the button is pressed when one of the DVI-D inputs is selected on the installed optional Interface Board.		
<hdmi></hdmi>	Switches the input to HDMI. This can be operated when the optional Interface Board equipped with the HDMI input is installed in the slot. The input is switched every time the button is pressed when one of the HDMI inputs is selected on the installed optional Interface Board.		
<displayport></displayport>	Switches the input to DisplayPort. This can be operated when the optional Interface Board equipped with the DisplayPort input is installed in the slot. The input is switched every time the button is pressed when one of the DisplayPort inputs is selected on the installed optional Interface Board.		
<slot 1=""></slot>	Switches the input to the signal of the optional Interface Board installed in <slot 1="">. The input is switched every time the button is pressed when one of the inputs is selected on the installed optional Interface Board.</slot>		
<slot 2=""></slot>	Switches the input to the signal of the optional Interface Board installed in <slot 2="">. The input is switched every time the button is pressed when one of the inputs is selected on the installed optional Interface Board.</slot>		
<sdi></sdi>	Switches the input to SDI1, SDI2, SDI3, or SDI4 installed on the projector as standard. The input is switched every time the button is pressed when one of the SDI inputs equipped on the projector as standard is selected. All the SDI inputs including the SDI input equipped on the projector as standard and the SDI input on the installed optional Interface Board are switched when an optional Interface Board equipped with the SDI input is installed in the slot.		

#### Attention

- Images may not be projected properly depending on the external device, or the Blu-ray disc or DVD disc, to be played back. Set the [PICTURE] menu → [SYSTEM SELECTOR]. When the SDI signal is input, set the [DISPLAY OPTION] menu → [SDI IN], or set the [DISPLAY OPTION] menu → [SLOT IN].
- Confirm the aspect ratio of the projection screen and the image, and switch to an optimum aspect ratio from the [POSITION] menu → [ASPECT].

#### Note

- When the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the <DIGITAL LINK/ LAN> terminal, the input on the DIGITAL LINK output supported device changes each time the <DIGITAL LINK> button is pressed. The input can also be changed using the RS-232C control command.
   For twisted-pair-cable transmitters of other manufacturers, switch the input on the projector to DIGITAL LINK, and then switch the input on the twisted-pair-cable transmitter.
- <DVI-D> button, <HDMI> button, <DISPLAYPORT> button, <SLOT 1> button, and <SLOT 2> button can be used when the optional Interface Board equipped with corresponding input is installed in the slot.
- The operation when the <DVI-D> button, <HDMI> button, <DISPLAYPORT> button, <SLOT 1> button, <SLOT 2> button, or <SDI> button is
  pressed can be fixed to operation to switch to the specified input using the [SECURITY] menu → [CONTROL DEVICE SETUP].

#### Switching the input directly with the control panel

The input of the image to project can be switched by directly specifying it with the input selection button on the control panel.

#### 1) Press the input selection button (<SDI 1/2>, <SDI 3/4>, <DIGITAL LINK>, <SLOT 1>, <SLOT 2>).

Switches the input to SDI1 or SDI2 equipped on the projector as standard.           The input is switched every time the button is pressed when either of the SDI1 or SDI2 input selected.	
<sdi 3="" 4=""></sdi>	Switches the input to SDI3 or SDI4 equipped on the projector as standard. The input is switched every time the button is pressed when either of the SDI3 or SDI4 input is selected.
<digital link=""></digital>	Switches the input to DIGITAL LINK. The image of the signal input to the <digital lan="" link=""> terminal is projected.</digital>
<slot 1=""></slot>	Switches the input to the signal of the optional Interface Board installed in <slot 1="">. The input is switched every time the button is pressed when one of the inputs is selected on the installed optional Interface Board.</slot>
<slot 2=""></slot>	Switches the input to the signal of the optional Interface Board installed in <slot 2="">. The input is switched every time the button is pressed when one of the inputs is selected on the installed optional Interface Board.</slot>

#### Attention

- Images may not be projected properly depending on the external device, or the Blu-ray disc or DVD disc, to be played back. Set the [PICTURE] menu → [SYSTEM SELECTOR]. When the SDI signal is input, set the [DISPLAY OPTION] menu → [SDI IN], or set the [DISPLAY OPTION] menu → [SLOT IN].
- Confirm the aspect ratio of the projection screen and the image, and switch to an optimum aspect ratio from the [POSITION] menu → [ASPECT].

#### Note

If the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the <DIGITAL LINK/LAN>
terminal, the input of the DIGITAL LINK output supported device is switched every time the <DIGITAL LINK> button is pressed. The input
can also be changed using the RS-232C control command.

For twisted-pair-cable transmitters of other manufacturers, switch the input on the projector to DIGITAL LINK, and then switch the input on the twisted-pair-cable transmitter.

• The <SLOT 1> button and the <SLOT 2> button can be used when the optional Interface Board equipped with corresponding input is installed in the slot.

 The operation when the <SDI 1/2> button, <SDI 3/4> button, <SLOT 1> button, or <SLOT 2> button is pressed can be fixed to operation to switch to the input set in the [SECURITY] menu → [CONTROL DEVICE SETUP].

#### Switching the input by displaying the input selection screen

The input of the image for projection can be selected by displaying the input selection screen.

#### 1) Press the <INPUT MENU> button on the remote control or control panel.

The input selection screen is displayed.
 Following input selection screen is an example of installing the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) to <SLOT 1>, and the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) to <SLOT 2>.

INPUT SELECT
• SDI1
SDI2
SDI3
SDI4
DIGITAL LINK
HDMI1 [SLOT1]
HDMI2 [SLOT1]
DVI-D3 [SLOT2]
DVI-D4 [SLOT2]
♦ SELECT
BITER SET

#### 2) Press the <INPUT MENU> button again.

• The input will switch each time you press the <INPUT MENU> button.

#### Note

- Input can be switched by pressing ▲▼ to select the input of the image for projection and pressing the <ENTER> button while the input selection screen is displayed.
- The [MULTI DISPLAY MODE] screen is display when the <INPUT MENU> button is pressed while in the four-screen display mode. Set the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] to anything other than [OFF] when using the four-screen display mode. (➡ page 183)
- If the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the projector, the input selection menu for the DIGITAL LINK output supported device is displayed when the <ENTER> button is pressed while the DIGITAL LINK input is selected in the input selection screen.
- If the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the projector, the DIGITAL LINK logo and the input name selected in the DIGITAL LINK output supported device are displayed in the display section of the [DIGITAL LINK] in the input selection screen.

## Adjusting the focus, zoom, and lens shift

Adjust the focus, zoom, and lens shift if the image projected to the screen or its position is shifted even if the projector and the screen are set up in the correct positions.

This section describes the adjustment method when anything other than the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used. When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, refer to "Adjusting the focus when the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used" ( $\Rightarrow$  page 76).

#### Using the control panel

- 1) Press the <LENS> button on the control panel.
  - Pressing the button changes the adjustment screen in the order of [FOCUS], [ZOOM], and [SHIFT].
- 2) Select each item and press ▲▼◀▶ to adjust it.

#### Using the remote control

- 1) Press the lens buttons (<FOCUS>, <ZOOM>, <SHIFT>) on the remote control.
  - Pressing the <FOCUS> button: Adjusts the focus (adjustment of the lens focus position).
  - Pressing the <ZOOM> button: Adjusts the zoom (adjustment of the lens zoom position).
  - Pressing the <SHIFT> button: Adjusts the lens shift (vertical position and horizontal position of the lens).
- 2) Select each item and press ▲▼◀▶ to adjust it.

## CAUTION

**During the lens shift operation, do not insert your hand in any opening around the lens.** Your hand may be caught in between, resulting to injury.

#### Note


- The zoom adjustment screen is not displayed when the projection lens without the zoom function is attached.
- When the Fixed-focus Lens (Model No.: ET-D75LE50) is used, do not adjust the lens shift, and use the projection lens in the home position.
   (+ page 79)
- The adjustment can be performed faster by holding down ▲▼◀▶ for approximately six seconds or longer while adjusting the focus, or for approximately three seconds or longer while adjusting the lens shift.
- It is recommended to perform the focus adjustment after 30 minutes have elapsed with the focus test pattern displayed. For details of the test pattern, refer to "[TEST PATTERN] menu" (
   → page 185). To use the active focus optimizer function, set the [PROJECTOR SETUP]
   menu → [LENS] → [ACTIVE FOCUS OPTIMIZER] → [ACTIVE FOCUS] to [ON], and then adjust the focus. (
   → page 154)
- Only [FOCUS] is shown in yellow so that the displayed menu item can be recognized by color, even when the projector is not focused and displayed characters are unreadable. (Factory default)
- The displayed color of [FOCUS] differs depending on the setting of the [DISPLAY OPTION] menu  $\rightarrow$  [ON-SCREEN DISPLAY]  $\rightarrow$  [OSD DESIGN].
- If the power is turned off during the focus adjustment, the zoom adjustment, or the lens shift adjustment, turn on the power again and execute the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION].
- When the main power is switched off during focus adjustment, lens calibration is performed automatically during the next focus adjustment.
  If the main power is turned off during the lens shift adjustment, a lens calibration error screen is displayed during the next lens shift
- adjustment. Execute the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION].
   Request a repair to your dealer if the lens calibration error screen is displayed even though the lens calibration is executed.
- Adjusting the focus when the Fixed-focus Lens (Model No : FT-D751 F95

## Adjusting the focus when the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used

After attaching the projection lens, adjust the focus with the projector correctly installed against the screen. The focus balance between the center and periphery of the projected image will differ depending on the size of the projected image when the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used. Adjust the focus balance of the periphery with the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) as necessary.

#### 1) Move the projection lens to the home position.

- For details of operation method, refer to "Moving the projection lens to the home position" (> page 79).
- 2) Adjust the focus at the center of projected image.
  - For the steps to adjust the focus, refer to "Adjusting the focus, zoom, and lens shift" (> page 75).
- 3) Loosen the lock screw and turn the periphery focus adjustment ring by hand to adjust the focus in the periphery of the screen.



Periphery focus adjustment ring

#### 4) Check the focus at the center of the image again and make fine adjustments.

#### 5) Tighten the lock screw.

• Periphery focus adjustment ring is fixed.

#### Note

When the projector is used for the first time or when the projection lens is replaced, confirm that the setting in the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is appropriate, and then execute the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION].

• The projected image size and scale shown on the periphery focus adjustment ring are an approximate guide.

### Setting the lens type

When the projector is used for the first time or when the projection lens is replaced, confirm the [LENS TYPE] setting. Change the setting if the type is different from the projection lens attached to the projector.

- 1) Press the <MENU> button.
  - The [MAIN MENU] screen is displayed.
- 2) Press ▲▼ to select [PROJECTOR SETUP].
- 3) Press the <ENTER> button.
  - The [PROJECTOR SETUP] screen is displayed.
- 4) Press ▲▼ to select [LENS].
- 5) Press the <ENTER> button.
  - The [LENS] screen is displayed, allowing to confirm the current setting in [LENS TYPE].
  - To change the setting, proceed to Step 6).
- 6) Press ▲▼ to select [LENS TYPE].
- 7) Press the <ENTER> button.
  - The [LENS TYPE] screen is displayed.
- 8) Press  $\blacktriangle \nabla$  to select the lens type.
  - Select the type of projection lens attached to the projector.

#### 9) Press the <ENTER> button.

#### Note

• For details of operation, refer to the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS TYPE] ( $\Rightarrow$  page 149).

#### Executing the lens calibration

Detect the lens adjustment limit value, and perform the calibration in the adjustment range. Execute the lens calibration after attaching the projection lens.

#### Zoom Lens with DC motor, the Fixed-focus Lens

This section describes the operating procedure when the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) in which the DC motor has not been replaced with the stepping motor unit is attached, or when the Fixed-focus Lens (Model No.: ET-D75LE50, ET-D75LE95, ET-D75LE90, etc.) without the zoom function is attached.

#### 1) Press the <MENU> button.

- The [MAIN MENU] screen is displayed.
- 2) Press ▲▼ to select [PROJECTOR SETUP].
- 3) Press the <ENTER> button.
  - The [PROJECTOR SETUP] screen is displayed.
- 4) Press ▲▼ to select [LENS].
- 5) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 6) Press  $\blacktriangle \forall$  to select [LENS CALIBRATION].
- 7) Press the <ENTER> button.
  - The confirmation screen is displayed.
- 8) Press **♦** to select [OK], and press the **<**ENTER> button.
  - The lens calibration is started.
  - After completing the calibration in the adjustment range, the projection lens will move to the home position.

#### Note

- [LENS CALIBRATION] cannot be executed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- For details of operation, refer to the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION] (→ page 159).
- The origin position of the lens mounter and the home position of the projection lens are automatically updated when the lens shift calibration is performed. The home position is a origin position of the lens shift (vertical position and horizontal position of the lens) based on the calibration result. It does not match with the optical image center position.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (+ page 80).

#### Zoom Lens with the stepping motor

This section describes the operating procedure when the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

1) Press the <MENU> button.

• The [MAIN MENU] screen is displayed.

- 2) Press ▲▼ to select [PROJECTOR SETUP].
- 3) Press the <ENTER> button.
  - The [PROJECTOR SETUP] screen is displayed.
- 4) Press ▲▼ to select [LENS].
- 5) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- Press ▲▼ to select [LENS CALIBRATION].
- 7) Press the <ENTER> button.

• The [LENS CALIBRATION] screen is displayed.

8) Press  $\blacktriangle \nabla$  to select an item.

[SHIFT/FOCUS/ZOOM]	Executes the calibrations for the lens shift, focus, and zoom. After completing the calibration in the adjustment range, the projection lens will move to the home position.
[SHIFT/FOCUS]	Executes the calibrations for the lens shift and focus. After completing the calibration in the adjustment range, the projection lens will move to the home position.
[ZOOM]	Executes the calibration of the zoom adjustment range.

#### 9) Press the <ENTER> button.

• The confirmation screen is displayed.

#### 10) Press **♦** to select [OK], and press the **<**ENTER> button.

• The lens calibration is started.

#### Note

- [LENS CALIBRATION] cannot be executed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- For details of operation, refer to the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS CALIBRATION] ( $\Rightarrow$  page 159).
- The origin position of the lens mounter and the home position of the projection lens are automatically updated when the lens shift calibration is performed. The home position is a origin position of the lens shift (vertical position and horizontal position of the lens) based on the calibration result. It does not match with the optical image center position.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).

## Moving the projection lens to the home position

Operate in following procedure to move the projection lens to the home position.

#### When operating from the main menu

- 1) Press the <MENU> button.
  - The [MAIN MENU] screen is displayed.
- 2) Press ▲▼ to select [PROJECTOR SETUP].
- 3) Press the <ENTER> button.
   The [PROJECTOR SETUP] screen is displayed.
- 4) Press ▲▼ to select [LENS].
- 5) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 6) Press ▲▼ to select [LENS HOME POSITION].
- 7) Press the <ENTER> button.
  - The confirmation screen is displayed.
- 8) Press **♦** to select [OK], and press the **<**ENTER> button.
  - [PROGRESS] is displayed in the [HOME POSITION] screen, and the projection lens is moved to the origin position.

#### Note

- [LENS HOME POSITION] cannot be executed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- [LENS HOME POSITION] will not operate correctly when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set incorrectly. Change the setting if the type is different from the projection lens attached to the projector.
- The projection lens is not moved to the correct home position when the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION] is not executed.
- The home position does not match with the optical image center position.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).
- The home position of the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) may deviate from the designed position.

#### When operating from the lens shift adjustment screen

- 1) Press the <DEFAULT> button on the remote control while displaying the lens shift adjustment screen.
  - The confirmation screen is displayed.

#### 2) Press **♦** to select [OK], and press the <ENTER> button.

• [PROGRESS] is displayed in the [HOME POSITION] screen, and the projection lens is moved to the origin position.

#### Note


- The [HOME POSITION] screen is not displayed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- The projection lens is not moved to the correct home position when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set incorrectly. Change the setting if the type is different from the projection lens attached to the projector.
- The projection lens is not moved to the correct home position when the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION] is not executed.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).
- The home position of the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) may deviate from the designed position.
- You can also display the [HOME POSITION] screen by pressing the <LENS> button on the control panel or the <SHIFT> button on the remote control for at least three seconds.

## Lens shift range

The projector can adjust the position of the projected image within the lens shift range for each projection lens based on the position of the projected image in the home position (standard projection position).

Perform the lens shift adjustment within the range indicated in the following illustration. Note that moving the lens outside the adjustment range may change the focus. This is because the shift of the lens is restricted to protect the optical parts.

Following illustration indicates the lens shift range when the projector is installed on desk/floor.



#### Note


• Use the projection lens in the standard projection position without adjusting the lens shift when the optional Fixed-focus Lens (Model No.: ET-D75LE50) is attached.

## Adjusting the lens mounter when the focus is unbalanced

#### Focus balance

#### Relationship between the tilt of the lens and the screen focus surface

When the projection lens is tilted in contrast with the image forming surface, tilting the front side (screen side) of the projection lens downwards (in the direction of the dotted arrow line), the upper side of the screen focus surface will tilt inwards and the lower side will tilt outwards as shown in the example.



#### How to adjust the focus balance (adjustment by tilting the lens mounter)

When the entire screen surface is not uniform even if the focus has been adjusted, the lens mounter has focus adjustment screws in three locations.

- Tool used: Hex driver or Allen wrench (diagonal 2.5 mm (3/32"))
- The Allen wrench is included with the projection lens ET-D75LE6, ET-D75LE8.


#### Lens mounter structure

Focus adjustment screws (a), (b), and (c) can be turned to move the lens mount bracket back and forth.

Also, tightening the fixed screws locks the lens mount bracket in place so it does not move.

When a projection lens with a large weight is installed, or when the projector is installed on an inclination, the lens may tilt and the focus may become unbalanced. In these cases, perform adjustment by referring to the relationship between the adjustment location and adjustment screws.

#### Front view diagram of the lens mounter (viewed from the screen side)




#### Note

• Focus adjustment screws (a), (b), and (c) are adjusted with the lens attached.

#### Adjustment procedure

#### Relationship between the adjustment location and adjustment screws



When the just focus point of		When the just focus point of	When the just focus point of the	When the just focus point of	When the just focus point of the
the screen in V up (top in the		the screen in V up (top in the	screen in V bottom (bottom in	the screen in H left (left in the	screen in H right (right in the
		vertical direction) is in the inner	the vertical direction) is in the	horizontal direction) is in the	horizontal direction) is in the
		side of the screen	inner side of the screen	inner side of the screen	inner side of the screen
	(a)		Rotate counterclockwise	_	_
	(b)	Rotate counterclockwise	_	Rotate counterclockwise	—
	(C)	Rotate counterclockwise	—	—	Rotate counterclockwise

- 1) Press the <FOCUS> button on the remote control or the <LENS> button on the control panel to display the focus adjustment screen.
- 2) Press ▼ to shift the focus of the entire screen once.
- 3) Press ▲ to stop on any part of the screen to be the first just focus point.

• For the location where focus is shifted in this state, the just focus point is on the inner side of the screen.

- 4) Loosen the fixed screws in the position relative to the location where the focus is shifted the most (the location where the just focus point is shifted the most towards the inner side in Step 2)) up to two rotations.
  - Turn screws clockwise in two locations, or at least in one location when making an adjustment.
- 5) Slowly turn the focus adjustment screws corresponding to the locations counterclockwise and stop where the image is in focus. (➡ page 81)

• If the screws are turned counterclockwise, the tilt of the lens will change by moving the lens mount bracket of the lens mounter forward (screen side), and in the projected image on the screen, the focus point in the opposite direction of the adjustment screws will move from the inner side of the screen to the outside.

- 6) Press the <SHIFT> button on the remote control or the <LENS> button on the control panel to display the lens shift adjustment menu, and reset the screen position of the projected image on the screen surface back to an optimal state.
- 7) Perform focus adjustment again near the center of the screen and if it is still not enough, fine tune the amount of rotation of the adjustment screws.
- 8) When adjustments have been made, securely tighten the loosened fixing screws.
- 9) Adjust the focus again using the remote control.

## **Operating with the remote control**



## Using the shutter function

If the projector is not used for a certain period of time during the meeting intermission, for example, it is possible to turn off the image temporarily.



#### 1) Press the <SHUTTER> button.

- The image disappears.
- This operation can be also performed using the <SHUTTER> button on the control panel.

#### 2) Press the <SHUTTER> button again.

• The image is displayed.

#### Note

- The power indicator <ON (G)/STANDBY (R)> will blink slowly in green while the shutter function is in use (shutter: closed).
- You can set whether to use the mechanical shutter or not and the time for the fade in/fade out of the image using the [DISPLAY OPTION] menu → [SHUTTER SETTING].
- If [MECHANICAL SHUTTER] in the [DISPLAY OPTION] menu → [SHUTTER SETTING] (
   → page 143) is set to [DISABLE], the light source
   may be lit dimly due to warm-up when the shutter function is used while the operating environment temperature is around 0 °C (32 °F).

### Using the on-screen display function

Turn off the on-screen display function (no display) when you do not wish the viewers to see the on-screen display, such as the menu or the input terminal name.

SCREEN button

#### 1) Press the <ON SCREEN> button.

- Turns off (hides) the on-screen display.
- 2) Press the <ON SCREEN> button again.
  - Cancels the hide condition of the on-screen display.

#### Note

• The hide condition of the on-screen display can also be canceled by pressing the <MENU> button on the control panel for at least three seconds while the on-screen display is off (hidden).

### Using the automatic setup function

The image position when DVI-D/HDMI/DisplayPort signal is input can be adjusted automatically. It is recommended to input an image with bright white borders at the edges and high-contrast black and white characters when the automatic setup is being performed.

Avoid using images that include halftones or gradation, such as photographs and computer graphics.



#### 1) Press the <AUTO SETUP> button.

- [COMPLETE] is displayed when it has completed without any problem.
- This operation can be also performed using the <AUTO SETUP> button on the control panel.

#### Note

- It is necessary to install the optional Interface Board equipped with the corresponding input on the slot to input the DVI-D/HDMI/DisplayPort
  signal directly without passing through the <DIGITAL LINK/LAN> terminal.
- If an image with blurred edges or a dark image is input, [INCOMPLETE] may appear or adjustment may not be performed properly even when [COMPLETE] appears. In such a case, adjust the setting in the [POSITION] menu → [SHIFT] (→ page 102).
- Adjust special signals according to the [DISPLAY OPTION] menu → [AUTO SETUP] (→ page 116).
- Automatic adjustment may not work depending on the model of the computer.
- Images may be disrupted for a few seconds during automatic adjustment, but it is not a malfunction.
- Adjustment is required for each input signal.
- Automatic adjustment can be canceled by pressing the <MENU> button during the automatic adjustment operation.
- Even if a signal possible to perform the automatic setup is being input, it may not be able to adjust correctly if the automatic setup function is used while the moving image is being input. [INCOMPLETE] may be displayed, or the adjustment may not be completed correctly even if [COMPLETE] is displayed.

## Switching the image aspect ratio

Switch the image aspect ratio according to the input.



#### 1) Press the <ASPECT> button.

• The setting will change each time you press the button.

#### Note

The aspect ratio of the image can also be switched using the menu operation. Refer to the [POSITION] menu → [ASPECT] (→ page 102) for details.

#### Using the function button

By assigning the following functions to the <FUNCTION> button, it can be used as a simplified shortcut button. [MULTI DISPLAY], [SUB MEMORY], [SYSTEM SELECTOR], [SYSTEM DAYLIGHT VIEW], [FREEZE], [WAVEFORM MONITOR], [LENS MEMORY LOAD], [PROJECTION METHOD]



#### 1) Press the <FUNCTION> button.

#### Note

Assignment of the function is performed from the [PROJECTOR SETUP] menu → [FUNCTION BUTTON] (⇒ page 176).

### Displaying internal test pattern

The projector has nine types of internal test patterns to check the condition of the projector. To display test patterns, perform the following steps.

PATTERN button

- 1) Press the <TEST PATTERN> button.
- 2) Press **I** to select the test pattern.

#### Note

- Test patterns can also be displayed using the menu operation. Refer to "[TEST PATTERN] menu" (> page 185) for details.
- Settings of position, size, and other factors will not be reflected in test patterns. Make sure to display the input signal before performing various adjustments.

### Using the status function

Display the status of the projector.



#### 1) Press the <STATUS> button.

• The [STATUS] screen is displayed.

STATUS	1/6
PROJECTOR TYPE	RQ32K(123456789012)
PROJECTOR RUNTIME	100000h
LIGHT RUNTIME	100000h / 100000h
MAIN/SUB VERSION	1.00 / 1.00
INTAKE AIR TEMP.	31°C/87°F
OPTICS MODULE TEMP.	27°C/80°F
EXHAUST AIR TEMP.	31°C/87°F
LIGHT1-B TEMP.	31°C/87°F
LIGHT1-S TEMP.	31°C/87°F
LIGHT2-B TEMP.	31°C/87°F
LIGHT2-S TEMP.	31°C/87°F
SELF TEST	NO ERRORS
ENTER SEND E-MAIL	
♦ CHANGE	MENU EXIT

Note

The projector status can also be displayed using the menu operation. Refer to the [PROJECTOR SETUP] menu → [STATUS]
 (⇒ page 177) for details.

## Using the AC voltage monitor function

The value of input supply voltage can be displayed on the self-diagnosis display at the side of the projector.

#### To display during projection

#### 1) Press the power on <|> button.

- The value of the input supply voltage is displayed only as numeric value on the self-diagnosis display.
- The display will turn off automatically after approximately 3 seconds.

#### To display during standby mode

#### 1) Press the power standby <⊕> button.

- The value of the input supply voltage is displayed only as numeric value on the self-diagnosis display.
- The display will turn off automatically after approximately 3 seconds.

#### Note

- The value of the input supply voltage can be always displayed in the self-diagnosis display by setting the [PROJECTOR SETUP] menu → [AC VOLTAGE MONITOR] (→ page 179) to [ON].
- The value of input supply voltage cannot be displayed in the self-diagnosis display during standby when the [PROJECTOR SETUP] menu
   → [STANDBY MODE] (→ page 168) is set to [ECO].
- Operation can also be performed by the power on <1> button or power standby <0> button on the control panel.

## Setting ID number of the remote control

When you use the multiple projectors together, you can operate all the projectors simultaneously or each projector individually using a single remote control, if a unique ID number is assigned to each projector.

After setting the ID number of the projector, set same ID number on the remote control.

The factory default ID number of the projector is set to [ALL]. When using a single projector, press the <ID ALL> button on the remote control. Also, you can control a projector by pressing the <ID ALL> button on the remote control even if you do not know the projector ID.





button

- 2) Within five seconds, press and set the one-digit or two-digit ID number set on the projector body using the number (<0> <9>) buttons.
  - If you press the <ID ALL> button, you can control the projectors regardless of the ID number setting of the projector body.

#### Attention

- Since the ID number of the remote control can be set without the projector body, do not press the <ID SET> button on the remote control carelessly. If the <ID SET> button is pressed and no number (<0> <9>) buttons are pressed within five seconds, the ID number returns to its original value before the <ID SET> button was pressed.
- The ID number set on the remote control will be stored unless it is set again. However, it will be erased if the remote control is left with dead batteries. Set the same ID number again when the batteries are replaced.

#### Note

- When the ID number of the remote control is set to [0], you can control the projector regardless of the ID number setting of the projector body, as same as when [ALL] is set.
- Set the ID number of the projector body from the [PROJECTOR SETUP] menu  $\rightarrow$  [PROJECTOR ID].

# Chapter 4 Settings

This chapter describes the settings and adjustments you can make using the on-screen menu.

## Menu navigation

The on-screen menu (Menu) is used to perform various settings and adjustments of the projector.

#### Navigating through the menu

#### **Operating procedure**



- 1) Press the <MENU> button on the remote control or control panel.
  - The [MAIN MENU] screen is displayed.

MAIN MENU
PICTURE
🛱 DISPLAY LANGUAGE
C DISPLAY OPTION
🐓 PROJECTOR SETUP
🖽 MULTI DISPLAY
TEST PATTERN
III SIGNAL LIST
o <sup>¢</sup> security
MENU SELECT
ENTER SUB MENU

- 2) Press  $\blacktriangle \nabla$  to select an item from the main menu.
  - The selected item is highlighted in yellow.


MAIN MENU
PICTURE
ADVANCED MENU
🛱 DISPLAY LANGUAGE
C DISPLAY OPTION
🖇 PROJECTOR SETUP
H MULTI DISPLAY
TEST PATTERN
III SIGNAL LIST
of SECURITY
Select

#### 3) Press the <ENTER> button.

• The sub-menu items of the selected main menu are displayed.



- 4) Press ▲▼ to select a sub-menu, and press ◀▶ or the <ENTER> button to change or adjust settings.
  - Some items will switch in order as follows each time you press ◀▶.



• For some items, press **\** to display an individual adjustment screen with a bar scale as shown below.



#### Note

- Pressing the <MENU> button while the menu screen is displayed returns to the previous menu.
- Some items or functions may not be adjusted or used depending on the signals to be input to the projector. When the items cannot be
  adjusted or used, the items in the menu screen are shown in black characters, and they cannot be adjusted or set.
  If the item in the menu screen is displayed in black characters and the item cannot be adjusted or set, the factor causing it is displayed by
  pressing the <ENTER> button while the corresponding menu is selected.
- Some items can be adjusted even if signals are not input.
- Individual adjustment screen is cleared automatically if no operation is performed for approximately five seconds.
- For menu items, refer to "Main menu" (→ page 89) and "Sub-menu" (→ page 90).
- The cursor color depends on the setting in the [DISPLAY OPTION] menu → [ON-SCREEN DISPLAY] → [OSD DESIGN]. The selected item is displayed with the yellow cursor by the factory default.
- In the portrait setting, the on-screen menu is displayed sideways. To display the on-screen menu vertically, change the setting of the [DISPLAY OPTION] menu → [ON-SCREEN DISPLAY] → [OSD ROTATION].

#### Resetting adjustment values to the factory default

If the <DEFAULT> button on the remote control is pressed, the values adjusted in the menu items are restored to the factory default settings.


## DEFAULT button

#### 1) Press the <DEFAULT> button on the remote control.



#### Note

- You cannot reset all the settings to the factory default at a time.
- To reset all the settings adjusted in the sub-menu item to the factory default one at a time, execute the [PROJECTOR SETUP] menu → [INITIALIZE].
- Some items cannot be reset to the factory default settings even when the <DEFAULT> button on the remote control is pressed. Adjust those items individually.
- The triangular mark under the bar scale in the individual adjustment screen indicates the factory default setting. The position of the triangular mark varies according to the selected input signals.



#### Main menu

The following items are in the main menu.

When a main menu item is selected, the screen changes to a sub-menu selection screen.

	Page	
	[PICTURE]	93
	[POSITION]	102
	[ADVANCED MENU]	107
<b>F</b>	[DISPLAY LANGUAGE]	113

	Main menu item	Page
L <u>ê</u>	[DISPLAY OPTION]	114
<b>₽</b>	[PROJECTOR SETUP]	148
	[MULTI DISPLAY]	183
	[TEST PATTERN]	185
Ī	[SIGNAL LIST]	186
<del>ر</del>	[SECURITY]	189
<del></del>	[NETWORK]	195

## Sub-menu

The sub-menu of the selected main menu item is displayed, and you can set and adjust items in the sub-menu.

## [PICTURE]

Sub-menu item	Factory default	Page
[PICTURE MODE]	[STANDARD]*1	93
[CONTRAST]	[0]*2	93
[BRIGHTNESS]	[0]*2	94
[COLOR]	[0]*2	94
[TINT]	[0]*2	94
[COLOR TEMPERATURE]	[DEFAULT]*2	94
[GAMMA]	[DEFAULT]*2	96
[SYSTEM DAYLIGHT VIEW]	[OFF]*2	97
[SHARPNESS]	[+8] <sup>*2</sup>	97
[NOISE REDUCTION]	[2]*2	98
[DYNAMIC CONTRAST]	[2]*2	98
[COLOR SPACE]	[NATIVE]	99
[SYSTEM SELECTOR]	[AUTO]*1	100

\*1 Depends on the signal input.\*2 Depends on the [PICTURE MODE].

## 

Sub-menu item	Factory default	Page
[SHIFT]	—	102
[ASPECT]	[DEFAULT]	102
[ZOOM]	_	103
[GEOMETRY]	[OFF]	104

## [ADVANCED MENU]

Sub-menu item	Factory default	Page
[DIGITAL CINEMA REALITY]	[AUTO]*1	107
[BLANKING]		107
[EDGE BLENDING]	[OFF]	108
[FRAME RESPONSE]	[NORMAL]	110
[FRAME CREATION]		111
[QUAD PIXEL DRIVE]	[ON]	112

Sub-menu item	Factory default	Page
[RASTER POSITION]	—	112

\*1 Depends on the signal input.



Details (➡ page 113)

## 

Sub-menu item	Factory default	Page
[COLOR MATCHING]	[OFF]	114
[LARGE SCREEN CORRECTION]	[OFF]	115
[SCREEN SETTING]	—	115
[AUTO SIGNAL]	[OFF]	116
[AUTO SETUP]	—	116
[BACKUP INPUT SETTING]	_	117
[SIMUL INPUT SETTING]		118
[SDI IN]		119
[DIGITAL LINK IN]		122
[SLOT IN]		124
[ON-SCREEN DISPLAY]		139
[BACK COLOR]	[BLUE]	141
[STARTUP LOGO]	[DEFAULT LOGO]	141
[UNIFORMITY]	—	142
[SHUTTER SETTING]	_	143
[FREEZE]		145
[WAVEFORM MONITOR]	[OFF]	145
[CUT OFF]	—	147

## [PROJECTOR SETUP]

Sub-menu item	Factory default	Page
[PROJECTOR ID]	[ALL]	148
[PROJECTION METHOD]	_	148
[LENS]	—	149
[OPERATION SETTING]	_	161
[LIGHT OUTPUT]	[83.3%]	163
[BRIGHTNESS CONTROL]	[OFF]	164
[STANDBY MODE]	[NORMAL]	168
[NO SIGNAL SHUT-OFF]	[DISABLE]	168
[NO SIGNAL LIGHTS-OUT]	[DISABLE]	168
[INITIAL STARTUP]	[LAST MEMORY]	169
[STARTUP INPUT SELECT]	[LAST USED]	169
[DATE AND TIME]	_	170
[SCHEDULE]	[OFF]	171
[MULTI PROJECTOR SYNC]	_	173
[RS-232C]	_	175
[REMOTE2 MODE]	[DEFAULT]	176
[FUNCTION BUTTON]	_	176
[STATUS]	—	177
[AC VOLTAGE MONITOR]	[OFF]	179
[FILTER SETTING]		180
[SAVE ALL USER DATA]	—	181
[LOAD ALL USER DATA]		181
[INITIALIZE]	—	181

Sub-menu item	Factory default	Page
[SERVICE PASSWORD]	_	182

## [MULTI DISPLAY] 田

Details (⇒ page 183)

### [TEST PATTERN]

Details (⇒ page 185)

## [SIGNAL LIST]

Details (➡ page 186)

## [SECURITY]

Sub-menu item	Factory default	Page
[SECURITY PASSWORD]	[OFF]	189
[SECURITY PASSWORD CHANGE]	_	189
[DISPLAY SETTING]	[OFF]	189
[TEXT CHANGE]	_	190
[CONTROL DEVICE SETUP]	_	190
[CONTROL DEVICE PASSWORD CHANGE]	_	194

## [NETWORK]

Sub-menu item	Factory default	Page
[DIGITAL LINK MODE]	[AUTO]	195
[DIGITAL LINK STATUS]	—	195
[NETWORK SETUP]	—	196
[NETWORK CONTROL]	_	196
[NETWORK STATUS]	—	197
[DIGITAL LINK MENU]	_	197
[Art-Net SETUP]	[OFF]	197
[Art-Net CHANNEL SETTING]	[2]	198
[Art-Net STATUS]	_	199

Note

• Some items may not be adjusted or used for certain signal formats to be input to the projector.

When the items cannot be adjusted or used, the items in the menu screen are shown in black characters, and they cannot be adjusted or set.

• Sub-menu items and factory default settings vary depending on the selected input terminal.

## [PICTURE] menu

On the menu screen, select [PICTURE] from the main menu, and select an item from the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

## [PICTURE MODE]

You can switch to the desired picture mode suitable for the image source and the environment in which the projector is used.

#### 1) Press ▲▼ to select [PICTURE MODE].

#### 2) Press **♦**.

• The [PICTURE MODE] individual adjustment screen is displayed.

#### 3) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[STANDARD]	The image becomes suitable for moving images in general.
[CINEMA]	The image becomes suitable for movie contents.
[NATURAL]	The image is sRGB compliant.
[DICOM SIM.]	The image becomes similar to that of DICOM Part 14 Grayscale Standard.
[DYNAMIC]	The light output is maximized for use in bright areas.
[GRAPHIC]	The image becomes suitable for input from the personal computer.
[USER]	Set any desired picture mode.

#### Note

- The factory default picture mode is [GRAPHIC] for still image input signals and [STANDARD] for movie-based input signals.
- DICOM is an abbreviation of "Digital Imaging and COmmunication in Medicine" and is a standard for medical imaging devices. Although the DICOM name is used, the projector is not a medical device, and should not be used for purposes such as diagnosis of display images.
- Press the <ENTER> button when each [PICTURE MODE] is selected to save as a specified value when a new signal is input. The data of all items except [SYSTEM SELECTOR] in the [PICTURE] menu is saved.
- In the factory default settings, [USER] is set to images that comply with the ITU-R BT.709 standard.

#### Changing the [USER] name

- 1) Press ▲▼ to select [PICTURE MODE].
- 2) Press **♦** to select [USER].
- 3) Press the <ENTER> button.
   The [PICTURE MODE] detailed screen is displayed.
- 4) Press ▲▼ to select [PICTURE MODE NAME CHANGE], and press the <ENTER> button.
  - The [PICTURE MODE NAME CHANGE] screen is displayed.
- 5) Press  $\blacktriangle = 4$  to select the text, and press the <ENTER> button to enter the text.
- 6) Press  $\blacktriangle = 4$  to select [OK], and press the <ENTER> button.
  - The picture mode name is changed.

#### [CONTRAST]

You can adjust the contrast of the colors.

- 1) Press  $\blacktriangle \blacksquare$  to select [CONTRAST].
- 2) Press **♦** or the **<**ENTER> button.
  - The **[CONTRAST]** individual adjustment screen is displayed.
- 3) Press **♦** to adjust the level.

Operation	Adjustment	Range of adjustment
Press ▶.	The screen becomes brighter.	24 + 24
Press ◀.	The screen becomes darker.	-31 - +31

#### Attention

• Adjust [BRIGHTNESS] first when you need to adjust the black level.

### [BRIGHTNESS]

You can adjust the dark (black) part of the projected image.

- 1) Press ▲▼ to select [BRIGHTNESS].
- 2) Press **♦** or the **<**ENTER> button.

• The [BRIGHTNESS] individual adjustment screen is displayed.

3) Press **♦** to adjust the level.

Operation	Adjustment	Range of adjustment
Press ▶.	Increases the brightness of the dark (black) parts of the screen.	24 24
Press ◀.	Reduces the brightness of the dark (black) parts of the screen.	-31 - +31

## [COLOR]

You can adjust the color saturation of the projected image.

- 1) Press ▲▼ to select [COLOR].
- 2) Press **♦** or the **<**ENTER> button.

• The **[COLOR]** individual adjustment screen is displayed.

3) Press **♦** to adjust the level.

Operation	Adjustment	Range of adjustment
Press ▶.	Deepens colors.	- 31 - +31
Press ◀.	Weakens colors.	

## [TINT]

You can adjust the skin tone in the projected image.

- 1) Press  $\blacktriangle \forall$  to select [TINT].
- 2) Press **♦** or the **<**ENTER**>** button.

• The [TINT] individual adjustment screen is displayed.

3) Press **♦** to adjust the level.

Operation	Adjustment	Range of adjustment
Press ▶.	Adjusts skin tone toward greenish color.	24 + 24
Press 4.	Adjusts skin tone toward reddish purple.	-31 - +31

### [COLOR TEMPERATURE]

You can switch the color temperature if the white areas of the projected image are bluish or reddish.

#### Adjusting with color temperature

- 1) Press  $\blacktriangle$  to select [COLOR TEMPERATURE].
- 2) Press **♦** or the **<**ENTER> button.
  - The **[COLOR TEMPERATURE]** individual adjustment screen is displayed.

#### 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[DEFAULT] Factory default setting.

[USER1]	Adjusts white balance as desired. Refer to "Adjusting desired white balance" (+ page 95) for		
[USER2]	details.		
[3200K] - [9300K]	Allows you to set in increments of 100 K. Select so that images become natural.		

#### Note

- When [PICTURE MODE] (→ page 93) is set to [USER] or [DICOM SIM.], [DEFAULT] cannot be selected.
- When [COLOR MATCHING] (→ page 114) adjustment is set to other than [OFF], [COLOR TEMPERATURE] is fixed to [USER1].

The color temperature numerical values are guidelines.

#### Adjusting desired white balance

- 1) Press ▲▼ to select [COLOR TEMPERATURE].
- 2) Press **♦** or the **<**ENTER> button.
  - The [COLOR TEMPERATURE] individual adjustment screen is displayed.
- 3) Press ◀▶ to select [USER1] or [USER2].
- 4) Press the <ENTER> button.
  - The [COLOR TEMPERATURE] screen is displayed.
- 5) Press ▲▼ to select [WHITE BALANCE].
- 6) Press the <ENTER> button.
  - The [WHITE BALANCE] screen is displayed.
- 7) Press ▲▼ to select [WHITE BALANCE HIGH] or [WHITE BALANCE LOW].
- 8) Press the <ENTER> button.

• The [WHITE BALANCE HIGH] screen or the [WHITE BALANCE LOW] screen is displayed.

- 9) Press ▲▼ to select [RED], [GREEN], or [BLUE].
- 10) Press **♦** to adjust the level.

Item	Operation	Adjustment	Range of adjustment
IDEDI	Press 🅨.	Deepens red.	
[RED]	Press ◀.	Weakens red.	[WHITE BALANCE HIGH]: 0 - +255 (factory default is
[GREEN]	Press 🅨.	Deepens green.	+255)
	Press ◀.	Weakens green.	[WHITE BALANCE LOW]: -127 - +127 (factory default is
[BLUE]	Press .	Deepens blue.	0)
	Press 4.	Weakens blue.	

#### Note

Adjust [COLOR TEMPERATURE] correctly. All colors will not be displayed properly unless adequate adjustment is made. If the adjustment
does not look suitable, you can press the <DEFAULT> button on the remote control to return the setting for the selected item only to the
factory default setting.

#### Adjusting desired white balance based on existing color temperature settings

- 1) Press  $\blacktriangle$  to select [COLOR TEMPERATURE].
- 2) Press () or the <ENTER> button.
   The [COLOR TEMPERATURE] individual adjustment screen is displayed.
- 3) Press **♦** to select an item other than [DEFAULT], [USER1], and [USER2].

#### 4) Press the <ENTER> button.

- The [CHANGE TO \*\*\*\*\*] screen is displayed.
- 5) Press ▲▼ to select [USER1] or [USER2].
  - The status of the color temperature changed is saved to the selected item.

#### 6) Press the <ENTER> button.

- The confirmation screen is displayed.
- 7) Press **♦** to select [OK], and press the **<**ENTER> button.
  - The [USER1] or [USER2] data is overwritten.
  - If you press **\** to select [CANCEL] and then press the **<**ENTER**>** button, the data will not be overwritten.
  - The [WHITE BALANCE HIGH] screen is displayed.

#### 8) Press ▲▼ to select [RED], [GREEN], or [BLUE].

#### 9) Press **♦** to adjust the level.

#### Note

Adjust [COLOR TEMPERATURE] correctly. All colors will not be displayed properly unless adequate adjustment is made. If the adjustment
does not look suitable, you can press the <DEFAULT> button on the remote control to return the setting for the selected item only to the
factory default setting.

When color temperature has been changed, the colors before and after the change will differ slightly.

#### Changing the name of [USER1] or [USER2]

- 1) Press ▲▼ to select [COLOR TEMPERATURE].
- 2) Press **♦** or the **<**ENTER> button.
  - The [COLOR TEMPERATURE] individual adjustment screen is displayed.
- 3) Press **♦** to select [USER1] or [USER2].
- 4) Press the <ENTER> button.
   The [COLOR TEMPERATURE] screen is displayed.
- 5) Press ▲▼ to select [COLOR TEMPERATURE NAME CHANGE].
- 6) Press the <ENTER> button.
  - The [COLOR TEMPERATURE NAME CHANGE] screen is displayed.
- 7) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the text, and press the <ENTER> button to enter the text.
- 8) Press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - The name set to color temperature is changed.

#### Note

When a name is changed, display of [USER1], [USER2] is also changed.

#### [GAMMA]

You can switch gamma mode.

#### 1) Press ▲▼ to select [GAMMA].

- 2) Press **♦** or the **<**ENTER> button.
  - The [GAMMA] individual adjustment screen is displayed.
- 3) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[DEFAULT]*1	Gamma mode unique to this projector.			
[USER1]	Uses the gamma data registered by the user.			
[USER2]	(Registration requires separate software. Consult your dealer.)			
[HDR ST2084-500]	Gamma mode compliant with SMPTE ST 2084 that assumes a highest luminance of 500 nt and supports HDR (High Dynamic Range).			
[HDR ST2084-1000] Gamma mode compliant with SMPTE ST 2084 that assumes a highest luminance of 1 000 supports HDR (High Dynamic Range).				
[HDR HLG] Gamma mode compliant with ARIB STD-B67 (HLG: Hybrid Log Gamma system) that support HDR (High Dynamic Range).				
[DICOM SIM.]	The picture becomes similar to that of DICOM standard.			

[1.0]	
[1.8]	Set so that images become as you like. [2.0] - [2.8] can be set in increments of 0.1.
[2.0] - [2.8]	

\*1 When [PICTURE MODE] is set to [DYNAMIC], [USER], or [DICOM SIM.], [DEFAULT] cannot be selected.

#### Note

• DICOM is an abbreviation of "Digital Imaging and COmmunication in Medicine" and is a standard for medical imaging devices. Although the DICOM name is used, the projector is not a medical device, and should not be used for purposes such as diagnosis of display images.

#### Changing the name of [USER1] or [USER2]

- 1) Press ▲▼ to select [GAMMA].
- 2) Press **♦** or the **<**ENTER> button.
  - The [GAMMA] individual adjustment screen is displayed.
- 3) Press ◀▶ to select [USER1] or [USER2].
- 4) Press the <ENTER> button.
  - The [GAMMA] screen is displayed.
- 5) Press the <ENTER> button.
  - The [GAMMA NAME CHANGE] screen is displayed.
- 6) Press ▲▼◀▶ to select the text, and press the <ENTER> button to enter the text.
- 7) Press  $\blacktriangle \forall \blacklozenge \flat$  to select [OK], and press the <ENTER> button.
  - The selected gamma name is changed.

#### Note

• When a name is changed, display of [USER1], [USER2] is also changed.

#### [SYSTEM DAYLIGHT VIEW]

You can correct the image to the optimal vividness even if it is projected under a bright light.

- 1) Press ▲▼ to select [SYSTEM DAYLIGHT VIEW].
- 2) Press **♦** or the **<**ENTER> button.
  - The [SYSTEM DAYLIGHT VIEW] individual adjustment screen is displayed.
- 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	No correction.	
[1] - [6]	Corrects the vividness of the image. The larger the value, the stronger the correction.	

### [SHARPNESS]

You can adjust the sharpness of the projected image.

- 1) Press ▲▼ to select [SHARPNESS].
- 2) Press **♦** or the **<**ENTER> button.

• The [SHARPNESS] individual adjustment screen is displayed.

3) Press **♦** to adjust the level.

Operation	Adjustment	Range of adjustment
Press .	Contours become sharper.	0 - +15
Press ◀.	Press 4. Contours become softer.	

#### Note

## [NOISE REDUCTION]

You can reduce noises when the input image is degraded and noise is occurring in the image signal.

#### 1) Press ▲▼ to select [NOISE REDUCTION].

- 2) Press **♦** or the **<**ENTER> button.
  - The [NOISE REDUCTION] individual adjustment screen is displayed.

#### 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	No correction.	
[1]	Slightly corrects the noise.	
[2]	Moderately corrects the noise.	
[3]	Strongly corrects the noise.	

#### Attention

• When this is set for an input signal with less noise, the image may look different from what it originally was. In such a case, set it to [OFF].

### [DYNAMIC CONTRAST]

Light adjustment of the light source and signal compensation are performed automatically according to the image to make the contrast optimum for the image.

#### 1) Press ▲▼ to select [DYNAMIC CONTRAST].

- 2) Press **♦** or the **<**ENTER> button.
  - The [DYNAMIC CONTRAST] individual adjustment screen is displayed.

#### 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the dynamic contrast function.			
[1]	Adjusts the light source and compensates signals to a small extent.			
[2]	djusts the light source and compensates signals to a moderate extent.			
[3]	Adjusts the light source and compensates signals to a large extent.			
[USER]	Set any desired correction. Refer to "Performing desired correction" (→ page 98) for details.			

#### Performing desired correction

#### 1) Press ▲▼ to select [DYNAMIC CONTRAST].

2) Press **♦** or the **<**ENTER> button.

• The [DYNAMIC CONTRAST] individual adjustment screen is displayed.

- 3) Press **♦** to select [USER].
- 4) Press the <ENTER> button.
  - The [DYNAMIC CONTRAST] screen is displayed.

#### 5) Press $\blacktriangle \blacksquare$ to select the item to set.

- The items of the detailed settings will switch each time you press **4**.
- Press the <ENTER> button when [MULTI PROJECTOR SYNC] is selected.

Setting item		Details	
	[OFF]	Does not adjust the light source.	
[AUTO CONTRAST] (Automatic light source adjustment)	[1] - [255]	The higher the value, the stronger the light adjustment of the light source. Can be set in increments of 1.	
[BRIGHT SIGNAL LEVEL] (Setting of the brightness level of the signal to start the light adjustment) [6%] - [50%]		Adjusts the light source when the brightness level of the video signal being input gets lower than the set value. The higher the value, the larger the range to perform the light adjustment of the light source. Can be set in increments of 1 %. (Factory setting: 30 %)	
	[DISABLE]	Does not turn off the light source.	
[LIGHTS OUT TIMER] (Time setting until the light turns off)	[0.0s] - [10.0s]	Turns off the light source when the brightness level of the video signal being input goes under the value set in [LIGHTS OUT SIGNAL LEVEL]. Select an item from [0.0s] - [4.0s], [5.0s], [7.0s], or [10.0s]. [0.0s] - [4.0s] can be selected in increments of 0.5.	
[LIGHTS OUT SIGNAL LEVEL] (Setting of the brightness level of the signal to turn off the light)	[0%] - [5%]	Set the level of the brightness of the video signal to turn off the lig source with [LIGHTS OUT TIMER]. Can be set in increments of 1 %. (Factory setting: 0 %)	
[MANUAL INTENSITY] (Manual light source adjustment)		The larger the value, the stronger the correction. Can be set in increments of 1. (Factory setting: 255)	
	[OFF]	Does not compensate the signal.	
	[1]	Slightly compensates the signal.	
(Adjustment of signal compensation)	[2]	Moderately compensates the signal.	
	[3]	Strongly compensates the signal.	
[MULTI PROJECTOR SYNC]		<ul> <li>Sets the contrast synchronization function.</li> <li>This setting item is common with the following menu item.</li> <li>The [PROJECTOR SETUP] menu → [MULTI PROJECTOR SYNC]</li> <li>Refer to the [PROJECTOR SETUP] menu → [MULTI PROJECTOR SYNC] (→ page 173) for details.</li> </ul>	

#### Note

- [LIGHTS OUT SIGNAL LEVEL] cannot be set when [LIGHTS OUT TIMER] is set to [DISABLE].
- When [LIGHTS OUT TIMER] is set to anything other than [DISABLE], the following are the conditions to turn the light source back on again from the state that the light source has turned off by this function.
- When the brightness level of the video signal being input has exceeded the value set in [LIGHTS OUT SIGNAL LEVEL]
- When the input signal is gone
- When on-screen display such as menu screen (OSD) or input guide, a test pattern, or a warning message is displayed
- When the operating environment temperature is around 0 °C (32 °F) and the light source is forced to turn on due to warm-up
- The contrast will be maximized when [DYNAMIC GAMMA] is set to [3].
- The brightness control function and the dynamic contrast function will operate simultaneously, but the dynamic contrast function will not
  operate while measuring the brightness and the color.
- The contrast synchronization function is a function to display a combined screen with a balanced contrast by sharing the brightness level of the video signal input to each projector when a multi-display is constructed by combining the projected image of multiple projectors.

## [COLOR SPACE]

Set the color space used for the color representation of the image.

#### 1) Press $\blacktriangle \forall$ to select [COLOR SPACE].

- 2) Press **♦** or the **<**ENTER**>** button.
  - The [COLOR SPACE] individual adjustment screen is displayed.
- 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[NATIVE]	Displays the image with a color space unique to this projector.		
[ITU-709]	Displays the image with a color space compliant with the ITU-R BT.709 standard.		
[DCI-P3 emu.]	Displays the image with a color space close to DCI-P3.		
[ITU-2020 emu.]	Displays the image with a color space close to the ITU-R BT.2020 standard.		

#### Note

DCI-P3 is the specifications of the digital cinema color region defined by the Digital Cinema Initiatives (DCI).

## [SYSTEM SELECTOR]

The projector will automatically detect the input signal, but you can set the system method manually when an unstable signal is input. Set the system method matching the input signal.

#### 1) Press ▲▼ to select [SYSTEM SELECTOR].

2) Press the <ENTER> button.

#### 3) Press ▲▼ to select a system format.

• Available system formats vary depending on the input signal.

Terminal	System format		
<digital lan="" link=""> terminal, <hdmi 1="" in=""></hdmi></digital>	480/60i, 576/50i, 480/60p, or 576/50p signal	Select [AUTO], [RGB], or [YC <sub>B</sub> C <sub>R</sub> ].	
terminal, <hdmi 2="" in=""> terminal, <hdmi 3="" in=""> terminal, <hdmi 4="" in=""> terminal</hdmi></hdmi></hdmi>	Other movie-based signals	Select [AUTO], [RGB], or [YP <sub>B</sub> P <sub>R</sub> ].	
<dvi-d 1="" in=""> terminal, <dvi-d IN 2&gt; terminal, <dvi-d in<br="">3&gt; terminal, <dvi-d 4="" in=""> terminal</dvi-d></dvi-d></dvi-d </dvi-d>	480/60i, 576/50i, 480/60p, or 576/50p signal	Select [RGB] or $[YC_BC_R]$ .	
	Other movie-based signals	Select [RGB] or $[YP_BP_R]$ .	
<displayport 1="" in=""> terminal, <displayport 2="" in=""> terminal, <displayport 3="" in=""> terminal, <displayport 4="" in=""> terminal</displayport></displayport></displayport></displayport>	Movie-based signals	Select [AUTO], [RGB], or [YP <sub>B</sub> P <sub>R</sub> ].	

#### 4) Press the <ENTER> button.

#### Note

- For details of the types of video signals that can be used with the projector, refer to "List of compatible signals" (+ page 255).
- This may not function properly for some connected external devices.
- The selection item for the input signal to the <HDMI IN 1> terminal and the <HDMI IN 2> terminal can be selected when the optional Interface Board equipped with the HDMI input is installed in <SLOT 1>.
- The selection item for the input signal to the <HDMI IN 3> terminal and the <HDMI IN 4> terminal can be selected when the optional Interface Board equipped with the HDMI input is installed in <SLOT 2>.
- The selection item for the input signal to the <DVI-D IN 1> terminal and the <DVI-D IN 2> terminal can be selected when the optional Interface Board equipped with the DVI-D input is installed in <SLOT 1>.
- The selection item for the input signal to the <DVI-D IN 3> terminal and the <DVI-D IN 4> terminal can be selected when the optional Interface Board equipped with the DVI-D input is installed in <SLOT 2>.
- The selection item for the input signal to the <DisplayPort IN 1> terminal and the <DisplayPort IN 2> terminal can be selected when the
  optional Interface Board equipped with the DisplayPort input is installed in <SLOT 1>.
- The selection item for the input signal to the <DisplayPort IN 3> terminal and the <DisplayPort IN 4> terminal can be selected when the
  optional Interface Board equipped with the DisplayPort input is installed in <SLOT 2>.
- For the SDI input, the signal format can be set in detail in the [DISPLAY OPTION] menu → [SDI IN] (→ page 119).

## sRGB-compliant video

sRGB is an international standard (IEC61966-2-1) for color reproduction defined by IEC (International Electrotechnical Commission).

Set according to the following steps to reproduce more faithful, sRGB compliant colors.

#### 1) Set [COLOR MATCHING] to [OFF].

- Refer to [COLOR MATCHING] (
  page 114).
- 2) Display the [PICTURE] menu.
  - Refer to "[PICTURE] menu" (⇒ page 93).
- 3) Press ▲▼ to select [PICTURE MODE].
- 4) Press **♦** to set [NATURAL].
- 5) Press ▲▼ to select [COLOR].
- 6) Press the <DEFAULT> button on the remote control to set the factory default setting.
- 7) Follow Steps 5) to 6) to set [TINT], [COLOR TEMPERATURE], [GAMMA], and [SYSTEM DAYLIGHT VIEW] to the factory default settings.

## 100 - ENGLISH

#### Note

• sRGB is available for RGB signal input only.

## [POSITION] menu

On the menu screen, select [POSITION] from the main menu, and select an item from the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

#### Note

 When the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the <DIGITAL LINK/ LAN> terminal, adjust the shift and aspect from the menu of DIGITAL LINK output supported device first.

## [SHIFT]

Move the image position vertically or horizontally if the image projected on the screen is still out of position even when the positions of the projector and screen are correct.

- 1) Press  $\blacktriangle \lor$  to select [SHIFT].
- 2) Press the <ENTER> button.
  - The [SHIFT] screen is displayed.
- 3) Press ▲▼◀▶ to adjust the position.

Orientation	Operation	Adjustment	
Vertical (up and down) adjustment	Press ▲.	The image position moves up.	
	Press ▼.	The image position moves down.	
Horizontal (right and left) adjustment	Press ▶.	The image position moves to the right.	
	Press ◀.	The image position moves to the left.	

#### Note

 For the portrait setting, image position is moved horizontally when "Vertical (up and down) adjustment" is made. Image position is moved vertically when "Horizontal (right and left) adjustment" is made.

## [ASPECT]

You can switch the aspect ratio of the image.

The aspect ratio is switched within the screen range selected in the [DISPLAY OPTION] menu  $\rightarrow$  [SCREEN SETTING]  $\rightarrow$  [SCREEN FORMAT]. Set [SCREEN FORMAT] first. ( $\Rightarrow$  page 115)

- 1) Press ▲▼ to select [ASPECT].
- 2) Press **♦** or the **<**ENTER> button.
  - The [ASPECT] individual adjustment screen is displayed.

#### 3) Press **♦** to switch the item.

• The items will switch each time you press the button.

[DEFAULT]	Displays images without changing the aspect ratio of the input signals.
[THROUGH]	Displays images without changing the resolution of the input signals.

## 102 - ENGLISH

[16:9]	Displays images with the aspect ratio converted to 16:9 when standard signals are input <sup>*1</sup> . When wide-screen signals are input <sup>*2</sup> , the images are displayed without changing the aspect ratio.	
[4:3]	Displays images without changing the aspect ratio when standard signals are input <sup>*1</sup> . When wide- screen signals are input <sup>*2</sup> , and [4:3] is selected in [SCREEN FORMAT], the image is displayed by converting the aspect ratio to 4:3. When anything other than [4:3] is selected in [SCREEN FORMAT], the images are reduced to be displayed without changing input aspect ratio so that the images will fit in the 4:3 screen.	
[H FIT]	Displays images using the entire width of the screen range selected in [SCREEN FORMAT]. When signals have the aspect ratio vertically longer than the screen aspect ratio selected in [SCREEN FORMAT], the images are displayed with the top and bottom parts cut off.	
[V FIT]	Displays images using the entire height of the screen range selected in [SCREEN FORMAT]. V signals have the aspect ratio horizontally longer than the aspect ratio of the screen selected in [SCREEN FORMAT], the images are displayed with the right and left parts cut off.	
[HV FIT]	Displays images in the entire screen range selected in [SCREEN FORMAT]. When the aspect ratio of the input signals differs from that of the screen range, the images are displayed with the aspect ratio converted to that of the screen selected in [SCREEN FORMAT].	

\*1 Standard signals are input signals with an aspect ratio of 4:3 or 5:4.

\*2 Wide-screen signals are input signals with an aspect ratio of 16:10, 16:9, 15:9 or 15:10.

#### Note

• If an aspect ratio which is different from the aspect ratio for the input signals is selected, the images will appear differently from the originals. Be careful of this when selecting the aspect ratio.

- If using the projector in places such as cafes or hotels to display programs for a commercial purpose or for public presentation, note that adjusting the aspect ratio or using the zoom function to change the screen images may be an infringement of the rights of the original copyright owner for that program under copyright protection laws. Take care when using a function of the projector such as the aspect ratio adjustment and zoom function.
- If conventional (normal) 4:3 images which are not wide-screen images are displayed on a wide screen, the edges of the images may not be visible or they may become distorted. Such images should be viewed as with an aspect ratio of 4:3 in the original format intended by the creator of the images.
- Image is displayed as the whole projected image is set to 3 840 x 2 400 dots when [ASPECT] is set to [THROUGH] while the [ADVANCED MENU] menu → [QUAD PIXEL DRIVE] is set to [ON].

### [ZOOM]

You can adjust the image size.

The adjustments in [ZOOM] will differ depending on the setting of the [POSITION] menu  $\rightarrow$  [ASPECT].

#### When [ASPECT] is set to other than [DEFAULT] and [THROUGH]

- 1) Press ▲▼ to select [ZOOM].
- 2) Press the <ENTER> button.

• The [ZOOM] screen is displayed.

3) Press ▲▼ to select [INTERLOCKED].

#### 4) Press **I** to switch the item.

[OFF]	Sets the [VERTICAL] and [HORIZONTAL] zoom ratio.	
[00]	Uses [BOTH] to set zoom ratio. Image can be enlarged or reduced vertically and horizontally at the same magnification.	

#### 5) Press ▲▼ to select [VERTICAL] or [HORIZONTAL].

• If [ON] is selected, select [BOTH].

#### 6) Press **♦** to adjust.

#### Note

- When [ASPECT] is set to [THROUGH], [ZOOM] cannot be adjusted.
- Zoom ratio less than 100 cannot be set when the video signal fulfilling one of the following conditions is being input.
- Video signal with resolution exceeding 1 920 x 1 200 dots
- Video signal with dot clock frequency exceeding 162 MHz

#### When [ASPECT] is set to [DEFAULT]

1) Press ▲▼ to select [ZOOM].

- 2) Press the <ENTER> button.
  - The [ZOOM] screen is displayed.
- 3) Press ▲▼ to select [MODE].
- 4) Press  $\triangleleft$  to switch the item.

[INTERNAL]	Enlarges the size within the aspect range set with [SCREEN FORMAT].
[FULL]	Enlarges or reduces the size using the entire display area set with [SCREEN FORMAT].

#### 5) Press ▲▼ to select [INTERLOCKED].

#### 6) Press **♦** to switch the item.

[OFF]	Sets the [VERTICAL] and [HORIZONTAL] zoom ratio.	
[ON]	Uses [BOTH] to set zoom ratio. Image can be enlarged or reduced vertically and horizontally at the same magnification.	

#### 7) Press $\blacktriangle$ to select [VERTICAL] or [HORIZONTAL].

• If [ON] is selected, select [BOTH].

#### 8) Press **♦** to adjust.

#### Note

- When [ASPECT] is not set to [DEFAULT], [MODE] is not displayed.
- Zoom ratio less than 100 cannot be set when the video signal fulfilling one of the following conditions is being input.
  - Video signal with resolution exceeding 1 920 x 1 200 dots
  - Video signal with dot clock frequency exceeding 162 MHz

## [GEOMETRY]

You can correct various types of distortion in a projected image.

Unique image processing technology enables projection of a square image on a special screen shape.

#### 1) Press $\blacktriangle \forall$ to select [GEOMETRY].

#### 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Does not perform geometric adjustment.		
[KEYSTONE]	Adjusts any trapezoidal distortion in the projected image.		
[CORNER CORRECTION]	Adjusts any distortion in the four corners of the projected image.		
[CURVED CORRECTION]	Adjusts any curved distortion in the projected image.		
[PC-1]*1			
[PC-2]*1	Performs geometric adjustment using a computer.		
[PC-3]*1			


\*1 Advanced skills are necessary to use a computer to control geometric adjustment. Consult your dealer. Up to three geometric adjustments performed using the computer can be saved.

#### Setting [KEYSTONE] or [CURVED CORRECTION]

- 1) Press  $\blacktriangle \forall$  to select [GEOMETRY].
- 2) Press **♦** to select [KEYSTONE] or [CURVED CORRECTION].
- 3) Press the <ENTER> button.

• The [GEOMETRY:KEYSTONE] or [GEOMETRY:CURVED CORRECTION] screen is displayed.


- 4) Press  $\blacktriangle \nabla$  to select the item to adjust.
- 5) Press **♦** to adjust.



#### Setting [CORNER CORRECTION]

- 1) Press  $\blacktriangle \blacksquare$  to select [GEOMETRY].
- 2) Press **♦** to select [CORNER CORRECTION].
- 3) Press the <ENTER> button.
  - The [GEOMETRY:CORNER CORRECTION] screen is displayed.
- 4) Press  $\blacktriangle \forall$  to select the item to adjust, and press the <ENTER> button.
- 5) Press  $\blacktriangle \lor \blacklozenge \lor$  to adjust.

#### Chapter 4 Settings — [POSITION] menu



#### Note

- The menu or logo may run off the screen when [GEOMETRY] is set.
- If [EDGE BLENDING] (
   page 108) adjustment and [GEOMETRY] are used together, correct edge blending adjustment may not be
   possible in certain environments.
- The optional Upgrade Kit (Model No.: ET-UK20) can be used to expand the correctable range. To purchase the product, consult your dealer.
- The [GEOMETRY] setting is disabled in the following cases, and the geometric adjustment function cannot be used.
   When the [ADVANCED MENU] menu → [QUAD PIXEL DRIVE] is set to [QFF]
- When the [ADVANCED MENU] menu → [QUAD PIXEL DRIVE] is set to [OFF]
   When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to anything other than [OFF]
- The image may disappear for a moment or may be disrupted while performing adjustment, but it is not a malfunction.

## [ADVANCED MENU] menu

On the menu screen, select [ADVANCED MENU] from the main menu, and select an item from the submenu.

Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

### [DIGITAL CINEMA REALITY]

The picture quality is enhanced by raising the vertical resolution further by performing the cinema processing when the 1080/50i or 1080/60i signal is input.

#### 1) Press ▲▼ to select [DIGITAL CINEMA REALITY].

#### 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically detects the input signal and performs cinema processing.		
[OFF]	Does not perform cinema processing.		
[30p FIXED]	When 1080/60i signal is input	Derferme ferred sincere anecesing (2:2 multideum)	
[25p FIXED]	When 1080/50i signal is input	Performs forced cinema processing (2:2 pulldown).	

#### Note

• In [DIGITAL CINEMA REALITY], the picture quality will degrade when a signal other than the 2:2 pulldown is set as [25p FIXED] or [30p FIXED]. (Vertical resolution will degrade.)

- [DIGITAL CINEMA REALITY] is fixed to [OFF] in the following cases.
- When [FRAME RESPONSE] is set to [FAST]
- When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying an image in simultaneous format
- The [DIGITAL CINEMA REALITY] setting is disabled and fixed to [OFF] when [DIGITAL CINEMA REALITY] is set to anything other than [OFF] and the following setting or operation is performed.
  - Set [FRAME RESPONSE] to [FAST].
  - Set the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] to [AUTO(x2-speed)] or [AUTO(x4-speed)] and display an image in simultaneous format.

## [BLANKING]

You can adjust the blanking width if there are noises at the edge of the screen or the image is slightly running out from the screen while an image from the VCR or other devices is projected.

#### 1) Press ▲▼ to select [BLANKING].

- 2) Press the <ENTER> button.
  - The [BLANKING] adjustment screen is displayed.

#### 3) Press ▲▼ to select [UPPER], [LOWER], [LEFT], or [RIGHT].

• The blanking width can be adjusted to a desired shape using a computer when [CUSTOM MASKING] is selected and set to anything other than [OFF] ([PC-1], [PC-2], [PC-3]). Up to three blanking settings adjusted using the computer can be saved.

[CUSTOM MASKING] uses the masking function of the Panasonic computer application.

To use the [CUSTOM MASKING] function, the optional Upgrade Kit (Model No.: ET-UK20) is required. To purchase the product, consult your dealer.

#### 4) Press **♦** to adjust the blanking width.

Blanking correction	Item	Operation	Adj	ustment	Range of adjustment
		Press ◀.	The blanking zone moves upward.		
Top of the screen	[UPPER]	Press ▶.	The blanking zone moves downward.		
		Press .	The blanking zone moves upward.		Top and bottom 0 - 2 398
Bottom of the screen	[LOWER]	Press ◀.	The blanking zone moves downward.		
Left side of the [LEF] screen		Press .	The blanking zone moves to the right.		
	[LEFT]	Press ◀.	The blanking zone moves to the left.		
Right side of the screen		Press ◀.	The blanking zone moves to the right.		Left and right 0 - 3 838
	[RIGHT]	Press ▶.	The blanking zone moves to the left.		

#### Chapter 4 Settings — [ADVANCED MENU] menu

#### Note

• The upper limit of the adjustment range may be restricted so that the entire projected image is not covered by blanking width.

• The [CUSTOM MASKING] setting in [BLANKING] is disabled in the following cases, and the masking function of Panasonic computer application cannot be used.

- When [QUAD PIXEL DRIVE] is set to [OFF]

- When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying an image in simultaneous format

## [EDGE BLENDING]

The overlapping area is made seamless by creating inclination in the brightness in the overlapped area when structuring a multi-display screen by combining the projected images from multiple projectors.

#### 1) Press ▲▼ to select [EDGE BLENDING].

#### 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Sets the edge blending function to off.		
[ON]	lse the setting value preset in the projector for the inclination of the edge blending area.		
[USER]	Use the user-setting value for the inclination of the edge blending area. (Configuration/registration requires separate software. Consult your dealer.)		

• When anything other than [OFF] is selected, proceed to Step 3).

#### 3) Press the <ENTER> button.

The [EDGE BLENDING] screen is displayed.

#### 4) Press $\blacktriangle \forall$ to specify the location to be corrected.

- When joining at top: Set [UPPER] to [ON]
- When joining at bottom: Set [LOWER] to [ON]
- When joining at left: Set [LEFT] to [ON]
- When joining at right: Set [RIGHT] to [ON]
- 5) Press **♦** to switch to [ON].
- 6) Press  $\blacktriangle \forall$  to select [START] or [WIDTH].
- 7) Press **(**) to adjust the starting position or correction width.

## 108 - ENGLISH

#### 8) Press ▲▼ to select [MARKER].

#### 9) Press **I** to switch to [ON].

 A marker for image position adjustment is displayed. The position where the red and green lines overlap for the projectors to be joined will be the optimal point. Make sure to set the correction width for the projectors to be joined with the same value. Optimal joining is not possible with projectors that have different correction widths.

> The optimal point is the point at which these lines overlap. Green line Red line

#### 10) Press ▲▼ to select [BRIGHTNESS ADJUST].

#### 11) Press the <ENTER> button.

- The [BRIGHTNESS ADJUST] screen is displayed.
- By setting [AUTO TESTPATTERN] to [ON] on the [EDGE BLENDING] screen, the black test pattern is displayed when you enter the [BRIGHTNESS ADJUST] screen.


#### 12) Press ▲▼ to select [NON-OVERLAPPED BLACK LEVEL].

- 13) Press the <ENTER> button.
  - The [NON-OVERLAPPED BLACK LEVEL] screen is displayed.
  - [RED], [GREEN], and [BLUE] can be adjusted individually if [INTERLOCKED] is set to [OFF].

#### 14) Press $\blacktriangle$ to select an item, and press $\blacklozenge$ to adjust the setting.

- Once the adjustment is completed, press the <MENU> button to return to the [BRIGHTNESS ADJUST] screen.
- 15) Press ▲▼ to select [UPPER], [LOWER], [LEFT], or [RIGHT] in [BLACK BORDER WIDTH].
- 16) Press **♦** to set the region (width) of the [BLACK BORDER WIDTH] adjustment.
- 17) Press ▲▼ to select [UPPER KEYSTONE AREA], [LOWER KEYSTONE AREA], [LEFT KEYSTONE AREA], or [RIGHT KEYSTONE AREA].
- 18) Press ◀▶ to adjust the tilt of the border between [NON-OVERLAPPED BLACK LEVEL] and [BLACK BORDER LEVEL].
- 19) Press ▲▼ to select [BLACK BORDER LEVEL].
- 20) Press the <ENTER> button.
  - The [BLACK BORDER LEVEL] screen is displayed.
  - [RED], [GREEN], and [BLUE] can be adjusted individually if [INTERLOCKED] is set to [OFF].
- 21) Press  $\blacktriangle \lor$  to select an item, and press  $\blacklozenge \lor$  to adjust the setting.
  - Once the adjustment is completed, press the <MENU> button to return to the [BRIGHTNESS ADJUST] screen.
- 22) Press ▲▼ to select [UPPER], [LOWER], [LEFT], or [RIGHT] for [OVERLAPPED BLACK LEVEL].
- 23) Press the <ENTER> button.
  - The [OVERLAPPED BLACK LEVEL] screen is displayed.
  - [RED], [GREEN], and [BLUE] can be adjusted individually if [INTERLOCKED] is set to [OFF].

#### 24) Press ▲▼ to select an item, and press ◀▶ to adjust the setting.



#### Note

- [BRIGHTNESS ADJUST] is a function that makes the increased brightness in black level of the overlapping image area difficult to notice when [EDGE BLENDING] is used to configure multiple screens. The optimal point of correction is set by adjusting [NON-OVERLAPPED BLACK LEVEL] so the black level of the overlapping image area will be the same level as the non-overlapping area. If the border area of the part where the image is overlapping and the non-overlapping part gets brighter after adjusting [NON-OVERLAPPED BLACK LEVEL], adjust the width of the top, bottom, left, or right. Adjust [BLACK BORDER LEVEL] when the width adjustment makes only the border area darker.
- The joining part may look discontinuous depending on the position you are looking from when a screen with high gain or rear screen is used.
  When configuring multiple screens using both horizontal and vertical edge blending, adjust [OVERLAPPED BLACK LEVEL] first before
- making adjustments in Step 12). Adjustment method is same as the procedure of [NON-OVERLAPPED BLACK LEVEL].
  If only horizontal or vertical edge blending is used, set all items in [OVERLAPPED BLACK LEVEL] to 0.
- The [AUTO TESTPATTERN] setting changes synchronizing with [AUTO TESTPATTERN] of [COLOR MATCHING].
- Adjustment of the tilt of the border between [NON-OVERLAPPED BLACK LEVEL] and [BLACK BORDER LEVEL] is a function to perform the adjustment of [GEOMETRY] (> page 104) together with the edge blending. If [NON-OVERLAPPED BLACK LEVEL] is tilted by correcting the keystone from [KEYSTONE] in [GEOMETRY], perform Steps 17) and 18) to adjust the edge blending according to the shape of [NON-OVERLAPPED BLACK LEVEL].

## [FRAME RESPONSE]

Set image frame delay.

#### 1) Press ▲▼ to select [FRAME RESPONSE].

#### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[NORMAL]	Standard setting.
[FAST] <sup>*1</sup>	Simplifies the image processing to reduce image frame delay.
[FIXED]*2	Sets image frame delay to be constant regardless of the image position or magnification.

\*1 [FAST] can be set in following cases.

When the input signal is an interlaced signal

When the [DISPLAY OPTION] menu  $\rightarrow$  [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying an image in simultaneous format

\*2 Only when moving image signals and still image signals with the vertical scanning frequency of 50 Hz or 60 Hz are input

#### Note

• [FRAME RESPONSE] is fixed to [NORMAL] in the following cases.

- While in the four-screen display mode

The four-screen display mode can be canceled by setting the [MULTI DISPLAY] menu  $\rightarrow$  [MULTI DISPLAY MODE] to [OFF]. ( $\Rightarrow$  page 183)

• The [FRAME RESPONSE] setting is disabled and fixed to [NORMAL] when [FRAME RESPONSE] is set to anything other than [NORMAL] and the following setting or operation is performed.

- Set the [MULTI DISPLAY] menu  $\rightarrow$  [MULTI DISPLAY MODE] to anything other than [OFF] and display the four-screen display.

 Input the video signals with the vertical synchronization signals completely matching to each input terminal when displaying the image in simultaneous format while [FRAME RESPONSE] is set to [FAST]. The proper image may not be projected when the vertical synchronization signals do not match. In such case, switch the setting to [NORMAL].

• The [DIGITAL CINEMA REALITY] and [FRAME CREATION] settings are disabled and fixed to [OFF] when [FRAME RESPONSE] is set to [FAST].

## [FRAME CREATION]

Set the amount of image frame interpolation.

The image with fast movement can be displayed more smoothly by automatically generating the intermediate frame from the previous and next frame.

#### 1) Press ▲▼ to select [FRAME CREATION].

#### 2) Press the <ENTER> button.

• The [FRAME CREATION] screen is displayed.

#### 3) Press ▲▼ to select [FRAME CREATION MODE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the frame creation function.
[1]	Sets the amount of interpolation weaker.
[2]	Sets the amount of interpolation midway.
[3]	Sets the amount of interpolation stronger.

#### Note

- The effect may be difficult to notice depending on the image.
- Switch the setting when the image looks unnatural due to delay of image or generation of noise.
- [FRAME CREATION] is fixed to [OFF] in the following cases.
- When [FRAME RESPONSE] is set to [FAST]
- When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying an image in simultaneous format
- While in the four-screen display mode
- The four-screen display mode can be canceled by setting the [MULTI DISPLAY] menu  $\rightarrow$  [MULTI DISPLAY MODE] to [OFF]. ( $\Rightarrow$  page 183)
- When the internal test patter is displayed.
- The [FRAME CREATION] setting is disabled and fixed to [OFF] when [FRAME CREATION] is set to anything other than [OFF] and the following setting or operation is performed.
  - Set [FRAME RESPONSE] to [FAST].
  - Set the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] to [AUTO(x2-speed)] or [AUTO(x4-speed)] and display an image in simultaneous format.
  - Set the [MULTI DISPLAY] menu  $\rightarrow$  [MULTI DISPLAY MODE] to anything other than [OFF] and display the four-screen display.

## Setting [FILM DETECTION]

Set the film detection function to enhance the video resolution by determining if it is a content that the telecine is performed on the input signal.

#### 1) Press ▲▼ to select [FRAME CREATION].

- 2) Press the <ENTER> button.
  - The [FRAME CREATION] screen is displayed.
- 3) Press ▲▼ to select [FRAME CREATION MODE].
- 4) Press **♦** to select a mode from [1], [2], or [3].
- 5) Press  $\blacktriangle \lor$  to select [FILM DETECTION].
- 6) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[OFF]	Disables the film detection function.
ION1	Enables the film detection function. The video resolution is enhanced for the contents that telecine is performed on the input signal.

#### Note

• The video resolution is not changed even if [FILM DETECTION] is set to [ON] for the contents that the telecine is not performed on the input signal.

The contents which telecine is performed is the contents that the film image is converted to the video image.

[FILM DETECTION] cannot be set when a signal for the content with vertical scanning frequency of 30 Hz, 25 Hz, or 24 Hz is input.

## [QUAD PIXEL DRIVE]

Set the enable/disable of the QUAD PIXEL DRIVE function to enhance the resolution of the projected image.

#### 1) Press ▲▼ to select [QUAD PIXEL DRIVE].

#### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[ON]	Enables the QUAD PIXEL DRIVE function.
[OFF]	Disables the QUAD PIXEL DRIVE function.

#### Note

• [QUAD PIXEL DRIVE] is fixed to [ON] in the following cases.

- When the [POSITION] menu  $\rightarrow$  [GEOMETRY] is set to anything other than [OFF]
- When [CUSTOM MASKING] in [BLANKING] is set to anything other than [OFF] ([PC-1], [PC-2], [PC-3])
- To use the [CUSTOM MASKING] function, the optional Upgrade Kit (Model No.: ET-UK20) is required. To purchase the product, consult your dealer.
- When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)], and the following image in simultaneous format is displayed
- 3840 x 2160/60, 3840 x 2160/50, 4096 x 2160/60, 4096 x 2160/50
- While in the four-screen display mode

The four-screen display mode can be canceled by setting the [MULTI DISPLAY] menu  $\rightarrow$  [MULTI DISPLAY MODE] to [OFF]. ( $\Rightarrow$  page 183)

• [QUAD PIXEL DRIVE] is fixed to [OFF] in the following cases.

When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)], and the following image in simultaneous format is displayed

1080/60p, 1080/50p, 1366 x 768/50, 1366 x 768/60, 1400 x 1050/50, 1400 x 1050/60, 1920 x 1080/50, 1920 x 1080/60, 1920 x 1200/50, 1920 x 1200/60RB

- When the focus test pattern is displayed using the [TEST PATTERN] menu
   To enable the QUAD PIXEL DRIVE function while displaying the focus test pattern, set [QUAD PIXEL DRIVE] to [ON] again while displaying the focus pattern.
- [QUAD PIXEL DRIVE] is fixed to [ON] when the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] and displaying the following image in simultaneous format while [QUAD PIXEL DRIVE] is set to [OFF].
   3840 x 2160/60, 3840 x 2160/50, 4096 x 2160/60, 4096 x 2160/50
- [QUAD PIXEL DRIVE] is fixed to [OFF] when the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying the following image in simultaneous format while [QUAD PIXEL DRIVE] is set to [ON].
   1080/60p, 1080/50p, 1366 x 768/50, 1366 x 768/60, 1400 x 1050/50, 1400 x 1050/60, 1920 x 1080/50, 1920 x 1080/60, 192
- [QUAD PIXEL DRIVE] is fixed to [ON] when the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display while [QUAD PIXEL DRIVE] is set to [OFF].
- When [QUAD PIXEL DRIVE] is set to [ON], the [DISPLAY OPTION] menu → [ON-SCREEN DISPLAY] → [OSD SIZE] cannot be set.

## [RASTER POSITION]

This will allow the position of the image to move within the display area arbitrarily when the input image is not using the whole display area.

#### 1) Press ▲▼ to select [RASTER POSITION].

- 2) Press the <ENTER> button.
  - The [RASTER POSITION] screen is displayed.

#### 3) Press ▲▼◀▶ to adjust the position.

#### Note

• The range that can be moved is limited when the projected image is smaller than the display size of the menu screen (OSD).

## [DISPLAY LANGUAGE] menu

On the menu screen, select [DISPLAY LANGUAGE] from the main menu, and display the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

### Changing the display language

You can select the language of the on-screen display.

1) Press ▲▼ to select the display language and press the <ENTER> button.

DISPLAY LANGUAGE
ENGLISH
DEUTSCH
FRANÇAIS
ESPAÑOL
ITALIANO
PORTUGUÊS
日本語
中文
РУССКИЙ
한국어
SELECT
SET SET

- Various menus, settings, adjustment screens, control button names, etc., are displayed in the selected language.
- The language can be changed to English, German, French, Spanish, Italian, Portuguese, Japanese, Chinese, Russian, or Korean.

Note

<sup>•</sup> The on-screen display language is set to English in the factory default setting as well as when the [PROJECTOR SETUP] menu  $\rightarrow$  [INITIALIZE]  $\rightarrow$  [ALL USER DATA] is executed.

# [DISPLAY OPTION] menu

On the menu screen, select [DISPLAY OPTION] from the main menu, and select an item from the submenu.

Refer to "Navigating through the menu" (→ page 88) for the operation of the menu screen.

## [COLOR MATCHING]

Correct the color difference between projectors when using multiple projectors simultaneously.

#### Adjusting the color matching as desired

#### 1) Press $\blacktriangle \forall$ to select [COLOR MATCHING].

#### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[OFF]	Color matching adjustment is not carried out.
[3COLORS]	Adjusts the three colors [RED], [GREEN], or [BLUE].
[7COLORS]	Adjusts the seven colors [RED], [GREEN], [BLUE], [CYAN], [MAGENTA], [YELLOW], or [WHITE].
[MEASURED]	Refer to "Adjusting the color matching using a colorimeter" (+ page 114) for details about this mode.

- 3) Select [3COLORS] or [7COLORS], and press the <ENTER> button.
   The [3COLORS] or [7COLORS] screen is displayed.
- 4) Press ▲▼ to select [RED], [GREEN], or [BLUE] ([RED], [GREEN], [BLUE], [CYAN], [MAGENTA], [YELLOW], or [WHITE] when [7COLORS] is selected).
- 5) Press the <ENTER> button.
  - The [3COLORS:RED], [3COLORS:GREEN], or [3COLORS:BLUE] screen is displayed. When [7COLORS] is selected, the [7COLORS:RED], [7COLORS:GREEN], [7COLORS:BLUE], [7COLORS:CYAN], [7COLORS:MAGENTA], [7COLORS:YELLOW], or [7COLORS:WHITE] screen is displayed.
  - By setting [AUTO TESTPATTERN] to [ON], the test pattern for the selected color is displayed.
- 6) Press ▲▼ to select [RED], [GREEN], or [BLUE].
- 7) Press **♦** to adjust.
  - The adjustment value changes between 0 and 2 048.

#### Note

• Operation when correcting the adjustment color

When the correction color same as the adjustment color is changed: The luminance of the adjustment color changes. When correction color red is changed: Red is added to or subtracted from the adjustment color. When correction color green is changed: Green is added to or subtracted from the adjustment color.

- When correction color blue is changed: Blue is added to or subtracted from the adjustment color.
  Since advanced skills are necessary for the adjustment, this adjustment should be carried out by a person who is familiar with the projector or by a service person.
- Pressing the <DEFAULT> button on the remote control will restore the factory default settings for all items.
- When [COLOR MATCHING] is set to other than [OFF], [COLOR TEMPERATURE] is fixed to [USER1].

#### Adjusting the color matching using a colorimeter

Use a colorimeter that can measure chromaticity coordinates and luminance to change the colors [RED], [GREEN], [BLUE], [CYAN], [MAGENTA], [YELLOW], or [WHITE] to desired colors.

- 1) Press ▲▼ to select [COLOR MATCHING].
- 2) Press **♦** to select [MEASURED].
- 3) Press the <ENTER> button.
  - The [MEASURED MODE] screen is displayed.
- 4) Press ▲▼ to select [MEASURED DATA].

- 5) Press the <ENTER> button.
  - The [MEASURED DATA] screen is displayed.
- 6) Measure the current luminance (Y) and the chromaticity coordinates (x, y) using the colorimeter.
- 7) Press  $\blacktriangle \lor$  to select a color, and press  $\blacklozenge \lor$  to adjust the setting.
  - Set [AUTO TESTPATTERN] to [ON] to display a test pattern of selected colors.
- 8) Once all the input is completed, press the <MENU> button.
  - The [MEASURED MODE] screen is displayed.
  - When [MEASURED] is selected in Step 2), proceed to Step 9) and enter the coordinates of desired colors.
- 9) Press  $\blacktriangle \forall$  to select [TARGET DATA].
- 10) Press the <ENTER> button.
  - The [TARGET DATA] screen is displayed.
- 11) Press  $\blacktriangle \blacksquare$  to select a color and press  $\blacklozenge \blacksquare$  to input coordinates for desired colors.
  - By setting [AUTO TESTPATTERN] to [ON], the test pattern for the selected color is displayed.

12) Once all the input is completed, press the <MENU> button.

#### Note

- Colors are not displayed properly when target data is a color outside the region of this projector.
- Set the [AUTO TESTPATTERN] to [ON] to automatically display a test pattern for use in adjusting the selected adjustment colors.
- [AUTO TESTPATTERN] settings change together with the [AUTO TESTPATTERN] of [EDGE BLENDING].
- Before using a colorimeter or similar instrument to measure measurement data, set [PICTURE MODE] to [DYNAMIC].
- A difference in the color coordinates of target data and measurement values obtained from an instrument may occur for certain instruments and measurement environments used.

## [LARGE SCREEN CORRECTION]

Corrects the phenomenon in which colors that appear lighter when viewed on a large screen viewed from a close distance compared to when viewed on an average screen size so that colors appear the same.

#### 1) Press ▲▼ to select [LARGE SCREEN CORRECTION].

2) Press **I** to switch the item.

[OFF]	Performs no correction.
[1]	Performs weak correction.
[2]	Performs strong correction.

## [SCREEN SETTING]

Set the screen size.

Correct to the optimum image position for the set screen when the aspect ratio of a projected image is changed. Set as necessary for the screen in use.

#### 1) Press ▲▼ to select [SCREEN SETTING].

#### 2) Press the <ENTER> button.

- The [SCREEN SETTING] screen is displayed.
- 3) Press **♦** to switch the [SCREEN FORMAT] item.
  - The items will switch each time you press the button.

[SCREEN FORMAT]	Range when [SCREEN POSITION] is selected
[16:10]	Cannot be adjusted.
[4:3]	Adjusts the horizontal position between -320 and 320.
[16:9]	Adjusts the vertical position between –120 and 120.

#### 4) Press $\blacktriangle \forall$ to select [SCREEN POSITION].

- [SCREEN POSITION] cannot be selected or adjusted when [SCREEN FORMAT] is set to [16:10].
- 5) Press **♦** to adjust [SCREEN POSITION].

## [AUTO SIGNAL]

Set whether to execute automatic setup of signals automatically.

The screen display position or signal level can be adjusted automatically without pressing the <AUTO SETUP> button on the remote control on each occasion if you input unregistered signals frequently at meetings, etc.

#### 1) Press ▲▼ to select [AUTO SIGNAL].

#### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[OFF]	Sets the auto signal function to off.
[ON]	Executes automatic setup automatically when images are changed to unregistered signals during projection.

## [AUTO SETUP]

Set this when adjusting a special signal or horizontally long (such as 16:9) signal.

#### Setting with [MODE]

- 1) Press ▲▼ to select [AUTO SETUP].
- 2) Press the <ENTER> button.
  - The [AUTO SETUP] screen is displayed.
- 3) Press ▲▼ to select [MODE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[DEFAULT]	Standard setting.
	Select this item when an image aspect ratio is a wide-screen signal, which does not meet the [DEFAULT] setting.

#### 5) Press the <ENTER> button.

 Automatic adjustment is executed. [PROGRESS] is displayed while in automatic adjustment. When completed, the screen returns to the [AUTO SETUP] screen.

#### Note

 Automatic adjustment can be executed when DVI-D/HDMI signal is input. It is necessary to install the optional Interface Board equipped with the corresponding input on the slot to input the DVI-D/HDMI signal directly without passing through the <DIGITAL LINK/LAN> terminal.

#### Adjusting position automatically

#### 1) Press ▲▼ to select [AUTO SETUP].

- 2) Press the <ENTER> button.
  - The [AUTO SETUP] screen is displayed.
- 3) Press  $\blacktriangle \lor$  to select [POSITION ADJUST].
- 4) Press  $\triangleleft$  to switch the item.

[ON]	Adjust the screen position and size when automatic setup is executed.
[OFF]	Does not perform automatic adjustment.

#### Adjusting signal level automatically

- 1) Press ▲▼ to select [AUTO SETUP].
- 2) Press the <ENTER> button.
  - The [AUTO SETUP] screen is displayed.

## 116 - ENGLISH

#### 3) Press $\blacktriangle \forall$ to select [SIGNAL LEVEL ADJUST].

#### 4) Press **♦** to switch the item.

[OFF]	Does not perform automatic adjustment.
[0N]	Adjusts black level (the [PICTURE] menu $\rightarrow$ [BRIGHTNESS]) and white level (the [PICTURE] menu $\rightarrow$ [CONTRAST]) when automatic setup is executed.

#### Note

• [SIGNAL LEVEL ADJUST] may not function properly unless a still image containing clear blacks and whites is input.

#### [BACKUP INPUT SETTING]

Set the backup function that switches the signal to the backup input signal as seamless as possible when input signal is disrupted.

- 1) Press ▲▼ to select [BACKUP INPUT SETTING].
- 2) Press the <ENTER> button.
  - The [BACKUP INPUT SETTING] screen is displayed.
- 3) Press ▲▼ to select [BACKUP INPUT MODE].
- 4) Press the <ENTER> button.
  - The [BACKUP INPUT MODE] screen is displayed.

#### 5) Press ▲▼ to select the combination of the input and press the <ENTER> button.

Primary input	Secondary input	Number of signals constructing one screen	Details
[0]	FF]	_	Disables the backup function.
[SDI1]	[SDI2]		
[HDMI1 [SLOT1]]*1	[HDMI2 [SLOT1]]*1		
[HDMI3 [SLOT2]]*2	[HDMI4 [SLOT2]]*2		
[DVI-D1 [SLOT1]]*1	[DVI-D2 [SLOT1]]*1		
[DVI-D3 [SLOT2]]*2	[DVI-D4 [SLOT2]]*2	4	
[DisplayPort1 [SLOT1]]*3	[DisplayPort3 [SLOT2]]*3		
[SDI1 [SLOT1]]*4	[SDI2 [SLOT1]]*4		
[SDI3 [SLOT2]]*5	[SDI4 [SLOT2]]*5		
[SDI1 [SLOT1]]*6	[SDI3 [SLOT1]]*6		Enables the backup function.
[SDI1 [SLOT2]]*7	[SDI3 [SLOT2]]*7		
[SDI1-2]	[SDI3-4]		
[HDMI1-2 [SLOT1]]*8	[HDMI3-4 [SLOT2]]*8	0	
[DVI-D1-2 [SLOT1]]*8	[DVI-D3-4 [SLOT2]]*8	2	
[SDI1-2 [SLOT1]]*9	[SDI3-4 [SLOT2]]*9		
[SDI1-2-3-4]*9	[SDI1-2-3-4 [SLOT1/2]]*9		
[SDI1-2-3-4]*6	[SDI1-2-3-4 [SLOT1]]*6	4	
[SDI1-2-3-4]*7	[SDI1-2-3-4 [SLOT2]]*7		

\*1 This is displayed when the optional Interface Board equipped with corresponding input is installed in <SLOT 1>.

\*2 This is displayed when the optional Interface Board equipped with corresponding input is installed in <SLOT 2>.

\*3 This is displayed when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in <SLOT 1> and <SLOT 2>.

\*4 This is displayed when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in <SLOT 1>.

\*5 This is displayed when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in <SLOT 2>.

\*6 This is displayed when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1>.

\*7 This is displayed when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 2>.

\*8 This is displayed when the optional Interface Boards equipped with corresponding input are installed in <SLOT 1> and <SLOT 2>.

\*9 This is displayed when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in <SLOT 1> and <SLOT 2>.

#### 6) Press the <MENU> button.

• The [BACKUP INPUT SETTING] screen is displayed.

#### 7) Press $\blacktriangle$ **v** to select [AUTOMATIC SWITCHING].

• When [BACKUP INPUT MODE] is set to [OFF], [AUTOMATIC SWITCHING] cannot be selected.

#### 8) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

	Switches to the secondary input (primary input) automatically when the input signal for primary input (secondary input) is disrupted.
[DISABLE]	Disables the automatic input switching function.

#### Note

- The backup function is enabled when [BACKUP INPUT MODE] is set to anything other than [OFF] and same signal is input to the primary input and the secondary input.
- To switch to the backup input signal using the backup function, make sure that the following three conditions are satisfied to be ready to use the function.
  - Set [BACKUP INPUT MODE] to anything other than [OFF].
  - Input the same signal to the primary and secondary inputs.
  - Display the image of the primary input or secondary input.
- If the input is switched to other than the primary or secondary input while the backup function is ready for use, the state of readiness to
  use the backup function is canceled. To switch to the backup input signal using the backup function again, switch to the primary input or
  secondary input.
- When [BACKUP INPUT MODE] is set to anything other than [OFF], the combination of that input is displayed in [PRIMARY INPUT] and [SECONDARY INPUT] of the [BACKUP INPUT SETTING] screen.
- [BACKUP INPUT STATUS] is displayed in the input guide (+ page 141) and the [STATUS] screen (+ pages 85, 177) when [BACKUP INPUT MODE] is set to anything other than [OFF].

When the signal can be switched to the backup input signal using the backup function, [ACTIVE] is displayed in [BACKUP INPUT STATUS]. When it is not possible, [INACTIVE] is displayed instead.

The secondary input will be the backup input when [BACKUP INPUT STATUS] is displaying [ACTIVE] while the image from the primary input is displayed.

The primary input will be the backup input when [BACKUP INPUT STATUS] is displaying [ACTIVE] while the image from the secondary input is displayed.

- When [BACKÚP INPUT MODE] is set to anything other than [OFF], the input is switched seamlessly if the input is switched between the primary input and the secondary input while it is possible to switch to the backup input signal.
- When [AUTOMATIC SWITCHING] is set to [ENABLE], and [BACKUP INPUT STATUS] shows [ACTIVE], the signal is switched to the backup input if a disruption occurs in the input signal.
- When [AUTOMATIC SWITCHING] is set to [ENABLE], the indication in [BACKUP INPUT STATUS] will change to [INACTIVE] if the input signal is disrupted and automatically switched to the backup input. In this case, it is not possible to switch to the backup input signal until the original input signal is restored. If the input has switched to the backup input automatically, it is possible to switch to the backup input signal when the original signal has restored. In this case, the current input is maintained.
- [BACKUP INPUT SETTING] cannot be set while in the four-screen display mode. The backup operation is not performed either. Set the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] to anything other than [OFF] when using the four-screen display mode.
- [BACKUP INPUT MODE] in which the standard SDI input is included as the primary input or the secondary input cannot be selected when the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] → [SDI IN] is set to anything other than [OFF].
- [BACKUP INPUT MODE] in which the input equipped on the optional Interface Board installed in the slot is included as the primary input or the secondary input cannot be selected when the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] → [SLOT IN] is set to anything other than [OFF].
- When [SDI LINK] for the primary input and the secondary input is set to [AUTO], [BACKUP INPUT MODE] for that combination cannot be selected. When [SDI LINK] for the primary input and the secondary input do not match, [BACKUP INPUT MODE] for that combination cannot be selected.

Match the setting in accordance with the signal and then input the same signal in the primary input and the secondary input.

- − The [DISPLAY OPTION] menu  $\rightarrow$  [SDI IN]  $\rightarrow$  [SDI LINK]
- The [DISPLAY OPTION] menu  $\rightarrow$  [SLOT IN]  $\rightarrow$  [SDI LINK]
- When [HDMI LINK SETTINGS] or [DVI-D LINK SETTINGS] for the primary input and the secondary input is set to [AUTO], [BACKUP INPUT MODE] for that combination cannot be selected. When [HDMI LINK SETTINGS] or [DVI-D LINK SETTINGS] for the primary input and the secondary input do not match, [BACKUP INPUT MODE] for that combination cannot be selected.

Match the setting in accordance with the signal and then input the same signal in the primary input and the secondary input.

- The [DISPLAY OPTION] menu → [SLOT IN] → [HDMI LINK]
- The [DISPLAY OPTION] menu  $\rightarrow$  [SLOT IN]  $\rightarrow$  [DVI-D LINK]
- The primary input setting values are applied to image adjustment values such as the [PICTURE] menu → [PICTURE MODE], [GAMMA], and [COLOR TEMPERATURE].

## [SIMUL INPUT SETTING]

Set this function when the video signal in simultaneous format is input and used.

#### 1) Press ▲▼ to select [SIMUL INPUT SETTING].

#### 2) Press the <ENTER> button.

• The [SIMUL INPUT SETTING] screen is displayed.

#### 3) Press ▲▼ to select [SDI IN], [SLOT IN].

- [SLOT IN] can be selected when the optional Interface Board is installed in the slot.
- [SLOT IN] cannot be selected when the Interface Board not supporting the simultaneous input is installed.

#### 4) Press $\triangleleft$ to switch the setting.

• The items will switch each time you press the button.

[OFF]	This is not used for simultaneous input.
[AUTO(x2-speed)]	Displays the image in double speed using the signals input in the two input terminals.
[AUTO(x4-speed)]*1	Displays the image in quadruple speed using the signals input in the four input terminals.

\*1 [SLOT IN] cannot be set to [AUTO(x4-speed)] when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1> or <SLOT 2>.

#### Note

- The image for double or quadruple speed is displayed when [AUTO(x2-speed)] or [AUTO(x4-speed)] is set and the same corresponding signal is input to each of the input terminal.
- [QUAD PIXEL DRIVE] is fixed to [ON] when [AUTO(x2-speed)] is set and the following image in simultaneous format is displayed. 3840 x 2160/60, 3840 x 2160/50, 4096 x 2160/60, 4096 x 2160/50
- [QUAD PIXEL DRIVE] is fixed to [OFF] when [AUTO(x2-speed)] or [AUTO(x4-speed)] is set and the following image in simultaneous format is displayed.
- 1080/60p, 1080/50p, 1366 x 768/50, 1366 x 768/60, 1400 x 1050/50, 1400 x 1050/60, 1920 x 1080/50, 1920 x 1080/60, 1920 x 1200/50, 1920 x 1200/60RB
- [SDI IN] or [SLOT IN] in [SIMUL INPUT SETTING] (including the input set as the primary input or the secondary input) is fixed to [OFF] when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set to anything other than [OFF].
- [SDI IN] in [SIMUL INPUT SETTING] is fixed to [OFF] when [SDI LINK] in [SDI IN] is set to anything other than [SINGLE].
- [SLOT IN] in [SIMUL INPUT SETTING] is fixed to [OFF] when [HDMI LINK], [DVI-D LINK], or [SDI LINK] in [SLOT IN] is set to anything other than [SINGLE].
- [SLOT IN] in [SIMUL INPUT SETTING] can be selected when the optional Interface Board is not installed in the slot.
- The Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) does not support simultaneous input.
- When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).

- [SIMUL INPUT SETTING] cannot be set when the [POSITION] menu → [GEOMETRY] is set to anything other than [OFF]. To input and
  project the video signal in simultaneous format, use a flat screen so that the geometric adjustment is unnecessary, and install the projector
  so that the projected image will be rectangular.
- [SIMUL INPUT SETTING] cannot be set when the [ADVANCED MENU] menu → [BLANKING] → [CUSTOM MASKING] is set to anything other than [OFF] ([PC-1], [PC-2], [PC-3]).
- [CUSTOM MASKING] uses the masking function of the Panasonic computer application.
- [SIMUL INPUT SETTING] cannot be set when the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display.
- This may not function properly for some connected external devices.
- This may not function properly depending on the signal.

### [SIMUL INPUT SETTING] screen

Usage of each input signal is displayed under the setting items of [SDI IN] and [SLOT IN] in the **[SIMUL INPUT SETTING]** screen when [AUTO(x2-speed)] or [AUTO(x4-speed)] is set.

[SIMUL INPUT SETTING]	Usage of the input signal	Details
[AUTO(x2-speed)]	[1st FRAME INPUT]	Uses the signal for the corresponding input as a signal for the odd frame.
	[2nd FRAME INPUT]	Uses the signal for the corresponding input as a signal for the even frame.
[AUTO(x4-speed)]	[1st FRAME INPUT]	Uses the signal for the corresponding input as the signal for the first frame $(1 + n \times 4)$ .
	[2nd FRAME INPUT]	Uses the signal for the corresponding input as the signal for the second frame $(2 + n \times 4)$ .
	[3rd FRAME INPUT]	Uses the signal for the corresponding input as the signal for the third frame $(3 + n \times 4)$ .
	[4th FRAME INPUT]	Uses the signal for the corresponding input as the signal for the fourth frame $(4 + n \times 4)$ .

### [SDI IN]

Set this item in accordance with the signal input to the <SDI IN 1>/<SDI IN 2>/<SDI IN 3>/<SDI IN 4> terminal.

#### Setting [SDI LINK] in [SDI IN]

Press ▲▼ to select [SDI IN].

#### 2) Press the <ENTER> button.

• The [SDI IN] screen is displayed.

#### 3) Press ▲▼ to select [SDI LINK].

- 4) Press the <ENTER> button.
  - The [SDI LINK] screen is displayed.

#### 5) Press $\blacktriangle \blacksquare$ to select the setting.

[AUTO]	Automatically selects the single link, the dual link, or the quad link.
[SINGLE]	Sets each of the SDI1 input, the SDI2 input, the SDI3 input, and the SDI4 input to single link.
[DUAL/SINGLE]	Sets the SDI1 input and the SDI2 input to dual link, and the SDI3 input and the SDI4 input to single link.
[SINGLE/DUAL]	Sets the SDI1 input and the SDI2 input to single link, and the SDI3 input and the SDI4 input to dual link.
[DUAL/DUAL]	Sets the SDI1 input and the SDI2 input to dual link, and the SDI3 input and the SDI4 input to dual link.
[QUAD]	Sets the SDI1 input, the SDI2 input, the SDI3 input, and the SDI4 input to quad link. (Factory default setting)

#### 6) Press the <ENTER> button.

#### Note

• The single link is a setting to display one image with one input signal. The dual link is a setting to display one image with two input signals. The quad link is a setting to display one image with four input signals.

- [SDI LINK] is fixed to [SINGLE] in the following cases.
  - When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to anything other than [OFF]
- When the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display
   The [SDI LINK] setting cannot be changed when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set as the combination to use the SDI input equipped on the projector as standard.
- When [SDI LINK] is set to [AUTO], use the same format for the signal to be input to the <SDI IN 1>/<SDI IN 2>/<SDI IN 3>/<SDI IN 4> terminals. If different format signal is input to even one terminal, currently displayed image may not be projected correctly.
- [3G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].
- The content set is displayed in [SDI LINK SETTINGS].

### Setting [RESOLUTION] in [SDI IN]

#### Press ▲▼ to select [SDI IN].

- 2) Press the <ENTER> button.
  - The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - When [QUAD LINK SETTING] is selected, proceed to Step 5).
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], [SDI4], [SDI1-2], or [SDI3-4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen or [DUAL LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \blacksquare$  to select [RESOLUTION], and press the <ENTER> button.
  - The [RESOLUTION] screen is displayed.
- 6) Press  $\blacktriangle \forall$  to select the item, and press the <ENTER> button.
  - Select [AUTO], [720x480i], [720x576i], [1280x720p], [1920x1080i], [1920x1080p], [1920x1080sF], or [2048x1080p] when [SINGLE LINK SETTING] is selected.
  - Select [AUTO], [1920x1080i], [1920x1080p], [1920x1080sF], [2048x1080p], [3840x2160p], or [4096x2160p] when [DUAL LINK SETTING] is selected.
  - Select [AUTO], [3840x2160p], [3840x2160sF], or [4096x2160p] when [QUAD LINK SETTING] is selected.

### Setting [4K DIVISION] in [SDI IN]

Set the transmission method in the 4K division when 4K image is displayed with SDI input.

1) Press ▲▼ to select [SDI IN].

## 120 - ENGLISH

#### 2) Press the <ENTER> button.

- The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [DUAL LINK SETTING] or [QUAD LINK SETTING], and press the <ENTER> button.
   The [DUAL LINK SETTING] screen or the [QUAD LINK SETTING] screen is displayed.
  - When [DUAL LINK SETTING] is selected, press ▲▼ to select [SDI1-2] or [SDI3-4], and press the <ENTER> button.

#### 4) Press ▲▼ to select [4K DIVISION].

#### 5) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically select [SQUARE] or [INTERLEAVE].
[SQUARE]	Fixes the transmission method to Square Division.
[INTERLEAVE]	Fixes the transmission method to 2-Sample Interleave Division.

#### Setting [3G-SDI MAPPING] in [SDI IN]

- 1) Press ▲▼ to select [SDI IN].
- 2) Press the <ENTER> button.
  - The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - When [QUAD LINK SETTING] is selected, proceed to Step 5).
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], [SDI4], [SDI1-2], or [SDI3-4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen or [DUAL LINK SETTING] screen for the selected item is displayed.
- 5) Press ▲▼ to select [3G-SDI MAPPING].

#### 6) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically select [LEVEL A] or [LEVEL B].
[LEVEL A]	Fixes the mapping method to 3G-SDI Level-A.
[LEVEL B]	Fixes the mapping method to 3G-SDI Level-B.

#### Note

• This function does not operate when the SD-SDI signal or the HD-SDI signal is input.

• [3G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].

#### Setting [SYSTEM SELECTOR] in [SDI IN]

- 1) Press ▲▼ to select [SDI IN].
- 2) Press the <ENTER> button.
  - The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - When [QUAD LINK SETTING] is selected, proceed to Step 5).
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], [SDI4], [SDI1-2], or [SDI3-4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen or [DUAL LINK SETTING] screen for the selected item is displayed.
- 5) Press ▲▼ to select [SYSTEM SELECTOR].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically selects [RGB], [YP <sub>B</sub> P <sub>R</sub> 4:4:4], [YP <sub>B</sub> P <sub>R</sub> 4:2:2], or [XYZ].
[RGB]	Fixes to [RGB].
[YP <sub>B</sub> P <sub>R</sub> 4:4:4]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:4:4].
[YP <sub>B</sub> P <sub>R</sub> 4:2:2]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:2:2].
[XYZ]	Fixes to [XYZ].

#### Setting [BIT DEPTH] in [SDI IN]

- 1) Press ▲▼ to select [SDI IN].
- 2) Press the <ENTER> button.
  - The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - When [QUAD LINK SETTING] is selected, proceed to Step 5).
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], [SDI4], [SDI1-2], or [SDI3-4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen or [DUAL LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \lor$  to select [BIT DEPTH].
- 6) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[AUTO]	Automatically select [12-bit] or [10-bit].
[12-bit]	Fixes to [12-bit].
[10-bit]	Fixes to [10-bit].

#### Setting [SIGNAL LEVEL] in [SDI IN]

- 1) Press ▲▼ to select [SDI IN].
- 2) Press the <ENTER> button.
  - The [SDI IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - When [QUAD LINK SETTING] is selected, proceed to Step 5).
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], [SDI4], [SDI1-2], or [SDI3-4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen or [DUAL LINK SETTING] screen for the selected item is displayed.
- 5) Press ▲▼ to select [SIGNAL LEVEL].
- 6) Press **♦** to switch the item.
  - The items will switch each time you press the button.

[64-940]	Normally use this setting.
[4-1019]	Select this item when gray is displayed as black.

### [DIGITAL LINK IN]

Set this item in accordance with the video signal input to the <DIGITAL LINK/LAN> terminal.

## 122 - ENGLISH

### Setting [SIGNAL LEVEL] in [DIGITAL LINK IN]

#### 1) Press ▲▼ to select [DIGITAL LINK IN].

2) Press the <ENTER> button.
• The [DIGITAL LINK IN] screen is displayed.

#### 3) Press ▲▼ to select [SIGNAL LEVEL].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically sets the signal level.
[64-940]	Select this item when the signal output from the HDMI terminal of an external device (Blu-ray disc player, etc.) is input to the <digital lan="" link=""> terminal via a twisted-pair-cable transmitter.</digital>
[0-1023]	Select this item when the signal output from the DVI-D terminal or HDMI terminal of an external device (such as a computer) is input to the <digital lan="" link=""> terminal via a twisted-pair-cable transmitter.</digital>

#### Note

- The optimal setting varies depending on the output setting of the connected external device. Refer to the operating instructions of the external device regarding the output of the external device.
- The signal level is displayed for 30 bits of input.

#### Setting [EDID SELECT] in [DIGITAL LINK IN]

#### 1) Press ▲▼ to select [DIGITAL LINK IN].

#### 2) Press the <ENTER> button.

• The [DIGITAL LINK IN] screen is displayed.

#### 3) Press ▲▼ to select [EDID SELECT].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[4K/60p]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 60 Hz).
[4K/30p]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 30 Hz).
[2K]	Switches to EDID corresponding to the 2K video signal (maximum 1 920 x 1 200 dots) or lower.

#### Note

• Switch the setting to [4K/30p] when proper image is not projected while [EDID SELECT] is set to [4K/60p] and the 4K video signal is input.

 Switch the setting to [2K] when proper image is not projected while [EDID SELECT] is set to [4K/60p] or [4K/30p] and the 2K video signal or lower is input.

• For details of the signal described in EDID of [4K/60p], [4K/30p], or [2K], refer to "List of plug and play compatible signals" (+ page 258).

### Setting [EDID MODE] in [DIGITAL LINK IN]

#### 1) Press ▲▼ to select [DIGITAL LINK IN].

#### 2) Press the <ENTER> button.

- The [DIGITAL LINK IN] screen is displayed.
- 3) Press  $\blacktriangle \forall$  to select [EDID MODE].
- 4) Press the <ENTER> button.
  - The [DIGITAL LINK EDID MODE] screen is displayed.

#### 5) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[DEFAULT] Standard setting.

[USER] Sets the [RESOLUTION] and [VERTICAL SCAN FREQUENCY] items to EDID.

• Proceed to Step 10) when [DEFAULT] is selected.

#### 6) Press the <ENTER> button.

• The [RESOLUTION] screen is displayed.

#### 7) Press ▲▼◀▶ to select [RESOLUTION].

Select [1024x768p], [1280x720p], [1280x768p], [1280x800p], [1280x1024p], [1366x768p], [1400x1050p], [1440x900p], [1600x900p], [1600x1200p], [1680x1050p], [1920x1080p], [1920x1080i], [1920x1200p], [2048x1080p], [2560x1600p], or [3840x2400p].

#### 8) Press the <ENTER> button.

• The [VERTICAL SCAN FREQUENCY] screen is displayed.

#### 9) Press **♦** to select [VERTICAL SCAN FREQUENCY].

- The setting is fixed to [30Hz] when [3840x2400p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], [30Hz], [25Hz], or [24Hz] when [2048x1080p] or [1920x1080p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], or [48Hz] when [1920x1080i] is selected for [RESOLUTION].
- Select [60Hz] or [50Hz] when anything other than following is selected for [RESOLUTION].
   [3840x2400p], [2048x1080p], [1920x1080p], [1920x1080i]

#### 10) Press the <ENTER> button.

• The confirmation screen is displayed.

#### 11) Press **↓** to select [OK], and press the <ENTER> button.

#### Note

- The settings in [RESOLUTION] and [VERTICAL SCAN FREQUENCY] are displayed in [EDID STATUS].
- The resolution and vertical scanning frequency settings may also be required on your computer or video device.
- After configuring settings, your computer or video device or the projector may be required to be turned off and on.
- A signal may not be output with the resolution and vertical scanning frequency that have been set, depending on your computer or video device.

## [SLOT IN]

Set this item in accordance with the signal input to the input terminal of the installed Interface Board when the optional Interface Board is installed in the slot.

The content that can be set varies depending on the structure of the installed Interface Board. It cannot be set if no Interface Board is installed in the slots.

### When the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed

#### Setting [HDMI LINK] in [SLOT IN] (HDMI input)

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [HDMI LINK], and press the <ENTER> button.
  - The [HDMI LINK] screen is displayed.
- 4) Press  $\blacktriangle \lor$  to select the setting.

[AUTO]	Automatically selects the single link, the dual link, or the quad link. Selects the quad link when the signal in the same format (such as resolution and timing) is input in the four inputs of HDMI1, HDMI2, HDMI3, and HDMI4. Selects the dual link when the signal in the same format is input in the HDMI1 input and the HDMI2 input, or the HDMI3 input and the HDMI4. Quad link will be automatically selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in both of the slots.
[SINGLE]	Sets the HDMI1 input and the HDMI2 input, and the HDMI3 input and the HDMI4 input to single link. (Factory default setting)
[DUAL]*1	Sets the HDMI1 input and the HDMI2 input, or the HDMI3 input and the HDMI4 input to dual link.

## 124 - ENGLISH

Chapter 4	Settings —	[DISPLAY OPTION] menu
-----------	------------	-----------------------

[DUAL/SINGLE] <sup>*2</sup>	Sets the HDMI1 input and the HDMI2 input to dual link, and the HDMI3 input and the HDMI4 input to single link.
[SINGLE/DUAL]*2	Sets the HDMI1 input and the HDMI2 input to single link, and the HDMI3 input and the HDMI4 input to dual link.
[DUAL/DUAL]*2	Sets the HDMI1 input and the HDMI2 input to dual link, and the HDMI3 input and the HDMI4 input to dual link.
[QUAD]*2	Sets the HDMI1 input, the HDMI2 input, the HDMI3 input, and the HDMI4 input to quad link.

\*1 This can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in either of the slots.

\*2 This can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in both of the slots.


#### 5) Press the <ENTER> button.

#### Note

- [HDMI LINK] is fixed to [SINGLE] in the following cases.
- When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to anything other than [OFF]
- When the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display
   The [HDMI LINK] setting cannot be changed when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set as the combination used for the HDMI input of the Interface Board.
- The content set is displayed in [HDMI LINK SETTINGS].

#### Structure of the projected image

The single link is a setting to display one image with one input signal. The dual link is a setting to display one image with two input signals. The quad link is a setting to display one image with four input signals.



Single link

Dual link

Quad link

#### Setting [SIGNAL LEVEL] in [SLOT IN] (HDMI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.

• The [SLOT IN] screen is displayed.

- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
- 4) Press ▲▼ to select [SIGNAL LEVEL].

#### 5) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically sets the signal level.
[64-940]	Select this item when the HDMI terminal output of the external device (such as Blu-ray disc player) is input to the <hdmi 1="" in=""> terminal, the <hdmi 2="" in=""> terminal, the <hdmi 3="" in=""> terminal, or the <hdmi 4="" in=""> terminal.</hdmi></hdmi></hdmi></hdmi>
[0-1023]	Select this item when the DVI-D terminal output from the external device (such as computer) is input to the <hdmi 1="" in=""> terminal, the <hdmi 2="" in=""> terminal, the <hdmi 3="" in=""> terminal, or the <hdmi 4="" in=""> terminal via a conversion cable, etc. This is the same when the HDMI terminal output from a device such as a computer is input to the <hdmi 1="" in=""> terminal, the <hdmi 2="" in=""> terminal, the <hdmi 3="" in=""> terminal, and the <hdmi 4="" in=""> terminal.</hdmi></hdmi></hdmi></hdmi></hdmi></hdmi></hdmi></hdmi>

#### Note

The optimal setting varies depending on the output setting of the connected external device. Refer to the operating instructions of the
external device regarding the output of the external device.

• The HDMI signal level is displayed for 30 bits of input.

#### Setting [EDID SELECT] in [SLOT IN] (HDMI input)

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [EDID SETTING], and press the <ENTER> button.
  - The [EDID SETTING] screen is displayed.
- 4) Press ▲▼ to select [EDID SELECT].

#### 5) Press **♦** to switch the item.

• The items will switch each time you press the button.

[4K/60p/SDR]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 60 Hz). This is EDID supporting SDR (Standard Dynamic Range). The does not support HDR (High Dynamic Range).
[4K/60p/HDR]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 60 Hz). This is EDID supporting HDR (High Dynamic Range).
[4K/30p]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 30 Hz).
[2K]	Switches to EDID corresponding to the 2K video signal (maximum 1 920 x 1 200 dots) or lower.

#### Note

- Switch the setting to [4K/30p] when proper image is not projected while [EDID SELECT] is set to [4K/60p/SDR] or [4K/60p/HDR] and the 4K video signal is input.
- Switch the setting to [2K] when proper image is not projected while [EDID SELECT] is set to [4K/60p/SDR], [4K/60p/HDR], or [4K/30p] and the 2K video signal or lower is input.
- For details of the signal described in EDID of [4K/60p/SDR], [4K/60p/HDR], [4K/30p], or [2K], refer to "List of plug and play compatible signals" (> page 258).

#### Setting [EDID MODE] in [SLOT IN] (HDMI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [EDID SETTING], and press the <ENTER> button.
  - The [EDID SETTING] screen is displayed.
- 4) Press  $\blacktriangle \forall$  to select [EDID MODE].
- 5) Press the <ENTER> button.
  - The [HDMI EDID MODE] screen is displayed.
- 6) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[DEFAULT]	Standard setting.
[USER]	Sets the [RESOLUTION] and [VERTICAL SCAN FREQUENCY] items to EDID.

• Proceed to Step 11) when [DEFAULT] is selected.

- 7) Press the <ENTER> button.
  - The [RESOLUTION] screen is displayed.

#### 8) Press ▲▼◀▶ to select [RESOLUTION].

Select [1024x768p], [1280x720p], [1280x768p], [1280x800p], [1280x1024p], [1366x768p], [1400x1050p], [1440x900p], [1600x900p], [1600x1200p], [1680x1050p], [1920x1080p], [1920x1080i], [1920x1200p], [1920x2160p], [2048x1080p], [2048x2160p], [2560x1600p], or [3840x2400p].

#### 9) Press the <ENTER> button.

• The [VERTICAL SCAN FREQUENCY] screen is displayed.

#### 10) Press **♦** to select [VERTICAL SCAN FREQUENCY].

- Select [60Hz], [50Hz], or [30Hz] when [3840x2400p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], [30Hz], [25Hz], or [24Hz] when [2048x2160p], [2048x1080p], [1920x2160p], or [1920x1080p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], or [48Hz] when [1920x1080i] is selected for [RESOLUTION].
- Select [60Hz] or [50Hz] when anything other than following is selected for [RESOLUTION]. - [3840x2400p], [2048x2160p], [2048x1080p], [1920x2160p], [1920x1080p], [1920x1080p]

#### 11) Press the <ENTER> button.

• The confirmation screen is displayed.

#### 12) Press **(**) to select [OK], and press the <ENTER> button.

#### Note

- The settings in [RESOLUTION] and [VERTICAL SCAN FREQUENCY] are displayed in [EDID STATUS].
- The resolution and vertical scanning frequency settings may also be required on your computer or video device.
- After configuring settings, your computer or video device or the projector may be required to be turned off and on.
- A signal may not be output with the resolution and vertical scanning frequency that have been set, depending on your computer or video device.

### When the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed

#### Setting [DVI-D LINK] in [SLOT IN] (DVI-D input)

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.

#### 3) Press ▲▼ to select [DVI-D LINK], and press the <ENTER> button.

- The [DVI-D LINK] screen is displayed.
- 4) Press  $\blacktriangle \blacksquare$  to select the setting.

[AUTO]	Automatically selects the single link, the dual link, or the quad link. Selects the quad link when the signal in the same format (such as resolution and timing) is input in the four inputs of DVI-D1, DVI-D2, DVI-D3, and DVI-D4. Selects the dual link when the signal in the same format is input in the DVI-D1 input and the DVI-D2 input, or the DVI-D3 input and the DVI-D4. Quad link will be automatically selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in both of the slots.
[SINGLE]	Sets the DVI-D1 input and the DVI-D2 input, and the DVI-D3 input and the DVI-D4 input to single link. (Factory default setting)
[DUAL]*1	Sets the DVI-D1 input and the DVI-D2 input, or the DVI-D3 input and the DVI-D4 input to dual link.
[DUAL/SINGLE]*2	Sets the DVI-D1 input and the DVI-D2 input to dual link, and the DVI-D3 input and the DVI-D4 input to single link.
[SINGLE/DUAL]*2	Sets the DVI-D1 input and the DVI-D2 input to single link, and the DVI-D3 input and the DVI-D4 input to dual link.
[DUAL/DUAL] <sup>*2</sup>	Sets the DVI-D1 input and the DVI-D2 input to dual link, and the DVI-D3 input and the DVI-D4 input to dual link.
[QUAD]*2	Sets the DVI-D1 input, the DVI-D2 input, the DVI-D3 input, and the DVI-D4 input to quad link.

\*1 This can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in either of the slots.

\*2 This can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in both of the slots.


#### 5) Press the <ENTER> button.

#### Note

- [DVI-D LINK] is fixed to [SINGLE] in the following cases.
  - When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to anything other than [OFF]
- When the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display
   The [DVI-D LINK] setting cannot be changed when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set as the combination used for the DVI-D input of the Interface Board.
- The content set is displayed in [DVI-D LINK SETTINGS].

#### Structure of the projected image

The single link is a setting to display one image with one input signal. The dual link is a setting to display one image with two input signals. The quad link is a setting to display one image with four input signals.



Single link

Dual link

Quad link

#### Setting [SIGNAL LEVEL] in [SLOT IN] (DVI-D input)

1) Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

• The [SLOT IN] screen is displayed.

- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.

#### 4) Press ▲▼ to select [SIGNAL LEVEL].

#### 5) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically sets the signal level.
[0-255:PC]	Select this item when the DVI-D terminal output of the external device (such as computer) is input to the <dvi-d 1="" in=""> terminal, the <dvi-d 2="" in=""> terminal, the <dvi-d 3="" in=""> terminal, or the <dvi-d 4="" in=""> terminal.</dvi-d></dvi-d></dvi-d></dvi-d>
[16-235]	Select this item when the HDMI terminal output from the external device (such as Blu-ray disc player) is input to the <dvi-d 1="" in=""> terminal, the <dvi-d 2="" in=""> terminal, the <dvi-d 3="" in=""> terminal, or the <dvi-d 4="" in=""> terminal via a conversion cable, etc.</dvi-d></dvi-d></dvi-d></dvi-d>

#### Note

• The optimal setting varies depending on the output setting of the connected external device. Refer to the operating instructions of the external device regarding the output of the external device.

#### Setting [EDID SELECT] in [SLOT IN] (DVI-D input)

1) Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

- The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [EDID SETTING], and press the <ENTER> button.
   The [EDID SETTING] screen is displayed.
- 4) Press  $\blacktriangle \lor$  to select [EDID SELECT].

#### 5) Press **♦** to switch the item.

• The items will switch each time you press the button.

[EDID3]	Recognizes movie-based video signals and still image signals automatically.
[EDID1]	Select this item mainly when the external device (such as Blu-ray disc player) which outputs the moving image signal is connected to the <dvi-d 1="" in=""> terminal, the <dvi-d 2="" in=""> terminal, the <dvi-d 3="" in=""> terminal, or the <dvi-d 4="" in=""> terminal.</dvi-d></dvi-d></dvi-d></dvi-d>
[EDID2:PC]	Select this item mainly when the external device (such as computer) which outputs the still image signal is connected to the <dvi-d 1="" in=""> terminal, the <dvi-d 2="" in=""> terminal, the <dvi-d 3="" in=""> terminal, or the <dvi-d 4="" in=""> terminal.</dvi-d></dvi-d></dvi-d></dvi-d>

#### Note

• The data for Plug and play will change when the setting is changed. Refer to "List of compatible signals" (+ page 255) for a resolution that supports plug and play.

#### Setting [EDID MODE] in [SLOT IN] (DVI-D input)

#### 1) Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

- The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [EDID SETTING], and press the <ENTER> button.
   The [EDID SETTING] screen is displayed.

#### 4) Press $\blacktriangle \blacksquare$ to select [EDID MODE].

#### 5) Press the <ENTER> button.

• The [DVI-D EDID MODE] screen is displayed.

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[DEFAULT]	Standard setting.
[USER]	Sets the [RESOLUTION] and [VERTICAL SCAN FREQUENCY] items to EDID.

• Proceed to Step 11) when [DEFAULT] is selected.

#### 7) Press the <ENTER> button.

• The [RESOLUTION] screen is displayed.

#### 8) Press ▲▼◀▶ to select [RESOLUTION].

Select [1024x768p], [1280x720p], [1280x768p], [1280x800p], [1280x1024p], [1366x768p], [1400x1050p], [1440x900p], [1600x900p], [1600x1200p], [1680x1050p], [1920x1080p], [1920x1080i], [1920x1200p], [1920x2160p], [2048x1080p], or [2048x2160p].

#### 9) Press the <ENTER> button.

• The [VERTICAL SCAN FREQUENCY] screen is displayed.

#### 10) Press **I** to select [VERTICAL SCAN FREQUENCY].

- Select [30Hz], [25Hz], or [24Hz] when [2048x2160p] or [1920x2160p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], [30Hz], [25Hz], or [24Hz] when [2048x1080p] or [1920x1080p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], or [48Hz] when [1920x1080i] is selected for [RESOLUTION].
- Select [60Hz] or [50Hz] when anything other than following is selected for [RESOLUTION].
   [2048x2160p], [2048x1080p], [1920x2160p], [1920x1080p], [1920x1080i]

#### 11) Press the <ENTER> button.

• The confirmation screen is displayed.

#### 12) Press **♦** to select [OK], and press the **<ENTER>** button.

#### Note

The settings in [RESOLUTION] and [VERTICAL SCAN FREQUENCY] are displayed in [EDID STATUS].

#### Chapter 4 Settings — [DISPLAY OPTION] menu

- The resolution and vertical scanning frequency settings may also be required on your computer or video device.
- · After configuring settings, your computer or video device or the projector may be required to be turned off and on.
- A signal may not be output with the resolution and vertical scanning frequency that have been set, depending on your computer or video device.

#### When the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed

#### Setting [SIGNAL LEVEL] in [SLOT IN] (DisplayPort input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [DisplayPort1], [DisplayPort2], [DisplayPort3], or [DisplayPort4], and press the <ENTER> button.
  - The [DisplayPort1] screen, the [DisplayPort2] screen, the [DisplayPort3] screen, or the [DisplayPort4] screen is displayed.
- 4) Press ▲▼ to select [SIGNAL LEVEL].

#### 5) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically sets the signal level.
[64-940]	Select this item when the HDMI terminal output from the external device (such as Blu-ray disc player) is input to the <displayport 1="" in=""> terminal, the <displayport 2="" in=""> terminal, the <displayport 3="" in=""> terminal, or the <displayport 4="" in=""> terminal via a conversion cable, etc.</displayport></displayport></displayport></displayport>
[0-1023]	Select this item when the DisplayPort terminal output of the external device (such as computer) is input to the <displayport 1="" in=""> terminal, the <displayport 2="" in=""> terminal, the <displayport 3="" in=""> terminal, or the <displayport 4="" in=""> terminal. This is the same when the HDMI terminal output from a device such as a computer is input to the <displayport 1="" in=""> terminal, the <displayport 2="" in=""> terminal, the <displayport 3="" in=""> terminal, or the <displayport 1="" in=""> terminal, the <displayport 2="" in=""> terminal, the <displayport 3="" in=""> terminal, or the <displayport 4="" in=""> terminal via a conversion cable, etc.</displayport></displayport></displayport></displayport></displayport></displayport></displayport></displayport></displayport></displayport></displayport>

#### Note

• The optimal setting varies depending on the output setting of the connected external device. Refer to the operating instructions of the external device regarding the output of the external device.

#### Setting [EDID SELECT] in [SLOT IN] (DisplayPort input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [DisplayPort1], [DisplayPort2], [DisplayPort3], or [DisplayPort4], and press the <ENTER> button.
  - The [DisplayPort1] screen, the [DisplayPort2] screen, the [DisplayPort3] screen, or the [DisplayPort4] screen is displayed.
- 4) Press  $\blacktriangle \lor$  to select [EDID SELECT].

#### 5) Press **♦** to switch the item.

• The items will switch each time you press the button.

[4K/60p/SDR]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 60 Hz). This is EDID supporting SDR (Standard Dynamic Range). This does not support HDR (High Dynamic Range).
[4K/60p/HDR]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 60 Hz). This is EDID supporting HDR (High Dynamic Range).
[4K/30p]	Switches to EDID corresponding to the 4K video signal (maximum 4 096 x 2 160 dots, maximum vertical scanning frequency 30 Hz).

[2K]

Switches to EDID corresponding to the 2K video signal (maximum 1 920 x 1 200 dots) or lower.

#### Note

- Switch the setting to [4K/30p] when proper image is not projected while [EDID SELECT] is set to [4K/60p/SDR] or [4K/60p/HDR] and the 4K video signal is input.
- Switch the setting to [2K] when proper image is not projected while [EDID SELECT] is set to [4K/60p/SDR], [4K/60p/HDR], or [4K/30p] and the 2K video signal or lower is input.
- For details of the signal described in EDID of [4K/60p/SDR], [4K/60p/HDR], [4K/30p], or [2K], refer to "List of DisplayPort compatible signals" (+ page 260).

#### Setting [EDID MODE] in [SLOT IN] (DisplayPort input)

#### 1) Press ▲▼ to select [SLOT IN].

2) Press the <ENTER> button.

• The [SLOT IN] screen is displayed.

- 3) Press ▲▼ to select [DisplayPort1], [DisplayPort2], [DisplayPort3], or [DisplayPort4], and press the <ENTER> button.
  - The [DisplayPort1] screen, the [DisplayPort2] screen, the [DisplayPort3] screen, or the [DisplayPort4] screen is displayed.

#### 4) Press $\blacktriangle \forall$ to select [EDID MODE].

#### 5) Press the <ENTER> button.

• The [DisplayPort EDID MODE] screen is displayed.

#### 6) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[DEFAULT]	Standard setting.
[USER]	Sets the [RESOLUTION] and [VERTICAL SCAN FREQUENCY] items to EDID.

• Proceed to Step 11) when [DEFAULT] is selected.

#### 7) Press the <ENTER> button.

• The [RESOLUTION] screen is displayed.

#### 8) Press ▲▼◀▶ to select [RESOLUTION].

Select [1024x768p], [1280x720p], [1280x800p], [1400x1050p], [1600x900p], [1600x1200p], [1920x1080p], [1920x1200p], [2048x1080p], [2560x1600p], or [3840x2400p].

#### 9) Press the <ENTER> button.

• The [VERTICAL SCAN FREQUENCY] screen is displayed.

#### 10) Press **I** to select [VERTICAL SCAN FREQUENCY].

- Select [60Hz], [50Hz], or [30Hz] when [3840x2400p] is selected for [RESOLUTION].
- Select [60Hz], [50Hz], [30Hz], [25Hz], or [24Hz] when [2048x1080p] or [1920x1080p] is selected for [RESOLUTION].
- Select [60Hz] or [50Hz] when anything other than following is selected for [RESOLUTION].
  - [3840x2400p], [2048x1080p], [1920x1080p]

#### 11) Press the <ENTER> button.

- The confirmation screen is displayed.
- 12) Press ◀▶ to select [OK], and press the <ENTER> button.

#### Note

<sup>•</sup> The settings in [RESOLUTION] and [VERTICAL SCAN FREQUENCY] are displayed in [EDID STATUS].

<sup>•</sup> The resolution and vertical scanning frequency settings may also be required on your computer or video device.

<sup>•</sup> After configuring settings, your computer or video device or the projector may be required to be turned off and on.

<sup>•</sup> A signal may not be output with the resolution and vertical scanning frequency that have been set, depending on your computer or video device.

#### When the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed

To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (→ page 35).

#### Setting [SDI LINK] in [SLOT IN] (SDI input)

#### 1) Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

• The [SLOT IN] screen is displayed.

#### 3) Press ▲▼ to select [SDI LINK], and press the <ENTER> button.

• The [SDI LINK] screen is displayed.

#### 4) Press $\blacktriangle \blacksquare$ to select the setting.

[AUTO]	Automatically selects the single link, the dual link, or the quad link. Quad link will be automatically selected when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in both of the slots.
[SINGLE]	Sets the SDI1 input and the SDI2 input, and the SDI3 input and the SDI4 input of the Interface Board to single link. (Factory default setting)
[DUAL] <sup>*1</sup>	Sets the SDI1 input and the SDI2 input, or the SDI3 input and the SDI4 input of the Interface Board to dual link.
[DUAL/SINGLE] <sup>*2</sup>	Sets the SDI1 input and the SDI2 input of the Interface Board to dual link, and the SDI3 input and the SDI4 input of the Interface Board to single link.
[SINGLE/DUAL] <sup>2</sup>	Sets the SDI1 input and the SDI2 input of the Interface Board to single link, and the SDI3 input and the SDI4 input of the Interface Board to dual link.
[DUAL/DUAL] <sup>*2</sup>	Sets the SDI1 input and the SDI2 input of the Interface Board to dual link, and the SDI3 input and the SDI4 input of the Interface Board to dual link.
[QUAD]*2	Sets the SDI1 input, the SDI2 input, the SDI3 input, and the SDI4 input of the Interface Board to quad link.

\*1 This can be selected when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in either of the slots.

\*2 This can be selected when the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is installed in both of the slots.

#### 5) Press the <ENTER> button.

#### Note

- The single link is a setting to display one image with one input signal. The dual link is a setting to display one image with two input signals. The quad link is a setting to display one image with four input signals.
- [SDI LINK] is fixed to [SINGLE] in the following cases.
   When the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to anything other than [OFF]
- When the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display
   The [SDI LINK] setting cannot be changed when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set as the combination used for the SDI input of the Interface Board.
- When [SDI LINK] is set to [AUTO], use the same format for the signal to be input to the <3G-SDI 1 IN>/<3G-SDI 2 IN>/<3G-SDI 3 IN>/<3G-</li>
- SDI 4 IN> terminals. If different format signal is input to even one terminal, currently displayed image may not be projected correctly.

• [3G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].

• The content set is displayed in [SDI LINK SETTINGS].

#### Setting [RESOLUTION] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.

- 4) Press  $\blacktriangle \forall$  to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \forall$  to select [RESOLUTION], and press the <ENTER> button.
  - The [RESOLUTION] screen is displayed.
- 6) Press  $\blacktriangle \forall$  to select an item, and press the <ENTER> button.
  - Select [AUTO], [720x480i], [720x576i], [1280x720p], [1920x1080i], [1920x1080p], [1920x1080sF], or [2048x1080p] when [SINGLE LINK SETTING] is selected.
  - Select [AUTO], [1920x1080i], [1920x1080p], [1920x1080sF], [2048x1080p], [3840x2160p], or [4096x2160p] when [DUAL LINK SETTING] is selected.
  - Select [AUTO], [3840x2160p], [3840x2160sF], or [4096x2160p] when [QUAD LINK SETTING] is selected.

#### Setting [4K DIVISION] in [SLOT IN] (SDI input)

Set the transmission method in the 4K division when 4K image is displayed with SDI input.

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [DUAL LINK SETTING] or [QUAD LINK SETTING], and press the <ENTER> button.
   The [DUAL LINK SETTING] screen or the [QUAD LINK SETTING] screen is displayed.
- 4) Press  $\blacktriangle \forall$  to select [4K DIVISION].
- 5) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[AUTO]	Automatically select [SQUARE] or [INTERLEAVE].
[SQUARE]	Fixes the transmission method to Square Division.
[INTERLEAVE]	Fixes the transmission method to 2-Sample Interleave Division.

#### Setting [3G-SDI MAPPING] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.

#### 5) Press ▲▼ to select [3G-SDI MAPPING].

- 6) Press  $\blacktriangleleft$  to switch the item.
  - The items will switch each time you press the button.

[AUTO]	Automatically select [LEVEL A] or [LEVEL B].
[LEVEL A]	Fixes the mapping method to 3G-SDI Level-A.
[LEVEL B]	Fixes the mapping method to 3G-SDI Level-B.

#### Note

• This function does not operate when the SD-SDI signal or the HD-SDI signal is input.

<sup>• [3</sup>G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].

#### Setting [SYSTEM SELECTOR] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press ▲▼ to select [SYSTEM SELECTOR].
- 6) Press **♦** to switch the item.
  - The items will switch each time you press the button.

[AUTO]	Automatically selects [RGB], [YP <sub>B</sub> P <sub>R</sub> 4:4:4], or [YP <sub>B</sub> P <sub>R</sub> 4:2:2].
[RGB]	Fixes to [RGB].
[YP <sub>B</sub> P <sub>R</sub> 4:4:4]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:4:4].
[YP <sub>B</sub> P <sub>R</sub> 4:2:2]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:2:2].

#### Setting [BIT DEPTH] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \blacksquare$  to select [BIT DEPTH].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically select [12-bit] or [10-bit].
[12-bit]	Fixes to [12-bit].
[10-bit]	Fixes to [10-bit].

#### Setting [SIGNAL LEVEL] in [SLOT IN] (SDI input)

1) Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

• The [SLOT IN] screen is displayed.

- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.

## 134 - ENGLISH

- Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press ▲▼ to select [SIGNAL LEVEL].
- 6) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[64-940]	Normally use this setting.
[4-1019]	Select this item when gray is displayed as black.

#### When the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed

#### Setting [SDI MODE] in [SLOT IN] (SDI input)

Switch input/output of the <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal.

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SDI MODE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[INPUT]	Select this item when using the <sdi 1="" 2="" in="" out=""> terminal and the <sdi 3="" 4="" in="" out=""> terminal as SDI2 input and SDI4 input.</sdi></sdi>
[OUTPUT]	Select this item when the signal input to the <sdi 1="" in=""> terminal is output from the <sdi 1="" 2="" in="" out=""> terminal, and the signal input to the <sdi 3="" in=""> terminal is output from the <sdi 3="" 4="" in="" out=""> terminal.</sdi></sdi></sdi></sdi>

#### Note

- The <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal do not support the input of the 6G-SDI signal or the 12G-SDI signal.
- The <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal support the output of the SD-SDI signal, HD-SDI signal, 3G-SDI signal, 6G-SDI signal, and 12G-SDI signal.
- When the projector is in standby mode, a signal is not output from the <SDI 2 IN/1 OUT> terminal and the <SDI 4 IN/3 OUT> terminal.

#### Setting [SDI LINK] in [SLOT IN] (SDI input)

Press ▲▼ to select [SLOT IN].

#### 2) Press the <ENTER> button.

- The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SDI LINK], and press the <ENTER> button.

• The [SDI LINK] screen is displayed.

4) Press  $\blacktriangle \nabla$  to select an item.

[AUTO]	Automatically selects the single link, the dual link, or the quad link.
[SINGLE]	Sets the SDI1 input, the SDI2 input, the SDI3 input, and the SDI4 input of the Interface Board to single link. (Factory default setting)
[DUAL]	Sets the SDI1 input and the SDI3 input of the Interface Board to dual link.
[QUAD]	Sets the SDI1 input, the SDI2 input, the SDI3 input, and the SDI4 input of the Interface Board to quad link.

5) Press the <ENTER> button.

#### Note

- The single link is a setting to display one image with one input signal. The dual link is a setting to display one image with two input signals. The quad link is a setting to display one image with four input signals.
- [SDI LINK] is fixed to [SINGLE] in the following cases.
  - When the [DISPLAY OPTION] menu  $\rightarrow$  [SIMUL INPUT SETTING] is set to anything other than [OFF]
- When the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] is set to anything other than [OFF] and displaying the four-screen display
   The [SDI LINK] setting cannot be changed when the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set as the combination used for the SDI input of the Interface Board.
- When [SDI LINK] is set to [AUTO], use the same format for the signal to be input to the <SDI 1 IN>/<SDI 2 IN/1 OUT>/<SDI 3 IN>/<SDI 4 IN/3 OUT> terminals. If different format signal is input to even one terminal, currently displayed image may not be projected correctly.
- [SDI MAPPING] and [3G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].
- The content set is displayed in [SDI LINK SETTINGS].

#### Setting [RESOLUTION] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \forall$  to select [RESOLUTION], and press the <ENTER> button.
  - The [RESOLUTION] screen is displayed.
- 6) Press ▲▼ to select an item, and press the <ENTER> button.
  - Select [AUTO], [720x480i], [720x576i], [1280x720p], [1920x1080i], [1920x1080p], [1920x1080sF], [2048x1080p], [3840x2160p], or [4096x2160p] when SDI1 input or SDI3 input is selected for [SINGLE LINK SETTING].
  - Select [AUTO], [720x480i], [720x576i], [1280x720p], [1920x1080i], [1920x1080p], [1920x1080sF], or [2048x1080p] when SDI2 input or SDI4 input is selected for [SINGLE LINK SETTING].
  - Select [AUTO], [1920x1080i], [1920x1080p], [1920x1080sF], [2048x1080p], [3840x2160p], or [4096x2160p] when [DUAL LINK SETTING] is selected.
  - Select [AUTO], [3840x2160p], [3840x2160sF], or [4096x2160p] when [QUAD LINK SETTING] is selected.

#### Setting [4K DIVISION] in [SLOT IN] (SDI input)

Set the transmission method in the 4K division when 4K image is displayed with SDI input.

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1] or [SDI3], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \forall$  to select [4K DIVISION].
- 6) Press **♦** to switch the item.
  - The items will switch each time you press the button.

#### Chapter 4 Settings — [DISPLAY OPTION] menu

[AUTO]	Automatically selects [SQUARE] or [INTERLEAVE].
[SQUARE]	Fixes the transmission method to Square Division.
[INTERLEAVE]	Fixes the transmission method to 2-Sample Interleave Division.

#### Setting [SDI MAPPING] in [SLOT IN] (SDI input)

Set the mapping method for the SDI1 input and the SDI3 input.

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1] or [SDI3], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.

#### 5) Press ▲▼ to select [SDI MAPPING].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically selects [TYPE1/LEVEL A] or [TYPE2/LEVEL B].
[TYPE1/LEVEL A]	Fixes the mapping method to Type 1 or Level-A.
[TYPE2/LEVEL B]	Fixes the mapping method to Type 2 or Level-B.

#### Note

• This function does not operate when the SD-SDI signal or the HD-SDI signal is input.

• [SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].

#### Setting [3G-SDI MAPPING] in [SLOT IN] (SDI input)

Set the mapping method for the SDI2 input and the SDI4 input.

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI2] or [SDI4], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen for the selected item is displayed.

#### 5) Press ▲▼ to select [3G-SDI MAPPING].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically selects [LEVEL A] or [LEVEL B].
[LEVEL A]	Fixes the mapping method to 3G-SDI Level-A.
[LEVEL B]	Fixes the mapping method to 3G-SDI Level-B.

#### Note

- This function does not operate when the SD-SDI signal or the HD-SDI signal is input.
- [3G-SDI MAPPING] cannot be set when [SDI LINK] is set to [AUTO].

#### Setting [SYSTEM SELECTOR] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen for the selected item is displayed.

#### 5) Press ▲▼ to select [SYSTEM SELECTOR].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically selects [RGB], [YP <sub>B</sub> P <sub>R</sub> 4:4:4], [YP <sub>B</sub> P <sub>R</sub> 4:2:2], or [XYZ].
[RGB]	Fixes to [RGB].
[YP <sub>B</sub> P <sub>R</sub> 4:4:4]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:4:4].
[YP <sub>B</sub> P <sub>R</sub> 4:2:2]	Fixes to [YP <sub>B</sub> P <sub>R</sub> 4:2:2].
[XYZ]	Fixes to [XYZ].

#### Setting [BIT DEPTH] in [SLOT IN] (SDI input)

#### 1) Press ▲▼ to select [SLOT IN].

- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.
- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
   The [SINGLE LINK SETTING] screen for the selected item is displayed.
- 5) Press  $\blacktriangle \lor$  to select [BIT DEPTH].
- 6) Press **♦** to switch the item.
  - The items will switch each time you press the button.

[AUTO]	Automatically selects [12-bit] or [10-bit].
[12-bit]	Fixes to [12-bit].
[10-bit]	Fixes to [10-bit].

#### Setting [SIGNAL LEVEL] in [SLOT IN] (SDI input)

- 1) Press ▲▼ to select [SLOT IN].
- 2) Press the <ENTER> button.
  - The [SLOT IN] screen is displayed.

## 138 - ENGLISH

- 3) Press ▲▼ to select [SINGLE LINK SETTING], [DUAL LINK SETTING], or [QUAD LINK SETTING], and press the <ENTER> button.
  - The [SINGLE LINK SETTING] screen, the [DUAL LINK SETTING] screen, or the [QUAD LINK SETTING] screen is displayed.
  - Proceed to Step 5) when [DUAL LINK SETTING] or [QUAD LINK SETTING] is selected.
- 4) Press ▲▼ to select [SDI1], [SDI2], [SDI3], or [SDI4], and press the <ENTER> button.
  - The **[SINGLE LINK SETTING]** screen for the selected item is displayed.

5) Press ▲▼ to select [SIGNAL LEVEL].

#### 6) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[64-940]	Normally use this setting.
[4-1019]	Select this item when gray is displayed as black.

## [ON-SCREEN DISPLAY]

Set the on-screen display.

#### Setting [OSD POSITION]

Set the position of the menu screen (OSD).

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

- 2) Press the <ENTER> button.
  - The [ON-SCREEN DISPLAY] screen is displayed.
- 3) Press ▲▼ to select [OSD POSITION].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[2]	Sets to the center left of the screen.
[3]	Sets to the bottom left of the screen.
[4]	Sets to the top center of the screen.
[5]	Sets to the center of the screen.
[6]	Sets to the bottom center of the screen.
[7]	Sets to the upper right of the screen.
[8]	Sets to the center right of the screen.
[9]	Sets to the bottom right of the screen.
[1]	Sets to the upper left of the screen.

### Setting [OSD SIZE]

Set the display size of the menu screen (OSD).

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

#### 2) Press the <ENTER> button.

- The [ON-SCREEN DISPLAY] screen is displayed.
- 3) Press  $\blacktriangle \blacksquare$  to select [OSD SIZE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[NORMAL]	Does not enlarge the text size.
[DOUBLE]	Displays the menu screen with the text size enlarged to double size.

#### Note

- [OSD SIZE] cannot be set when the [ADVANCED MENU] menu → [QUAD PIXEL DRIVE] is set to [ON]. The menu screen with the text size enlarged to double size is displayed.
- [OSD SIZE] cannot be set when the [DISPLAY OPTION] menu → [SIMUL INPUT SETTING] is set to [AUTO(x2-speed)] or [AUTO(x4-speed)] and displaying the image in simultaneous format.

#### Setting [OSD ROTATION]

Set the orientation of the menu screen (OSD).

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

#### 2) Press the <ENTER> button.

The [ON-SCREEN DISPLAY] screen is displayed.

#### 3) Press $\blacktriangle \lor$ to select [OSD ROTATION].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Does not rotate the screen.
[CLOCKWISE]	Rotates the screen by 90° clockwise.
[COUNTERCLOCKWISE]	Rotates the screen by 90° counterclockwise.

#### Setting [OSD DESIGN]

Set the color of the menu screen (OSD).

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

- 2) Press the <ENTER> button.
  - The [ON-SCREEN DISPLAY] screen is displayed.

#### 3) Press $\blacktriangle \lor$ to select [OSD DESIGN].

#### 4) Press **♦** to switch the item.

• The items will switch each time you press the button.

[1]	Sets to yellow.
[2]	Sets to blue.
[3]	Sets to white.
[4]	Sets to green.
[5]	Sets to peach.
[6]	Sets to brown.

#### Setting [OSD MEMORY]

Set hold for the position of the menu screen (OSD) cursor.

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

#### 2) Press the <ENTER> button.

- The [ON-SCREEN DISPLAY] screen is displayed.
- 3) Press  $\blacktriangle \blacksquare$  to select [OSD MEMORY].
- 4) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[ON]	Holds the cursor position.
[OFF]	Does not hold the cursor position.

#### Note

The cursor position is not maintained even if [OSD MEMORY] is set to [ON].

#### Setting [INPUT GUIDE]

Set whether to display the input guide in the position set in [OSD POSITION].

The input guide is the screen to display the information such as currently selected input terminal name, signal name, memory number, the input terminal and signal structuring [MULTI DISPLAY], and [BACKUP INPUT STATUS].

- 1) Press ▲▼ to select [ON-SCREEN DISPLAY].
- 2) Press the <ENTER> button.
  The [ON-SCREEN DISPLAY] screen is displayed.
- 3) Press  $\blacktriangle \lor$  to select [INPUT GUIDE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[ON]	Displays the input guide.
[OFF]	Hides the input guide.

#### Setting [WARNING MESSAGE]

Set the display/hide of the warning message.

#### 1) Press ▲▼ to select [ON-SCREEN DISPLAY].

2) Press the <ENTER> button.

• The [ON-SCREEN DISPLAY] screen is displayed.

#### 3) Press ▲▼ to select [WARNING MESSAGE].

#### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[ON]	Displays the warning message.
[OFF]	Hides the warning message.

#### Note

 If [OFF] is set, the warning message will not be displayed on the projected image even when warning condition such as [TEMPERATURE WARNING] or [CLEAN THE AIR FILTER] is detected while using the projector. Also, the following countdown message is not displayed: the message until the power is turned off after the no signal lights-out function is executed; the message until the light source is turned off after the no signal lights-out function is executed

### [BACK COLOR]

Set the display of the projected screen when there is no signal input.

#### 1) Press ▲▼ to select [BACK COLOR].

#### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[BLUE]	Displays the entire projection area in blue.
[BLACK]	Displays the entire projection area in black.
[DEFAULT LOGO]	Displays the Panasonic logo.
[USER LOGO]	Displays the image registered by the user.

#### Note

• To create/register the [USER LOGO] image, use "Logo Transfer Software" included in the supplied CD-ROM.

## [STARTUP LOGO]

Set the logo display when the power is turned on.

1) Press ▲▼ to select [STARTUP LOGO].

#### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[DEFAULT LOGO]	Displays the Panasonic logo.
[USER LOGO]	Displays the image registered by the user.
[NONE]	Disables the startup logo display.

#### Note

- When [USER LOGO] is selected, the display of the startup logo will be kept for approximately 15 seconds.
- To create/register the [USER LOGO] image, use "Logo Transfer Software" included in the supplied CD-ROM.

## [UNIFORMITY]

Correct the brightness and color unevenness of the entire screen.

#### Setting each color

1) Press  $\blacktriangle \forall$  to select [UNIFORMITY].

#### 2) Press the <ENTER> button.

- The [UNIFORMITY] screen is displayed.
- 3) Press ▲▼ to select [WHITE], [RED], [GREEN], or [BLUE].

#### 4) Press **♦** to adjust the level.

Item	Operation	Adjustment	Range of adjustment
[VERTICAL]	Press ▶.	The lower-side color becomes pale, or the upper-side color becomes dark.	-127 - +127
	Press ◀.	The upper-side color becomes pale, or the lower-side color becomes dark.	
[HORIZONTAL]	Press ▶.	The left-side color becomes pale, or the right-side color becomes dark.	
	Press ◀.	The right-side color becomes pale, or the left-side color becomes dark.	

#### Setting [PC CORRECTION]

Set the [PC CORRECTION] function to correct the brightness and the color unevenness of the entire screen using a computer.

To use the [PC CORRECTION] function, the optional Upgrade Kit (Model No.: ET-UK20) is required. To purchase the product, consult your dealer.

#### 1) Press ▲▼ to select [UNIFORMITY].

- 2) Press the <ENTER> button.
  - The [UNIFORMITY] screen is displayed.
- 3) Press ▲▼ to select [PC CORRECTION].
- 4) Press **♦** to switch the item.

[OFF]	Does not perform correction using a computer.
[ON]*1	Performs correction for the brightness and color unevenness of the entire screen using a computer.

\*1 Advanced skills are necessary to use computer control correction. Consult your dealer.

#### Note

The setting value for [UNIFORMITY] will not return to factory default even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

### [SHUTTER SETTING]

The operation of the shutter function is set.

#### Setting [MECHANICAL SHUTTER]

- 1) Press ▲▼ to select [SHUTTER SETTING].
- 2) Press the <ENTER> button.
  - The [SHUTTER SETTING] screen is displayed.

#### 3) Press ▲▼ to select [MECHANICAL SHUTTER].

#### 4) Press **♦** to switch the item.

[ENABLE]	Closes the mechanical shutter when the shutter function is enabled (shutter: closed).
[DISABLE]	Leaves the mechanical shutter open and turns off the light source when the shutter function is enabled (shutter: closed).

#### Note

- By closing the mechanical shutter, the malfunction of the DLP chip caused by high power laser ray entering the projection lens surface can be prevented. To close the mechanical shutter, set [MECHANICAL SHUTTER] to [ENABLE] and then set the shutter function to be enabled (shutter: closed).
- When [MECHANICAL SHUTTER] is set to [ENABLE], it will take approximately 0.5 seconds from when the shutter function is enabled (shutter: closed) to the shutter function is disabled (shutter: opened).
- The light source may turn on darker to warm up when the shutter function is used when the operating environment temperature is around 0 °C (32 °F) when [MECHANICAL SHUTTER] is set to [DISABLE].

### Setting [FADE-IN] or [FADE-OUT]

Set the image fade-in and fade-out when the shutter function operates.

#### 1) Press $\blacktriangle \lor$ to select [SHUTTER SETTING].

#### 2) Press the <ENTER> button.

- The [SHUTTER SETTING] screen is displayed.
- 3) Press ▲▼ to select [FADE-IN] or [FADE-OUT].
- 4) Press  $\triangleleft$  to switch the item.

lt	em	Adjustment
	[OFF]	Does not set fade-in or fade-out.
[FADE-IN] [FADE-OUT]	[0.5s] - [10.0s]	Sets the fade-in or fade-out time. Select an item from [0.5s] - [4.0s], [5.0s], [7.0s], or [10.0s]. [0.5s] - [4.0s] can be selected in increments of 0.5.

#### Note

• Press the <SHUTTER> button on the remote control or the control panel during fade-in or fade-out to cancel the fade operation.

#### Setting [STARTUP]

Automatically enable/disable the shutter function (shutter: closed/open) when the power is turned on.

#### 1) Press ▲▼ to select [SHUTTER SETTING].

- 2) Press the <ENTER> button.
  - The [SHUTTER SETTING] screen is displayed.
- 3) Press ▲▼ to select [STARTUP].

#### 4) Press $\triangleleft$ to switch the item.

[OPEN]	The projector goes into projection mode with the shutter function disabled (shutter: opened) when the power is turned on.
[CLOSE]	The projector goes into projection mode with the shutter function enabled (shutter: closed) when the power is turned on.

### Setting [SHUT-OFF]

Automatically open/close the mechanical shutter when the power is turned off.

- 1) Press  $\blacktriangle \lor$  to select [SHUTTER SETTING].
- 2) Press the <ENTER> button.

• The [SHUTTER SETTING] screen is displayed.

- 3) Press ▲▼ to select [SHUT-OFF].
- 4) Press  $\triangleleft$  to switch the item.

[KEEP CURRENT STATE]	The projector goes into standby mode with the condition of the mechanical shutter maintained when the projector is switched off.
[OPEN]	The projector goes into standby mode with the mechanical shutter opened when the projector is switched off.
[CLOSE]	The projector goes into standby mode with the mechanical shutter closed when the projector is switched off.

#### Setting the shutter synchronization function

The shutter synchronization function is a function to synchronize the shutter operation of the specified projector to other projectors, and the effect using the shutter function including the fade in/fade out operation can be synchronized.

To use the shutter synchronization function, it is necessary to connect the projectors targeted for synchronization in a loop with daisy chain connection using the <MULTI PROJECTOR SYNC IN> terminal and the <MULTI PROJECTOR SYNC OUT> terminal. For details of how to connect the projectors, refer to "Connecting example when using the contrast synchronization function/shutter synchronization function" (+ page 59).

#### 1) Press ▲▼ to select [SHUTTER SETTING].

- 2) Press the <ENTER> button.
  - The [SHUTTER SETTING] screen is displayed.

#### 3) Press ▲▼ to select [MULTI PROJECTOR SYNC].

#### 4) Press the <ENTER> button.

• The [MULTI PROJECTOR SYNC] screen is displayed.

#### 5) Press $\blacktriangle \forall$ to select [MODE].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Select this item when the contrast synchronization function and the shutter synchronization function are not used.
[MASTER]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item only on one of the linked projectors that becomes the synchronization source of the shutter operation.
[SLAVE]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item in all the linked projectors excluding the projector set as the [MASTER].

• When anything other than [OFF] is selected, the diagnostic result is displayed in [LINK STATUS], indicating if all the projectors including the projectors targeted for synchronization are correctly connected, and if [MODE] is correctly set.

[LINKED]	All the projectors are correctly connected, and correctly set. They are in the condition that the contrast synchronization function or the shutter synchronization function can be used.
	The projectors are not correctly connected, or not correctly set. Check the cable connection status and the projector setting for each projector that is linked.

#### 7) Press ▲▼ to select [SHUTTER SYNC].

## 144 - ENGLISH

# 8) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Select this item when the shutter synchronization function is not used.
[ON]	Select this item when the shutter synchronization function is used.

### Note

- The [MULTI PROJECTOR SYNC] setting item is common with the following menu item.
- The [PROJECTOR SETUP] menu  $\rightarrow$  [MULTI PROJECTOR SYNC]
- For details on contrast synchronization function, refer to the [PROJECTOR SETUP] menu  $\rightarrow$  [MULTI PROJECTOR SYNC] ( $\Rightarrow$  page 173). • The shutter synchronization function will operate when all of the following conditions are fulfilled.
- All the projectors to be linked are connected in a loop with the daisy chain connection. (Maximum 64 projectors)
- [MODE] on only one projector that is linked is set to [MASTER], and [MODE] on all other projectors are set to [SLAVE].
- [SHUTTER SYNC] on the projectors to perform the shutter synchronization is set to [ON].
- It is possible to set [SHUTTER SYNC] to [OFF] for the projectors that are linked but not to synchronize.
- The shutter operation by the shutter synchronization function will follow the setting of the [DISPLAY OPTION] menu → [SHUTTER SETTING] on the projector that [MODE] is set to [MASTER].
- The operation of the mechanical shutter is not included in the shutter synchronization function.
- When the input signal to each linked projector is not synchronized, the timing of the shutter operation between the projectors may shift up to 1 frame while using the shutter synchronization function.
- The shutter function of the projector with [MODE] set to [SLAVE] can be operated individually. At that time, the shutter operation will follow
  the setting of the [DISPLAY OPTION] menu → [SHUTTER SETTING] set in that projector.

# [FREEZE]

Pause the projected image temporarily regardless of the playback of the external device.

- 1) Press ▲▼ to select [FREEZE].
- 2) Press the <ENTER> button.
  - Press the <MENU> button to release.

### Note

- [FREEZE] is displayed on the screen when video is paused.
- When an image from one input terminal is displayed on multiple screens while in the four-screen display mode, the appearance may vary for each image being paused. Set the [MULTI DISPLAY] menu → [MULTI DISPLAY MODE] to anything other than [OFF] when using the fourscreen display mode.

# [WAVEFORM MONITOR]

Use the input signals from a connected external device to display in a waveform. Check whether video output (luminance) signal level is within the recommended range for the projector and adjust.

- 1) Press ▲▼ to select [WAVEFORM MONITOR].
- 2) Press **♦** to switch the item.

[OFF]	Does not display the waveform monitor.
[ON]	Displays the waveform monitor.

- 3) Press the <MENU> button two times to clear.
- 4) Press ▲▼ to select any horizontal line.
- 5) Press the <ENTER> button to switch the Select line to either luminance, red, green, or blue.
  - Line selection items switch each time the <ENTER> button is pressed only when the waveform monitor is displayed.

"Select line (luminance)"	Displayed in white waveform.
"Select line (red)"	Displayed in red waveform.
"Select line (green)"	Displayed in green waveform.
"Select line (blue)"	Displayed in blue waveform.

### Note


The waveform monitor cannot be displayed while in the four-screen display mode. Set the [MULTI DISPLAY] menu → [MULTI DISPLAY] MODE] to anything other than [OFF] when using the four-screen display mode.

Setting is also available from the [PROJECTOR SETUP] menu → [FUNCTION BUTTON].

- The waveform monitor turns off when [MULTI DISPLAY] is executed during waveform monitoring.
- The waveform monitor is not displayed when on-screen display is hidden (off).

## Adjusting the waveform

Project the luminance adjustment signal of a commercial test disk (0 % (0 IRE or 7.5 IRE) – 100 % (100 IRE)) and adjust.



1) Select "Select line (luminance)" on the waveform monitor.

### 2) Adjust black level.

 Adjust the black level 0 % of the video signal to the 0 % position of the waveform monitor using the [PICTURE] menu → [BRIGHTNESS].

3) Adjust white level.

 Adjust the white level 100 % of the video signal to the 100 % position of the waveform monitor using the [PICTURE] menu → [CONTRAST].

# Adjusting red, green, and blue

- 1) Set [COLOR TEMPERATURE] to [USER1] or [USER2] (⇒ page 94).
- 2) Select "Select line (red)" on the waveform monitor.
- 3) Adjust dark red areas.
  - Use [RED] in [WHITE BALANCE LOW] to adjust the black level 0 % of the video signal to the 0 % position
    of the waveform monitor.
- 4) Adjust bright red areas.
  - Use [RED] in [WHITE BALANCE HIGH] to adjust the white level 100 % of the video signal to the 100 % position of the waveform monitor.

# 5) Use the procedure for [RED] to adjust [GREEN] and [BLUE].

### Note

• Confirm that the [SIGNAL LEVEL] setting of the input signal is correct before adjusting the black level.

Check the [SIGNAL LEVEL] setting in following menu in accordance with the input.

- The [DISPLAY OPTION] menu  $\rightarrow$  [DIGITAL LINK IN]  $\rightarrow$  [SIGNAL LEVEL]
- − The [DISPLAY OPTION] menu → [SLOT IN] → [SINGLE LINK SETTING]/[DUAL LINK SETTING]/[QUAD LINK SETTING] → [SIGNAL LEVEL]

<sup>−</sup> The [DISPLAY OPTION] menu → [SDI IN] → [SINGLE LINK SETTING]/[DUAL LINK SETTING]/[QUAD LINK SETTING] → [SIGNAL LEVEL]

# [CUT OFF]

Each red, green, and blue color component can be removed.

- 1) Press  $\blacktriangle \forall$  to select [CUT OFF].
- 2) Press the <ENTER> button.
   The [CUT OFF] screen is displayed.
- 3) Press ▲▼ to select [RED], [GREEN], or [BLUE].

# 4) Press $\triangleleft$ to switch the item.

[OFF]	Disables cutoff.
[ON]	Enables cutoff.

Note

• When input is switched or a signal is switched, the cutoff setting returns to its original setting (off).

# [PROJECTOR SETUP] menu

On the menu screen, select [PROJECTOR SETUP] from the main menu, and select an item from the submenu.

Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

# [PROJECTOR ID]

The projector has an ID number setting function that can be used when multiple projectors are used side by side to enable simultaneous control or individual control via a single remote control.

# 1) Press $\blacktriangle \forall$ to select [PROJECTOR ID].

## 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[ALL]	Select this item when controlling projectors without specifying an ID number.
[1] - [64]	Select this item when specifying an ID number to control individual projector.

#### Note

- To specify an ID number for individual control, the ID number of a remote control must match the ID number of the projector.
- When the ID number is set to [ALL], the projector will operate regardless of the ID number specified during remote control or computer control.
- If multiple projectors are set up side by side with IDs set to [ALL], they cannot be controlled separately from the projectors with other ID numbers.
- Refer to "Setting ID number of the remote control" (> page 86) for how to set the ID number on the remote control.

# [PROJECTION METHOD]

Set the projection method in accordance with the installation status of the projector.

Change the [FRONT/REAR] setting when the screen display is inverted.

Change the [FLOOR/CEILING] setting when the screen display is upside down.

# Setting [FRONT/REAR]

- 1) Press ▲▼ to select [PROJECTION METHOD].
- 2) Press the <ENTER> button.
  - The [PROJECTION METHOD] screen is displayed.
- 3) Press ▲▼ to select [FRONT/REAR].

### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[FRONT]	Select this item when installing the projector in front of the screen.
[REAR]	Select this item when installing behind the screen (using translucent screen).

# Setting [FLOOR/CEILING]

# 1) Press $\blacktriangle$ to select [PROJECTION METHOD].

- 2) Press the <ENTER> button.
   The [PROJECTION METHOD] screen is displayed.
- 3) Press ▲▼ to select [FLOOR/CEILING].

# 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[AUTO]	Automatically detects the attitude of the projector by the built-in angle sensor. Set [AUTO] normally.
[FLOOR]	Select this item when installing the projector on a desk, etc.

Select this item when installing the projector with the top surface of the projector facing down such as ceiling attachment.	
 Projected image is inverted upside down.	

• Refer to "Angle sensor" (> page 40) for details on the range of the installation attitude that can be detected by the built-in angle sensor.

# [LENS]

Perform the setting and operation regarding the projection lens.

# [LENS TYPE]

When the projector is used for the first time or when the projection lens is replaced, confirm the [LENS TYPE] setting. Change the setting if the type is different from the projection lens attached to the projector. If the [LENS TYPE] information is written into the EEPROM (Electrically Erasable Programmable Read-Only Memory) built in the projection lens, that information is automatically acquired as the setting value of the projector when the projector is turned on.

1) Press ▲▼ to select [LENS].

# 2) Press the <ENTER> button.

• The [LENS] screen is displayed, allowing to confirm the current setting in [LENS TYPE].

• To change the setting, proceed to Step 3).

# 3) Press ▲▼ to select [LENS TYPE].

## 4) Press the <ENTER> button.

• The [LENS TYPE] screen is displayed.

## 5) Press $\blacktriangle \nabla$ to select an item.

• Select the type of projection lens attached to the projector.

ET-D75LE95	Select this item when the Fixed-focus Lens (Model No.: ET-D75LE95) is attached to the projector.
ET-D75LE90*1	Select this item when the Fixed-focus Lens (Model No.: ET-D75LE90) is attached to the projector.
ET-D75LE50	Select this item when the Fixed-focus Lens (Model No.: ET-D75LE50) is attached to the projector.
ET-D75LE6	Select this item when the Zoom Lens (Model No.: ET-D75LE6) is attached to the projector.
ET-D75LE10	Select this item when the Zoom Lens (Model No.: ET-D75LE10) is attached to the projector.
ET-D75LE20	Select this item when the Zoom Lens (Model No.: ET-D75LE20) is attached to the projector. (Factory default setting)
ET-D75LE30	Select this item when the Zoom Lens (Model No.: ET-D75LE30) is attached to the projector.
ET-D75LE40	Select this item when the Zoom Lens (Model No.: ET-D75LE40) is attached to the projector.
ET-D75LE8	Select this item when the Zoom Lens (Model No.: ET-D75LE8) is attached to the projector.

\*1 Set the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] to 77.0 % or less when the Fixed-focus Lens (Model No.: ET-D75LE90) is used. The focus performance is not achieved when used in setting exceeding 77.0 %.

# 6) Press the <ENTER> button.

### Note

- If a projection lens equipped with EEPROM is attached, the [LENS TYPE] setting is written into the EEPROM of the projection lens. If a projection lens without built-in EEPROM is attached, the [LENS TYPE] setting is saved in the projector as user data.
- If the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), [LENS TYPE] is set to [NOT SELECTED] when it is used for the first time. By selecting the type of the projection lens and pressing the <ENTER> button, selected [LENS TYPE] information is written to the EEPROM installed in the stepping motor unit.
- [LENS HOME POSITION], [ACTIVE FOCUS OPTIMIZER], and [LENS CALIBRATION] cannot be executed when [LENS TYPE] is set to [NOT SELECTED].
- [LENS HOME POSITION], [ACTIVE FOCUS OPTIMIZER], and [LENS CALIBRATION] will not operate correctly when [LENS TYPE] is set incorrectly.
- When a projection lens equipped with EEPROM is attached, [LENS TYPE] will not return to factory default setting even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

# [LENS INFORMATION SETTING]

# Confirming the projection lens information

## 1) Press ▲▼ to select [LENS].

# 2) Press the <ENTER> button.

• The [LENS] screen is displayed.

# 3) Press ▲▼ to select [LENS INFORMATION SETTING].

# 4) Press the <ENTER> button.

• The [LENS INFORMATION SETTING] screen is displayed.

[LENS ID]	Displays the set ID.
[LENS NAME]	Displays the set name.
[LENS TYPE]	Displays the set projection lens type.
[LENS ZOOM TYPE]	Displays the drive method of the zoom motor.

#### Note

• [LENS INFORMATION SETTING] is not displayed when a projection lens without built-in EEPROM is attached.

### Setting ID to the projection lens

Write the identification information unique to the projection lens into the EEPROM built in the projection lens. Set ID if required.

#### 1) Press ▲▼ to select [LENS].

- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [LENS INFORMATION SETTING].

### 4) Press the <ENTER> button.

• The [LENS INFORMATION SETTING] screen is displayed.

### 5) Press $\blacktriangle \forall$ to select [LENS ID].

### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[ALL]	Select this item when the ID number is not to be specified.
[1] - [255]	Select this item when the ID number is to be set.

#### Note

- [LENS INFORMATION SETTING] is not displayed when a projection lens without built-in EEPROM is attached.
- If the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), the [LENS ID]
- information is written into the EEPROM built in the stepping motor unit every time the [LENS ID] item is switched. • [LENS ID] will not return to factory default setting even when the [PROJECTOR SETUP] menu  $\rightarrow$  [INITIALIZE]  $\rightarrow$  [ALL USER DATA] is

### Setting name to the projection lens

A name for identifying individual projection lens can be written into the EEPROM built in the projection lens. Set the name if required.

## Press ▲▼ to select [LENS].

- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [LENS INFORMATION SETTING].

executed.

- 4) Press the <ENTER> button.
  - The [LENS INFORMATION SETTING] screen is displayed.
- 5) Press  $\blacktriangle \forall$  to select [LENS NAME].
- 6) Press the <ENTER> button.
  - The [LENS NAME INPUT] screen is displayed.
- 7) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the character, and press the <ENTER> button to enter the character.
- 8) Press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - Name of the projection lens is changed.

- [LENS INFORMATION SETTING] is not displayed when a projection lens without built-in EEPROM is attached.
- Factory default name is [LENS01].
- If the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), the [LENS NAME] information is written into the EEPROM built in the stepping motor unit.
- [LENS NAME] will not return to factory default setting even when the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is
  executed.

# [LENS MEMORY]

The adjusted lens position (vertical position, horizontal position, focus position, and zoom position) can be saved and loaded.

### Saving lens position

- 1) Press ▲▼ to select [LENS].
- 2) Press the <ENTER> button.
   The [LENS] screen is displayed.
- 3) Press ▲▼ to select [LENS MEMORY].
- 4) Press the <ENTER> button.
  - The [LENS MEMORY] screen is displayed.
- 5) Press ▲▼ to select [LENS MEMORY SAVE].
- 6) Press the <ENTER> button.
  - The [LENS MEMORY SAVE] screen is displayed.
  - If the lens memory has already been saved, the name of the saved lens memory and its lens position information ([VERTICAL POSITION]/[HORIZONTAL POSITION]/[FOCUS POSITION]/[ZOOM POSITION]) are displayed in the [LENS MEMORY SAVE] screen.
- 7) Press  $\blacktriangle \forall$  to select the item to save, and press the <ENTER> button.
  - The confirmation screen is displayed.
  - Current lens position information ([VERTICAL POSITION]/[HORIZONTAL POSITION]/[FOCUS POSITION]/ [ZOOM POSITION]) is displayed in the confirmation screen.
- 8) Press **♦** to select [OK], and press the **<**ENTER> button.
  - The [LENS MEMORY NAME INPUT] screen is displayed.
- 9) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the text, and press the <ENTER> button to enter the text.
- 10) After the name is input, press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - Saving of the lens memory is completed, and the [LENS MEMORY SAVE] screen returns.
  - If you press ▲▼◀▶ to select [CANCEL] and then press the <ENTER> button, the lens memory will not be saved.
  - If you press ▲▼◀▶ to select [DEFAULT] and press the <ENTER> button, the entered name will not be registered and the default name will be used.
  - If you select [OK] without entering any characters and press the <ENTER> button, the default name will be used.

- The numeric value information of the zoom position is displayed only in following cases.
- When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10)
- When the projection lens with stepping motor is attached

### Loading the lens position

### 1) Press ▲▼ to select [LENS].

2) Press the <ENTER> button.

• The [LENS] screen is displayed.

- Press ▲▼ to select [LENS MEMORY].
- 4) Press the <ENTER> button.
  - The [LENS MEMORY] screen is displayed.
- 5) Press ▲▼ to select [LENS MEMORY LOAD].
- 6) Press the <ENTER> button.
  - The [LENS MEMORY LOAD] screen is displayed.
  - The name of the saved lens memory and its lens position information ([VERTICAL POSITION]/ [HORIZONTAL POSITION]/[FOCUS POSITION]/[ZOOM POSITION]) are displayed in the [LENS MEMORY LOAD] screen.
- 7) Press  $\blacktriangle \forall$  to select the item to load, and press the <ENTER> button.
  - The confirmation screen is displayed.

## 8) Press **♦** to select [OK], and press the <ENTER> button.

• The lens will automatically move to the lens position (vertical position, horizontal position, focus position, and zoom position) of the loaded lens memory.

### Note

- Lens memory is not guaranteed to be 100 % reproduced. Readjust the focus, zoom, and lens shift after loading the lens memory if required.
- If the projection lens is replaced, execute the [PROJECTOR SETUP] menu → [LENS] → [LENS CALIBRATION], readjust the focus, zoom, and lens shift, and save the lens memory again.
- The lens memory for the zoom position will not operate when a projection lens without the zoom function is used.
- The numeric value information of the zoom position is displayed only in following cases.
- When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20,
- ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10) - When the projection lens with stepping motor is attached
- The saved lens memory is loaded in order every time the <FUNCTION> button is pressed when [LENS MEMORY LOAD] is assigned to the <FUNCTION> button.

### Deleting a lens memory

# 1) Press ▲▼ to select [LENS].

2) Press the <ENTER> button.

• The [LENS] screen is displayed.

- 3) Press  $\blacktriangle$   $\checkmark$  to select [LENS MEMORY].
- 4) Press the <ENTER> button.
   The [LENS MEMORY] screen is displayed.
- 5) Press ▲▼ to select [LENS MEMORY EDIT].
- 6) Press the <ENTER> button.
   The [LENS MEMORY EDIT] screen is displayed.
- 7) Press ▲▼ to select [LENS MEMORY DELETE].
- 8) Press the <ENTER> button.
  - The [LENS MEMORY DELETE] screen is displayed.

# 152 - ENGLISH

- The name of the saved lens memory and its lens position information ([VERTICAL POSITION]/ [HORIZONTAL POSITION]/[FOCUS POSITION]/[ZOOM POSITION]) are displayed in the [LENS MEMORY DELETE] screen.
- 9) Press  $\blacktriangle \forall$  to select the item to delete, and press the <ENTER> button.
  - The confirmation screen is displayed.
- 10) Press **♦** to select [OK], and press the **<**ENTER> button.

- The numeric value information of the zoom position is displayed only in following cases.
- When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10)
- When the projection lens with stepping motor is attached

### Changing the lens memory name

- 1) Press ▲▼ to select [LENS].
- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [LENS MEMORY].
- 4) Press the <ENTER> button.

• The [LENS MEMORY] screen is displayed.

- 5) Press ▲▼ to select [LENS MEMORY EDIT].
- 6) Press the <ENTER> button.
   The [LENS MEMORY EDIT] screen is displayed.
- 7) Press ▲▼ to select [LENS MEMORY NAME CHANGE].
- 8) Press the <ENTER> button.
  - The [LENS MEMORY NAME CHANGE] screen is displayed.
  - The name of the saved lens memory and its lens position information ([VERTICAL POSITION]/ [HORIZONTAL POSITION]/[FOCUS POSITION]/[ZOOM POSITION]) are displayed in the [LENS MEMORY NAME CHANGE] screen.
- 9) Press  $\blacktriangle \forall$  to select the name to change, and press the <ENTER> button.
  - The [LENS MEMORY NAME INPUT] screen is displayed.
- 10) Press  $\blacktriangle \forall \blacklozenge \forall$  to select the text, and press the <ENTER> button to enter the text.
- 11) After the name is changed, press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - Saving of the lens memory is completed, and the [LENS MEMORY NAME CHANGE] screen returns.
  - If you press ▲▼◀▶ to select [CANCEL] and then press the <ENTER> button, the changed name will not be registered.
  - If you press ▲▼◀▶ to select [DEFAULT] and press the <ENTER> button, the changed name will not be registered and the default name will be used.
  - If you select [OK] without entering any characters and press the <ENTER> button, the default name will be used.

### Note

- The numeric value information of the zoom position is displayed only in following cases.
  - When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20,
  - ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10) - When the projection lens with stepping motor is attached

# [LENS HOME POSITION]

Operate in following procedure to move the projection lens to the home position.

1) Press ▲▼ to select [LENS].

- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [LENS HOME POSITION].
- 4) Press the <ENTER> button.
  - The confirmation screen is displayed.
- 5) Press **♦** to select [OK], and press the **<**ENTER> button.
  - [PROGRESS] is displayed in the [HOME POSITION] screen, and the projection lens is moved to the origin position.

- [LENS HOME POSITION] cannot be executed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- [LENS HOME POSITION] can also be executed by pressing the <DEFAULT> button on the remote control while the lens shift adjustment screen is displayed.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).

# [ACTIVE FOCUS OPTIMIZER]

Enable/disable the active focus optimizer function. The shift in focus caused by the change of the image brightness can be reduced by enabling this function. It will also reduce the shift in focus for the focus right before enabling the shutter function (shutter: closed) and the focus right after disabling the shutter function (shutter: open).

# 1) Press ▲▼ to select [LENS].

2) Press the <ENTER> button.

• The [LENS] screen is displayed.

- 3) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- 4) Press the <ENTER> button.
   The [ACTIVE FOCUS OPTIMIZER] screen is displayed.

• The [ACTIVE FOCUS OP TIMIZER] Screen is display

# 5) Press $\blacktriangle \blacksquare$ to select [ACTIVE FOCUS].

6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the active focus optimizer function.
[ON]	Enables the active focus optimizer function.

### Note

- [ACTIVE FOCUS] cannot be set when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- When this function is set to [ON], the focus adjustment (adjustment of the focus position of the lens) is automatically performed when the brightness of the image changes. Note following especially when constructing multi-display using multiple projectors such as using the edge blending function by setting the [ADVANCED MENU] menu → [EDGE BLENDING].
  - Position of the projected image may slightly shift due to the amount of focus adjustment.
  - The projected image may slightly undulate during the focus adjustment.
- When this function is set to [ON], driving sound of the focus adjustment motor may be audible when the brightness of the image changes.
- When this function is set to [ON], the setting status of [ACTIVE FOCUS OPTIMIZER] ([ON]) is displayed in the focus adjustment screen.
- The active focus optimizer function operates within the range of focus adjustment. It may not operate properly when used close to the limit
  value for the focus adjustment.
- The active focus optimizer function may not correctly operate when the optional Lens Fixed Attachment (Model No.: ET-PLF10) is attached. Do not press the lens fixing clasp of the Lens Fixed Attachment too strong against the projection lens.
- The value of the parameter used by the active focus optimizer function is displayed as [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK].
- Parameter for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] will be the factory default value set for each type of projection lens in following cases.
  - When the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [FOCUS OFFSET SETUP]  $\rightarrow$  [SETUP ASSISTANT] is not executed
  - When the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [FOCUS OFFSET SETUP]  $\rightarrow$  [INITIALIZE] is executed
- When the <DEFAULT> button is pressed while [FOCUS OFFSET BRIGHT] or [FOCUS OFFSET DARK] is selected
- To reduce the shift in focus caused by the change in the brightness of the image, set [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] following the guidance in [SETUP ASSISTANT]. For details, refer to "Performing simplified setting using the internal test pattern"
   (+ page 155), "Performing simplified setting using the external input image" (+ page 156).
- [ACTIVE FOCUS] will be set to [OFF] when the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

# 154 - ENGLISH

# Performing simplified setting using the internal test pattern

Set the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] using the test pattern built in the projector following the guidance of [SETUP ASSISTANT].

- 1) Press  $\blacktriangle \blacksquare$  to select [LENS].
- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- 4) Press the <ENTER> button.

• The [ACTIVE FOCUS OPTIMIZER] screen is displayed.

# 5) Press ▲▼ to select [FOCUS OFFSET SETUP].

# 6) Press the <ENTER> button.

• The [FOCUS OFFSET SETUP] screen is displayed.

# 7) Press ▲▼ to select [SETUP ASSISTANT].

# 8) Press the <ENTER> button.

- If the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to [100.0%], the internal focus test pattern of signal level approximately 50 % is projected, and the [SETUP ASSISTANT] screen (page 1/8) is displayed. Proceed to Step 10).
- If the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to less than [100.0%], the confirmation screen is displayed. Proceed to Step 9).

# 9) Press **♦** to select [NEXT], and press the **<**ENTER> button.

- Even if the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to less than [100.0%], the projector will
  operate with the [100.0%] setting while [SETUP ASSISTANT] is executing. Once [SETUP ASSISTANT] is
  completed, it will return to the original [LIGHT OUTPUT] setting value.
- After confirming the confirmation message, press ◀▶ to select [NEXT], and press the <ENTER> button. The internal focus test pattern of signal level approximately 50 % is projected, and the [SETUP ASSISTANT] screen (page 1/8) is displayed.
- To cancel the setting by [SETUP ASSISTANT], press ◀▶ to select [CANCEL], and press the <ENTER> button. [SETUP ASSISTANT] is cancelled, and the [FOCUS OFFSET SETUP] screen is displayed.

# 10) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.

# 11) Press **♦** to select [NEXT], and press the **<**ENTER> button.

- The [SETUP ASSISTANT] screen (page 2/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 12) Press ▲▼◀▶ to select [FOCUS POSITION].

- 13) Press the ◀▶ button to adjust the focus.
- 14) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.
   The [SETUP ASSISTANT] screen (page 3/8) is displayed.
- 15) Press ▲▼◀▶ to select [TEST PATTERN].

# 16) Press ◀▶ to select [INTERNAL].

• The items will switch each time you press the button.

[INTERNAL]	RNAL] Uses the internal focus test pattern of signal level approximately 100 % for focus adjustment.		
[EXTERNAL]	Select this item when using the input image from an external device for focus adjustment.		

# 17) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.

• The [SETUP ASSISTANT] screen (page 4/8) is displayed.

• It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 18) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.
- 19) Press **♦** to select [NEXT], and press the <ENTER> button.
  - The [SETUP ASSISTANT] screen (page 5/8) is displayed.
  - It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.
- 20) Press ▲▼◀▶ to select [FOCUS POSITION].
- 21) Press the ◀▶ button to adjust the focus.
- 22) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.
  The [SETUP ASSISTANT] screen (page 6/8) is displayed.
- 23) Press ▲▼◀▶ to select [TEST PATTERN].
- 24) Press **♦** to select [INTERNAL].
  - The items will switch each time you press the button.

[INTERNAL] Uses the internal focus test pattern of signal level approximately 0 % for focus adjustment	
[EXTERNAL]	Select this item when using the input image from an external device for focus adjustment.

# 25) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.

- The [SETUP ASSISTANT] screen (page 7/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 26) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.

# 27) Press **♦** to select [NEXT], and press the <ENTER> button.

- The [SETUP ASSISTANT] screen (page 8/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.
- 28) Press ▲▼◀▶ to select [FOCUS POSITION].
- 29) Press the ◀▶ button to adjust the focus.

# 30) Press ▲▼◀▶ to select [STORE], and press the <ENTER> button.

• [SETUP ASSISTANT] is completed, and the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are updated.

Note

- When the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are set by executing [SETUP ASSISTANT], the [PROJECTOR SETUP] menu → [LENS] → [ACTIVE FOCUS OPTIMIZER] → [ACTIVE FOCUS] will be set to [ON].
- When [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are set following the guidance of [SETUP ASSISTANT] with AC 100 V to AC 120 V, use the projector with AC 100 V to AC 120 V. When the power supply is changed to AC 200 V to AC 240 V, reset the settings using [SETUP ASSISTANT].

# Performing simplified setting using the external input image

Input any focus adjustment still image from the external device connected to the projector, and set the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] following the guidance of [SETUP ASSISTANT].

# 1) Switch to the input to display the focus adjustment image.

- 2) Press ▲▼ to select [LENS].
- 3) Press the <ENTER> button.
  - The [LENS] screen is displayed.

- 4) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- 5) Press the <ENTER> button.
   The [ACTIVE FOCUS OPTIMIZER] screen is displayed.
- 6) Press  $\blacktriangle$  to select [FOCUS OFFSET SETUP].
- 7) Press the <ENTER> button.
  - The [FOCUS OFFSET SETUP] screen is displayed.
- 8) Press ▲▼ to select [SETUP ASSISTANT].

# 9) Press the <ENTER> button.

- If the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to [100.0%], the internal focus test pattern of signal level approximately 50 % is projected, and the [SETUP ASSISTANT] screen (page 1/8) is displayed. Proceed to Step 11).
- If the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to less than [100.0%], the confirmation screen is displayed. Proceed to Step **10**).

# 10) Press **♦** to select [NEXT], and press the **<**ENTER> button.

- Even if the [PROJECTOR SETUP] menu → [LIGHT OUTPUT] is set to less than [100.0%], the projector will
  operate with the [100.0%] setting while [SETUP ASSISTANT] is executing. Once [SETUP ASSISTANT] is
  completed, it will return to the original [LIGHT OUTPUT] setting value.
- After confirming the confirmation message, press ◀▶ to select [NEXT], and press the <ENTER> button. The internal focus test pattern of signal level approximately 50 % is projected, and the [SETUP ASSISTANT] screen (page 1/8) is displayed.
- To cancel the setting by [SETUP ASSISTANT], press **↓** to select [CANCEL], and press the <ENTER> button. [SETUP ASSISTANT] is cancelled, and the **[FOCUS OFFSET SETUP]** screen is displayed.

# 11) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.

# 12) Press **I** to select [NEXT], and press the **<**ENTER**>** button.

- The [SETUP ASSISTANT] screen (page 2/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.
- 13) Press ▲▼◀▶ to select [FOCUS POSITION].
- 14) Press the ◀▶ button to adjust the focus.

# 15) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.

• The [SETUP ASSISTANT] screen (page 3/8) is displayed.

# 16) Press ▲▼◀▶ to select [TEST PATTERN].

# 17) Press **♦** to select [EXTERNAL].

• The items will switch each time you press the button.

[INTERNAL]	Select this item when using the internal test pattern for focus adjustment.			
	Uses the input image from the external device for focus adjustment. If the level of [Brightness of the image] falls below the specified value, [NEXT] cannot be selected. When the bright image with a brightness level indicated in the menu screen (OSD) or greater is input, [NEXT] can be selected.			

# 18) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.

- The [SETUP ASSISTANT] screen (page 4/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 19) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.

# 20) Press **I** to select [NEXT], and press the **<**ENTER**>** button.

- The [SETUP ASSISTANT] screen (page 5/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 21) Press ▲▼◀▶ to select [FOCUS POSITION].

# 22) Press the **I** button to adjust the focus.

- 23) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.
  - The [SETUP ASSISTANT] screen (page 6/8) is displayed.

# 24) Press ▲▼◀▶ to select [TEST PATTERN].

# 25) Press ◀▶ to select [EXTERNAL].

• The items will switch each time you press the button.

[INTERNAL]	Select this item when using the internal test pattern for focus adjustment.			
[EXTERNAL]	Uses the input image from the external device for focus adjustment. If the level of [Brightness of the image] exceeds the specified value, [NEXT] cannot be selected. When the dark image with a brightness level indicated in the menu screen (OSD) or lower is input, [NEXT] can be selected.			

# 26) Press ▲▼◀▶ to select [NEXT], and press the <ENTER> button.

- The [SETUP ASSISTANT] screen (page 7/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 27) Wait until [Waiting time] turns [0s].

- Wait until the focus is stabilized.
- When the [Waiting time] turns [0s], the [Please wait...] message disappears, and [NEXT] becomes selectable.

# 28) Press **♦** to select [NEXT], and press the **<**ENTER**>** button.

- The [SETUP ASSISTANT] screen (page 8/8) is displayed.
- It will return to previous screen by selecting [BACK] and pressing the <ENTER> button.

# 29) Press ▲▼◀▶ to select [FOCUS POSITION].

30) Press the **♦** button to adjust the focus.

# 31) Press ▲▼◀▶ to select [STORE], and press the <ENTER> button.

 [SETUP ASSISTANT] is completed, and the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are updated.

### Note

- When the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are set by executing [SETUP ASSISTANT], the [PROJECTOR SETUP] menu → [LENS] → [ACTIVE FOCUS OPTIMIZER] → [ACTIVE FOCUS] will be set to [ON].
- When [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] are set following the guidance of [SETUP ASSISTANT] with AC 100 V to AC 120 V, use the projector with AC 100 V to AC 120 V. When the power supply is changed to AC 200 V to AC 240 V, reset the settings using [SETUP ASSISTANT].

# Directly setting the parameter

When using the projection lens where the optimal parameter at the time when combined with the projector is already known, [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] parameters can be individually set without executing [SETUP ASSISTANT].

# 1) Press $\blacktriangle \forall$ to select [LENS].

# 2) Press the <ENTER> button.

- The [LENS] screen is displayed.
- 3) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- Press the <ENTER> button.
  - The [ACTIVE FOCUS OPTIMIZER] screen is displayed.
- 5) Press ▲▼ to select [FOCUS OFFSET SETUP].

- 6) Press the <ENTER> button.
  - The [FOCUS OFFSET SETUP] screen is displayed.
- 7) Press ▲▼ to select [FOCUS OFFSET BRIGHT] or [FOCUS OFFSET DARK].
- 8) Press **I** to set the parameter.

# Displaying the test pattern

The internal focus test pattern used with [SETUP ASSISTANT] is displayed.

# 1) Press ▲▼ to select [LENS].

# 2) Press the <ENTER> button.

- The [LENS] screen is displayed.
- 3) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- 4) Press the <ENTER> button.
  - The [ACTIVE FOCUS OPTIMIZER] screen is displayed.
- 5) Press ▲▼ to select [FOCUS OFFSET SETUP].
- 6) Press the <ENTER> button.
  - The [FOCUS OFFSET SETUP] screen is displayed.
- 7) Press ▲▼ to select [TEST PATTERN].

### 8) Press **♦** to select an item.

• The items will switch each time you press the button.

[OFF]	Does not display the test pattern.			
[0%]	splays the focus test pattern of signal level approximately 0 %.			
[50%]	Displays the focus test pattern of signal level approximately 50 %.			
[100%]	Displays the focus test pattern of signal level approximately 100 %.			

### Initializing the parameter

Return all the parameters for [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] saved by each setting in the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS TYPE] to factory default settings.

- 1) Press ▲▼ to select [LENS].
- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.
- 3) Press ▲▼ to select [ACTIVE FOCUS OPTIMIZER].
- 4) Press the <ENTER> button.
  - The [ACTIVE FOCUS OPTIMIZER] screen is displayed.
- 5) Press ▲▼ to select [FOCUS OFFSET SETUP].
- 6) Press the <ENTER> button.
   The [FOCUS OFFSET SETUP] screen is displayed.
- 7) Press ▲▼ to select [INITIALIZE], and press the <ENTER> button.

• The confirmation screen is displayed.

8) Press **♦** to select [OK], and press the <ENTER> button.

# [LENS CALIBRATION]

Detect the lens adjustment limit value, and perform the calibration in the adjustment range. Execute the lens calibration after attaching the projection lens.

## Zoom Lens with DC motor, the Fixed-focus Lens

This section describes the operating procedure when the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) in which the DC motor has not been replaced with the stepping motor unit is attached, or when the Fixed-focus Lens (Model No.: ET-D75LE50, ET-D75LE95, ET-D75LE90, etc.) without the zoom function is attached. Refer to "Zoom Lens with the stepping motor" (→ page 160) when a projection lens with stepping motor is attached.

## 1) Press ▲▼ to select [LENS].

## 2) Press the <ENTER> button.

• The [LENS] screen is displayed.

# 3) Press ▲▼ to select [LENS CALIBRATION].

## 4) Press the <ENTER> button.

• The confirmation screen is displayed.

# 5) Press **♦** to select [OK], and press the **<**ENTER> button.

- The lens calibration is started. Perform the calibrations for the lens shift, focus, and zoom when the Zoom Lens is attached. Perform the calibrations for the lens shift and focus when the Fixed-focus Lens is attached.
- After completing the calibration in the adjustment range, the projection lens will move to the home position.
- To cancel, select [CANCEL].

### Note

- [LENS CALIBRATION] cannot be executed when the [PROJECTOR SETUP] menu → [LENS] → [LENS TYPE] is set to [NOT SELECTED].
- [PROGRESS] is displayed in the menu during lens calibration. The operation cannot be canceled during calibration.
- [INCOMPLETE] is displayed when the lens calibration is not performed correctly.
- The origin position of the lens mounter and the home position of the projection lens are automatically updated when the lens shift calibration is performed. The home position is a origin position of the lens shift (vertical position and horizontal position of the lens) based on the calibration result. It does not match with the optical image center position.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).

### Zoom Lens with the stepping motor

This section describes the operating procedure when the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

# 1) Press ▲▼ to select [LENS].

- 2) Press the <ENTER> button.
  - The [LENS] screen is displayed.

### 3) Press $\blacktriangle \lor$ to select [LENS CALIBRATION].

# 4) Press the <ENTER> button.

• The [LENS CALIBRATION] screen is displayed.

### 5) Press $\blacktriangle \lor$ to select an item.

[SHIFT/FOCUS/ZOOM]	Executes the calibrations for the lens shift, focus, and zoom. After completing the calibration in the adjustment range, the projection lens will move to the home position.
[SHIFT/FOCUS]	Executes the calibrations for the lens shift and focus. After completing the calibration in the adjustment range, the projection lens will move to the home position.
[ZOOM]	Executes the calibration of the zoom adjustment range.

### 6) Press the <ENTER> button.

• The confirmation screen is displayed.

# 7) Press ◀▶ to select [OK], and press the <ENTER> button.

• The lens calibration is started.

## • To cancel, select [CANCEL].

## Note

- [LENS CALIBRATION] cannot be executed when the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS TYPE] is set to [NOT SELECTED].
- [PROGRESS] is displayed in the menu during lens calibration. The operation cannot be canceled during calibration.
- [INCOMPLETE] is displayed when the lens calibration is not performed correctly.
- The origin position of the lens mounter and the home position of the projection lens are automatically updated when the lens shift calibration is performed. The home position is a origin position of the lens shift (vertical position and horizontal position of the lens) based on the calibration result. It does not match with the optical image center position.
- The home position varies depending on the projection lens type. For details, refer to "Lens shift range" (> page 80).

# [OPERATION SETTING]

Set the operation method of the projector.

The settings are reflected when "Initial setting (operation setting)" (→ page 66) in the **[INITIAL SETTING]** screen is already set.

If you change the settings while using the projector, the duration until the luminance of the light source decreases by half may shorten or the luminance may decrease.

# Setting [OPERATING MODE]

# 1) Press ▲▼ to select [OPERATION SETTING].

2) Press the <ENTER> button.
• The [OPERATION SETTING] screen is displayed.

# 3) Press ▲▼ to select [OPERATING MODE].

## 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[HIGH]*1	The life of the light source will shorten compared to [NORMAL], but set this item when a higher luminance than [NORMAL] is required. The estimated runtime is approximately 8 000 hours.				
[NORMAL] <sup>-1</sup>	Set this item when high luminance is required. The estimated runtime is approximately 20 000 hours. (Factory default setting)				
[LONG LIFE1] <sup>∗1</sup>	The luminance will decrease compared to [NORMAL], but set this item to increase the expected life of the light source. The estimated runtime is approximately 43 000 hours.				
[LONG LIFE2] <sup>*1</sup>	The luminance will decrease compared to [LONG LIFE1], but set this item to increase the expected life of the light source. The estimated runtime is approximately 61 000 hours.				
[LONG LIFE3] <sup>-1</sup>	The luminance will decrease compared to [LONG LIFE2], but set this item to increase the expected life of the light source. The estimated runtime is approximately 87 000 hours.				
[USER1]					
[USER2]	Set [MAX LIGHT OUTPUT LEVEL] and [LIGHT OUTPUT] individually.				
[USER3]					

\*1 The runtime is an estimation when the [PICTURE] menu  $\rightarrow$  [DYNAMIC CONTRAST] is set to [3].

# 5) Press $\blacktriangle \forall$ to select [APPLY].

6) Press the <ENTER> button.

# 7) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.

### Note

- The [OPERATING MODE] setting does not return to factory default setting even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.
- Set [OPERATING MODE] to anything other than [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when using the projector at an altitude of 2 700 m (8 858') or higher above sea level.
- [OPERATING MODE] cannot be set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when the [PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER TYPE] is set to [SMOKE CUT]. Set [OPERATING MODE] to [HIGH], [NORMAL], [USER1], [USER2], or [USER3] when using the optional Smoke Cut Filter (Model No.: ET-SFR330).
- The estimated runtime is the time until when the luminance decreases approximately by half, except when [OPERATING MODE] is set to [HIGH].
- If the consolidated runtime of the projector exceeds 20 000 hours, replacement of the components inside the projector may be required. The consolidated runtime can be confirmed in the **[STATUS]** screen. Refer to the [PROJECTOR SETUP] menu → [STATUS] for details.

# Setting [MAX LIGHT OUTPUT LEVEL]

Adjust the maximum level to correct screen brightness according to the changes in brightness of the light source.

- 1) Press ▲▼ to select [OPERATION SETTING].
- 2) Press the <ENTER> button.

• The [OPERATION SETTING] screen is displayed.

- 3) Press ▲▼ to select [MAX LIGHT OUTPUT LEVEL].
- 4) Press **♦** to adjust.

Operation Adjustment		Range of adjustment	
Press .	Press ▶. Increases the maximum level of brightness correction.		
Press ◀.	Decreases the maximum level of brightness correction.	8.0 % - 100.0 %	

## 5) Press ▲▼ to select [APPLY].

6) Press the <ENTER> button.

# 7) When the confirmation screen is displayed, press **(**) to select [OK], and press the **<ENTER>** button.

### Note

• When [OPERATING MODE] is set to [NORMAL], [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the item of [MAX LIGHT OUTPUT LEVEL] cannot be adjusted.

- The brightness is corrected using this setting when the [PROJECTOR SETUP] menu → [BRIGHTNESS CONTROL] → [BRIGHTNESS CONTROL
- The [MAX LIGHT OUTPUT LEVEL] setting does not return to factory default setting even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

# Setting [LIGHT OUTPUT]

Adjust the brightness of light source.

The [LIGHT OUTPUT] setting is synchronized with the [PROJECTOR SETUP] menu  $\rightarrow$  [LIGHT OUTPUT]. The most recent setting is reflected in both items.

# 1) Press ▲▼ to select [OPERATION SETTING].

# 2) Press the <ENTER> button.

- The [OPERATION SETTING] screen is displayed.
- 3) Press ▲▼ to select [LIGHT OUTPUT].
- 4) Press **♦** to adjust.

Orecretica	Adjus	Denne of edimetricent	
Operation	Brightness	Runtime	Range of adjustment
Press .	The screen becomes brighter.	The runtime becomes shorter.	8.0 % - 100.0 %*1
Press 4.	The screen becomes darker.	The runtime becomes longer.	0.0 % - 100.0 % 1

\*1 The upper limit of the adjustment range is the value of [MAX LIGHT OUTPUT LEVEL].

### 5) Press ▲▼ to select [APPLY].

- 6) Press the <ENTER> button.
- 7) When the confirmation screen is displayed, press ◀▶ to select [OK], and press the <ENTER> button.

### Note

<sup>• [</sup>LIGHT OUTPUT] can be adjusted individually for each setting item of [OPERATING MODE].

The uniformity of the brightness between multiple displays can be maintained by adjusting [LIGHT OUTPUT] for each projector when structuring a multi-display screen by combining the projected images from multiple projectors.

# Interrelation of luminance and runtime

The projector can be operated at arbitrary brightness and duration of use by combining the settings of [MAX LIGHT OUTPUT LEVEL], [LIGHT OUTPUT], and [CONSTANT MODE] in [BRIGHTNESS CONTROL SETUP]. Interrelation of luminance and runtime is as follows. Make the settings depending on your desired duration of use and brightness of the projected image.

Values of the luminance and runtime are rough estimations.

# To set the projector based on the duration of use

	When [CONSTANT MODE] is set to [OFF]			When [CONSTANT MODE] is set to [AUTO] or [PC]		
Duration of use (hour)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT]*1 (%)	Luminance (Im)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT] (%)	Luminance (Im)
5 000	100.0	100.0	26 000	83.3	67.7	17 500
10 000	100.0	100.0	26 000	83.3	59.4	15 400
20 000	83.3	83.3	21 600	83.3	46.7	12 100
24 000	83.3	53.6	13 900	83.3	42.7	11 100
48 000	83.3		_	83.3	26.2	6 800
63 000	83.3	_	_	83.3	19.8	5 100
87 000	83.3	—	—	83.3	13.0	3 300

\*1 The upper limit of the adjustment range is the value described in the [MAX LIGHT OUTPUT LEVEL] column in the table.

# To set the projector based on luminance

	When [CONSTANT MODE] is set to [OFF]			When [CONSTANT MODE] is set to [AUTO] or [PC]		
Luminance (Im)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT]*1 (%)	Runtime (hour)	[MAX LIGHT OUTPUT LEVEL] (%)	[LIGHT OUTPUT] (%)	Runtime (hour)
26 000	100.0	100.0	18 000	—	—	—
21 000	83.3	80.8	20 000	—	—	—
17 000	83.3	65.4	22 100	83.3	65.4	6 300
13 000	83.3	50.0	24 500	83.3	50.0	17 000
9 000	83.3	—	—	83.3	34.6	33 900
7 000	83.3	_	_	83.3	26.9	46 500
4 000	83.3	_	_	83.3	15.4	77 100

\*1 The upper limit of the adjustment range is the value described in the [MAX LIGHT OUTPUT LEVEL] column in the table.

#### Note

- Under influence of characteristics of each light source, conditions of use, installation environment, etc., the runtime may be shorter than the estimation.
- The duration of use is referred to as the runtime when you use the projector successively. The duration of use is an estimated duration and is not the warranty period.
- If the consolidated runtime of the projector exceeds 20 000 hours, replacement of the components inside the projector may be required. The consolidated runtime can be confirmed in the [STATUS] screen. Refer to the [PROJECTOR SETUP] menu → [STATUS] for details.

# [LIGHT OUTPUT]

Adjust the brightness of light source.

The setting is reflected when it is already set with "Initial setting (operation setting)" ( $\Rightarrow$  page 66) in the **[INITIAL SETTING]** screen or with the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]. The [LIGHT OUTPUT] setting is synchronized with the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [LIGHT OUTPUT]. The most recent setting is reflected in both items.

# 1) Press ▲▼ to select [LIGHT OUTPUT].

# 2) Press **♦** to adjust.

Onenetien	Adjus	Denne of a diverse	
Operation	Brightness	Runtime	Range of adjustment
Press ▶.	The screen becomes brighter.	The runtime becomes shorter.	8.0 % - 100.0 %*1
Press ◀.	The screen becomes darker.	The runtime becomes longer.	0.0 % - 100.0 % 1

\*1 The upper limit of the adjustment range is the value set in the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [MAX LIGHT OUTPUT LEVEL].

- [LIGHT OUTPUT] can be adjusted individually for each setting item of [OPERATING MODE].
- The uniformity of the brightness between multiple displays can be maintained by adjusting [LIGHT OUTPUT] for each projector when structuring a multi-display screen by combining the projected images from multiple projectors.
- When the Fixed-focus Lens (Model No.: ET-D75LE90) is used, set [LIGHT OUTPUT] to 77.0 % or less considering the focus quality. The luminance when [LIGHT OUTPUT] is set to 77.0 % is 20 000 lm (approximate).

# [BRIGHTNESS CONTROL]

The projector is equipped with a brightness sensor to measure brightness and color of the light source, and corrects brightness and white balance of the projected image according to the changes in brightness and color of the light source.

By using this function while structuring the multi-display by combining the projected images from multiple projectors, the change in the brightness and white balance for the whole multi-display can be reduced or hold down the difference of the brightness and white balance to maintain uniformity, caused by the aging of the light source.

# Setting [BRIGHTNESS CONTROL SETUP]

Set the operation of the brightness control function.

# 1) Press ▲▼ to select [BRIGHTNESS CONTROL].

- 2) Press the <ENTER> button.
  - The [BRIGHTNESS CONTROL] screen is displayed.

# 3) Press ▲▼ to select [BRIGHTNESS CONTROL SETUP].

4) Press the <ENTER> button.

• The [BRIGHTNESS CONTROL SETUP] screen is displayed.

# 5) Press ▲▼ to select [CONSTANT MODE].

# 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Does not correct the brightness of the screen by the brightness sensor.
[AUTO]	Corrects the brightness of the screen by the brightness sensor. When the brightness of light source or white balance changes, the brightness of the projected image is automatically corrected.
[PC]	Synchronizes nine or more projectors using a computer and the dedicated software "Multi Monitoring & Control Software" <sup>1</sup> .

\*1 "Multi Monitoring & Control Software" is included in the supplied CD-ROM.

• When [PC] is selected, proceed to Step 9).

# 7) Press ▲▼ to select [LINK].

# 8) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Performs corrections by the brightness sensor on a single projector without synchronizing with the other projectors. The duration that the constant brightness is kept will become longer by setting the value of [LIGHT OUTPUT] smaller.
[GROUP A] [GROUP B] [GROUP C] [GROUP D]	Performs correction by the brightness sensor in multiple projectors in synchronization. Up to four groups (A to D) can be set within the same subnet by using the network function. You can register and synchronize up to eight projectors in one group.

# 9) Press ▲▼ to select [CALIBRATION TIME].

# 10) Press the <ENTER> button.

• The projector is in the adjustment mode (the time is blinking).

- 11) Press **♦** to select "hour" or "minute", and press **▲**▼ or the number (<0> <9>) buttons to set a time.
  - Selecting "hour" allows setting of only the hour in increments of one hour, and selecting "minute" allows setting of only the minute in increments of one minute between 00 and 59.
  - When the time is not specified, select [OFF] between 23 and 00 of the hour, or between 59 and 00 of the minute.
- 12) Press the <ENTER> button.
  - [CALIBRATION TIME] is set.
  - Brightness and color are measured at the specified time. The dynamic contrast function does not operate during measurement.

# 13) Press ▲▼ to select [CALIBRATION MESSAGE].

# 14) Press **♦** to switch the item.

• The items will switch each time you press the button.

[ON]	Displays messages during calibration.
[OFF]	Does not display messages during calibration.

# 15) Press $\blacktriangle \blacksquare$ to select [APPLY].

# 16) Press the <ENTER> button.

- When [CONSTANT MODE] in [BRIGHTNESS CONTROL SETUP] is set to anything other than [OFF], the brightness and white balance of light source at the time when the <ENTER> button is pressed is recorded as the standard brightness and white balance.
- If the <ENTER> button is pressed when [LINK] is set from [GROUP A] to [GROUP D], the group name is displayed on the screens of projectors that have been set in the same group.



### Note

- When [CONSTANT MODE] is set to [AUTO] or [PC], keep the shutter function disabled (shutter: open) for at least two minutes, since the brightness sensor calibration is performed after the [BRIGHTNESS CONTROL SETUP] setting has been completed.
- If the shutter function is enabled (shutter: closed) within approximately 10 minutes after the light source has been turned on while the
  projector operates with [CONSTANT MODE] set to [AUTO] or [PC], brightness and color cannot be measured. Therefore, brightness may be
  corrected approximately two minutes after the shutter function is disabled (shutter: open).
- When the projector operates with [CONSTANT MODE] set to [AUTO] or [PC], the brightness and color of the light source do not stabilize for approximately eight minutes after the light source is turned on. Therefore, the brightness and color of the light source will be automatically measured after approximately eight minutes have elapsed after the light source is turned on.
- When the projector operates with [CONSTANT MODE] set to [AUTO], and [LINK] set to [OFF], the brightness will be corrected until it reaches the value set in [MAX LIGHT OUTPUT LEVEL].
- The variation in brightness may increase due to dust accumulating on the lens, screen, or inside the projector, depending on the installation environment of the projector.
- When the variation in brightness has increased due to aging of the light source, or when you replaced the light source, readjust the brightness control.
- When the projector is used continuously for more than 24 hours, set the [CALIBRATION TIME] in [BRIGHTNESS CONTROL SETUP]. If it is not set, correction will not be performed automatically.
- The brightness control function and the dynamic contrast function will operate simultaneously, but the dynamic contrast function will not operate while measuring the brightness and the color.
- The [CALIBRATION TIME] setting will be reflected when you enter the time.
- The [CALIBRATION MESSAGE] setting will be reflected at the time when the item is switched using **4**.

# Displaying [BRIGHTNESS CONTROL STATUS]

Display the brightness control status.

- 1) Press ▲▼ to select [BRIGHTNESS CONTROL].
- 2) Press the <ENTER> button.
  - The [BRIGHTNESS CONTROL] screen is displayed.
- 3) Press ▲▼ to select [BRIGHTNESS CONTROL STATUS].
- 4) Press the <ENTER> button.
  - The [BRIGHTNESS CONTROL STATUS] screen is displayed.

# [BRIGHTNESS CONTROL STATUS] screen display example

# When [CONSTANT MODE] is set to [OFF]

The screen shows the status that the brightness control is disabled.

BRIGHTNESS CONTROL STA	TUS	]
CONSTANT MODE	OFF	
PROJECTOR		
		ť
		L

## When [CONSTANT MODE] is set to [AUTO], and [LINK] is set to [OFF]

The screen shows the status of the brightness control in one projector.

BRIGHTNESS CONTROL	STATUS	
LINK	OFF	_5
PROJECTOR -		-1
		-6
(MENU) RETURN		

# When [CONSTANT MODE] is set to [AUTO], and [LINK] is set to [GROUP A] through [GROUP D]

The screen shows the status of the brightness control of synchronized projectors (up to eight units), including the projector being controlled through the on-screen menu.

BRIGHTNESS CONTROL STATUS	
LINK GROUP A	
PROJECTOR 192. 168. 30. 2	
1: PROJECTOR2 192. 168. 30. 3	
2: PROJECTOR3 192. 168. 30. 4	
3:	
4:	
5:	
6:	
7:	<u>i</u>
UPDATE	- e
MENU SELECT	

### When [CONSTANT MODE] is set to [PC]

BRIGHTNESS CONTROL STA	TUS	
CONSTANT MODE	PC	
PROJECTOR		
		6

1 Display the name of the projector.

2 Display the synchronized group.

- 3 Display the IP address of the projector.
- 4 Display the names and IP addresses of projectors in same group detected over the network.

#### 5 Display the status by color.

Green: There is an allowance for brightness correction. Yellow: There is little allowance for brightness correction. Red: There is a brightness control error.

#### 6 Display error detailed messages.

#### 7 Display error messages.

When the message [Failed to apply BRIGHTNESS CONTROL to some projectors.] appears, it means that synchronization with the projector displayed in red has failed.

Press ▲▼ to select the projector displayed in red, and press the <ENTER> button to display the error details.

8 Update to the latest status information.

# Error details

Error message	Measures to take
[Exceed maximum number of projectors.]	<ul> <li>Limit the number of projectors in one group to eight.</li> <li>To synchronize nine or more projectors, use a PC and the dedicated software "Multi Monitoring &amp; Control Software"<sup>*1</sup>.</li> </ul>
[Please check the COMMAND CONTROL setting.]	<ul> <li>Set [NETWORK CONTROL] → [COMMAND CONTROL] to [ON] for the projector in error.</li> <li>Set [NETWORK CONTROL] → [COMMAND PORT] of all linked projectors to the same value.</li> </ul>
[Please check the USER NAME and PASSWORD in the COMMAND CONTROL setting.]	<ul> <li>Assign same character strings for [User name] and [Password] as the web control administrator rights to all linked projectors.</li> </ul>
[Cannot apply BRIGHTNESS CONTROL. Please check projector status.]	The projector is in standby. Switch on the power.
[Brightness Sensor Error]	• There is a problem with the brightness sensor. If problems persist even after switching on the power, consult your dealer.

\*1 "Multi Monitoring & Control Software" is included in the supplied CD-ROM.

#### Note

• If the synchronized projectors are not displayed in the list, check the following:

- Are there devices with the same IP address on the network?
- Are the LAN cables connected correctly? (
   page 201)
- Are the subnets of the projectors the same?
- Are the same [LINK] settings applied to a group?

• Refer to [NETWORK SETUP] (+ page 196) or "[Network config] page" (+ page 211) on how to change the projector name.

### Brightness control adjustment procedure example

The steps exemplify an adjustment to link the brightness of eight projectors connected in a network.

- 1) Connect all projectors to the hub using LAN cables. (⇒ page 201)
- 2) Switch on all projectors and start projection.
- Set [CONSTANT MODE] of [BRIGHTNESS CONTROL SETUP] to [OFF], and select [APPLY], and then press the <ENTER> button.
- 4) Set [OPERATING MODE] of each projector to the same setting. (⇒ page 161)

# 5) Set [SUBNET MASK] and [IP ADDRESS] in each projector.

- To be able to communicate over the network, set the same value in [SUBNET MASK] for all projectors and set a different value in [IP ADDRESS] for each projector.
- 6) Wait for at least eight minutes after projection has started until the light source brightness becomes steady.
- 7) Set all items in the [PICTURE] menu of all projectors to the same values.
- 8) Adjust [COLOR MATCHING] to match colors.
- 9) Display the internal test pattern "All white" in all projectors.
- 10) Set [LIGHT OUTPUT] of all projectors to 100 % or the maximum value that can be set.
  Depending on the [OPERATING MODE] settings, [LIGHT OUTPUT] may not be able to be set to 100 %.
- 11) Set [LIGHT OUTPUT] of the projector with the least brightness to 90 % or 10 % lower than the maximum value that can be set.

# 12) Adjust [LIGHT OUTPUT] of each projector.

- Adjust [LIGHT OUTPUT] of all the other projectors so that the brightness will be the same as the projector with the least brightness.
- 13) Set [CONSTANT MODE] of [BRIGHTNESS CONTROL SETUP] to [AUTO], and [LINK] to [GROUP A] in all projectors.
- 14) Select [APPLY] of [BRIGHTNESS CONTROL SETUP] and press the <ENTER> button in all projectors.
  - Brightness control starts.

### Note

- · Brightness is automatically corrected whenever the light source lights up by switching on/off the projector, etc.
- When the variation in brightness has increased due to aging of the light source, or when you replaced the light source, readjust the brightness control.

# [STANDBY MODE]

Set the power consumption during the standby.

### 1) Press ▲▼ to select [STANDBY MODE].

- 2) Press  $\triangleleft$  to switch the item.
  - The items will switch each time you press the button.

[NORMAL]	Select this item to use the network function during standby.
[ECO]	Select this item to reduce power consumption during standby.

#### Note

- The AC voltage monitor function, the network function, the <SERIAL OUT> terminal, and part of the RS-232C command cannot be used during the standby when set to [ECO].
- When an error or warning occurs on the projector, the self-diagnosis display appears on the control panel regardless of the [STANDBY MODE] settings. (
  page 235)
- When [ECO] is set, it may take approximately 10 seconds longer before the projector starts projecting after the power is turned on, compared with when [NORMAL] is set.
- When [NORMAL] is set, the network function and the <SERIAL OUT> terminal can be used during standby.
- When [NORMAL] is set, power can be supplied by using the <DC OUT 1> terminal or the <DC OUT 2> terminal even while the projector is in standby mode. If [ECO] is set, power cannot be supplied in standby mode.
- The [STANDBY MODE] setting does not return to factory default setting even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

# [NO SIGNAL SHUT-OFF]

A function that automatically switches the power source of the projector to standby if there is no input signal for a certain period of time. The time before switching to standby can be set.

# 1) Press ▲▼ to select [NO SIGNAL SHUT-OFF].

### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[DISABLE]	Disables the No signal shut-off function.
[10MIN.] - [90MIN.]	Sets the time in increments of 10 minutes.

# [NO SIGNAL LIGHTS-OUT]

This is a function to automatically turn off the light source of the projector when there is no input signal for specific period. The time until the light source is turned off can be set.

# 1) Press ▲▼ to select [NO SIGNAL LIGHTS-OUT].

### 2) Press $\triangleleft$ to switch the item.

The items will switch each time you press the button.

[DISABLE]	Disables the no signal lights-out function.
[10SEC 1 - [5MIN 1	Turns off the light source when there is no input signal for the preset period. Select [10SEC.], [20SEC.], [30SEC.], [1MIN.], [2MIN.], [3MIN.], or [5MIN.].

- The power indicator <ON (G)/STANDBY (R)> will blink slowly in green while the no signal lights-out function is operating and the light source is turned off.
- When [NO SIGNAL LIGHTS-OUT] is set to anything other than [DISABLE], the following are the conditions to turn the light source back on again from the condition that the light source has turned off by this function.
  - When the signal is input
  - When on-screen display such as menu screen (OSD) or input guide, a test pattern, or a warning message is displayed
  - When the power on <|> button is pressed
  - When the operation to disable the shutter function (shutter: open) is performed, such as pressing the <SHUTTER> button
- When the operating environment temperature is around 0 °C (32 °F) and the light source is forced to turn on due to warm-up
- The no signal lights-out function is disabled when the [DISPLAY OPTION] menu → [BACK COLOR] is set to either [DEFAULT LOGO] or [USER LOGO] and the Panasonic logo or the image registered by the user is displayed on the projected image.

# [INITIAL STARTUP]

Set the startup method when the <MAIN POWER> switch is set to <ON>.

- 1) Press ▲▼ to select [INITIAL STARTUP].
- 2) Press **I** to switch the item.
  - The items will switch each time you press the button.

[LAST MEMORY]	Starts up the projector in the condition before the <main power=""> switch is set to <off>.</off></main>	
[STANDBY]	Starts up the projector in standby.	
[ON]	Starts projecting immediately.	

# [STARTUP INPUT SELECT]

Set the input when the projector is switched on to start projection.

- 1) Press ▲▼ to select [STARTUP INPUT SELECT].
- 2) Press the <ENTER> button.
  - The [STARTUP INPUT SELECT] screen is displayed.
- 3) Press ▲▼◀▶ to select the input, and press the <ENTER> button.

[LAST USED]	Keeps the input selected last.
[SDI1]	Sets the input to SDI1.
[SDI2]	Sets the input to SDI2.
[SDI3]	Sets the input to SDI3.
[SDI4]	Sets the input to SDI4.
[DIGITAL LINK]	Sets the input to DIGITAL LINK.
[HDMI1 [SLOT1]]*1	Sets the input to HDMI1 of the Interface Board.
[HDMI2 [SLOT1]]*1	Sets the input to HDMI2 of the Interface Board.
[HDMI3 [SLOT2]]*2	Sets the input to HDMI3 of the Interface Board.
[HDMI4 [SLOT2]]*2	Sets the input to HDMI4 of the Interface Board.
[DVI-D1 [SLOT1]]*1	Sets the input to DVI-D1 of the Interface Board.
[DVI-D2 [SLOT1]]*1	Sets the input to DVI-D2 of the Interface Board.
[DVI-D3 [SLOT2]]*2	Sets the input to DVI-D3 of the Interface Board.
[DVI-D4 [SLOT2]]*2	Sets the input to DVI-D4 of the Interface Board.
[DisplayPort1 [SLOT1]]*1	Sets the input to DisplayPort1 of the Interface Board.
[DisplayPort2 [SLOT1]]*1	Sets the input to DisplayPort2 of the Interface Board.
[DisplayPort3 [SLOT2]]*2	Sets the input to DisplayPort3 of the Interface Board.
[DisplayPort4 [SLOT2]]*2	Sets the input to DisplayPort4 of the Interface Board.
[SDI1 [SLOT1]]*1	Sets the input to SDI1 of the Interface Board.
[SDI2 [SLOT1]]*1	Sets the input to SDI2 of the Interface Board.
[SDI3 [SLOT1]]*3	Sets the input to SDI3 of the Interface Board.
[SDI4 [SLOT1]]*3	Sets the input to SDI4 of the Interface Board.
[SDI1 [SLOT2]]*3	Sets the input to SDI1 of the Interface Board.
[SDI2 [SLOT2]]*3	Sets the input to SDI2 of the Interface Board.
[SDI3 [SLOT2]]*2	Sets the input to SDI3 of the Interface Board.
[SDI4 [SLOT2]]*2	Sets the input to SDI4 of the Interface Board.

**[INPUT1] - [INPUT10]**<sup>-4</sup> Sets the input to DIGITAL LINK, and switches the input of the Panasonic twisted-pair-cable transmitter to the specified input.

- \*1 This can be set when the optional Interface Board equipped with corresponding input is installed in <SLOT 1>.
- \*2 This can be set when the optional Interface Board equipped with corresponding input is installed in <SLOT 2>.
- \*3 This is displayed when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1> or <SLOT 2>.
- \*4 When the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the projector, its input name is automatically reflected from [INPUT1] to [INPUT10]. When an item that does not reflect the input name is selected, it will be disabled.

# [DATE AND TIME]

Set the time zone, date, and time of the built-in clock of the projector.

# Setting the time zone

- 1) Press ▲▼ to select [DATE AND TIME].
- 2) Press the <ENTER> button.
  - The [DATE AND TIME] screen is displayed.
- 3) Press ▲▼ to select [TIME ZONE].
- 4) Press **♦** to switch [TIME ZONE].

# Setting the date and time manually

- 1) Press ▲▼ to select [DATE AND TIME].
- 2) Press the <ENTER> button.
   The [DATE AND TIME] screen is displayed.
- 3) Press ▲▼ to select [ADJUST CLOCK].
- 4) Press the <ENTER> button.
   The [ADJUST CLOCK] screen is displayed.
- 5) Press ▲▼ to select an item, and press ◀▶ to set the local date and time.
- 6) Press ▲▼ to select [APPLY], and press the <ENTER> button.
  - The setting of the date and time will be completed.

### Setting the date and time automatically

- 1) Press ▲▼ to select [DATE AND TIME].
- 2) Press the <ENTER> button.
   The [DATE AND TIME] screen is displayed.
- 3) Press ▲▼ to select [ADJUST CLOCK].
- 4) Press the <ENTER> button.
  - The [ADJUST CLOCK] screen is displayed.
- 5) Press ▲▼ to select [NTP SYNCHRONIZATION], and press ◀▶ to change the setting to [ON].
- 6) Press ▲▼ to select [APPLY], and press the <ENTER> button.
  - The setting of the date and time will be completed.

Note

- To set the date and time automatically, the projector must be connected to the network.
- If synchronization with the NTP server fails just after [NTP SYNCHRONIZATION] is set to [ON], [NTP SYNCHRONIZATION] will return to [OFF]. If [NTP SYNCHRONIZATION] is set to [ON] while the NTP server is not set, [NTP SYNCHRONIZATION] will return to [OFF].
- Access the projector via a web browser to set the NTP server. Refer to "[Adjust clock] page" (> page 212) for details.

The [TIME ZONE] setting is reset to the factory default when the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed. However, the date and time based on the local date and time setting (Coordinated Universal Time, UTC, Universal Time, Coordinated) will be maintained without being initialized.

• The replacement of the battery inside the projector is required when the time goes out of alignment right after correcting the time. Consult your dealer.

# [SCHEDULE]

Set the command execution schedule for each day of the week.

# Enabling/disabling the schedule function

## 1) Press ▲▼ to select [SCHEDULE].

### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the schedule function.
IUNI	Enables the schedule function. Refer to "How to assign a program" (➡ page 171) or "How to set a program" (➡ page 171) for how to set the schedule.

#### Note

When [SCHEDULE] is set to [ON] while the [PROJECTOR SETUP] menu → [STANDBY MODE] is set to [ECO], the [STANDBY MODE] setting is forcibly switched to [NORMAL], and the setting cannot be changed to [ECO]. The [STANDBY MODE] setting will not return to original even if [SCHEDULE] is set to [OFF] in this condition.

## How to assign a program

- 1) Press ▲▼ to select [SCHEDULE].
- 2) Press ◀▶ to select [ON], and press the <ENTER> button.
   The [SCHEDULE] screen is displayed.
- 3) Select and assign a program to each day of week.
  - Press  $\blacktriangle \forall$  to select the day of week, and press  $\blacklozenge \flat$  to select a program number.
  - You can set the program from No.1 to No.7. "- -" indicates that the program number has not been set.

# How to set a program

Set up to 16 commands to each program.

- 1) Press ▲▼ to select [SCHEDULE].
- 2) Press ◀▶ to select [ON], and press the <ENTER> button.
   The [SCHEDULE] screen is displayed.
- 3) Press ▲▼ to select [PROGRAM EDIT].
- 4) Press **(**) to select a program number, and press the **<ENTER>** button.
- 5) Press ▲▼ to select a command number, and press the <ENTER> button.
   You can change the page using ◀▶.
- 6) Press ▲▼◀▶ to select [TIME], and press the <ENTER> button.
   The projector is in the adjustment mode (the time is blinking).
- 7) Press **♦** to select "hour" or "minute", and press **▲ ▼** or the number (<0> <9>) buttons to set a time, and then press the <ENTER> button.
- 8) Press  $\blacktriangle \lor \blacklozenge \lor$  to select [COMMAND].
- 9) Press the <ENTER> button.
  - The [COMMAND] detailed screen is displayed.
- 10) Press ▲▼ to select a [COMMAND].
  - For [COMMAND] which requires detailed settings, the items of the detailed settings will switch each time you press ◀▶.
  - When [INPUT] is selected, press the <ENTER> button, and then press ▲▼◀▶ to select the input to be set.

[COMMAND]	Detailed settings of [COMMAND]	Description
[POWER ON]	_	Switches on the projector.
[STANDBY]	_	Enters standby.
	[OPEN]	Disables the shutter function (shutter: open).
[SHUTTER]	[CLOSE]	Enables the shutter function (shutter: closed).
	[SDI1]	Switches the input to SDI1.
	[SDI2]	Switches the input to SDI2.
	[SDI3]	Switches the input to SDI3.
	[SDI4]	Switches the input to SDI4.
	[DIGITAL LINK]	Switches the input to DIGITAL LINK.
	[HDMI1 [SLOT1]]*1	Switches the input to HDMI1 of the Interface Board.
	[HDMI2 [SLOT1]]*1	Switches the input to HDMI2 of the Interface Board.
	[HDMI3 [SLOT2]]*2	Switches the input to HDMI3 of the Interface Board.
	[HDMI4 [SLOT2]]*2	Switches the input to HDMI4 of the Interface Board.
	[DVI-D1 [SLOT1]]*1	Switches the input to DVI-D1 of the Interface Board.
	[DVI-D2 [SLOT1]]*1	Switches the input to DVI-D2 of the Interface Board.
	[DVI-D3 [SLOT2]]*2	Switches the input to DVI-D3 of the Interface Board.
	[DVI-D4 [SLOT2]]*2	Switches the input to DVI-D4 of the Interface Board.
[INPUT]	[DisplayPort1 [SLOT1]]*1	Switches the input to DisplayPort1 of the Interface Board.
	[DisplayPort2 [SLOT1]]*1	Switches the input to DisplayPort2 of the Interface Board.
	[DisplayPort3 [SLOT2]]*2	Switches the input to DisplayPort3 of the Interface Board.
	[DisplayPort4 [SLOT2]]*2	Switches the input to DisplayPort4 of the Interface Board.
	[SDI1 [SLOT1]]*1	Switches the input to SDI1 of the Interface Board.
	[SDI2 [SLOT1]]*1	Switches the input to SDI2 of the Interface Board.
	[SDI3 [SLOT1]]*3	Switches the input to SDI3 of the Interface Board.
	[SDI4 [SLOT1]]*3	Switches the input to SDI4 of the Interface Board.
	[SDI1 [SLOT2]]*4	Switches the input to SDI1 of the Interface Board.
	[SDI2 [SLOT2]]*4	Switches the input to SDI2 of the Interface Board.
	[SDI3 [SLOT2]]*2	Switches the input to SDI3 of the Interface Board.
	[SDI4 [SLOT2]]*2	Switches the input to SDI4 of the Interface Board.
	[INPUT1] - [INPUT10]*5	Switches the input to DIGITAL LINK, and switches the input of the Panasonic twisted-pair-cable transmitter to the specified input.
	[HIGH]	The life of the light source shortens compared to [NORMAL], but the luminance increases more than [NORMAL].
	[NORMAL]	Prioritizes luminance. (Factory default setting)
	[LONG LIFE1]	Controls the power to increase the life of the light source although the luminance is lower than that of [NORMAL].
[OPERATING MODE]*6	[LONG LIFE2]	Controls the power to increase the life of the light source although the luminance is even lower than that of [LONG LIFE1].
	[LONG LIFE3]	Controls the power to increase the life of the light source to the maximum although the luminance is even lower than that of [LONG LIFE2].
	[USER1]	Controls the power with the setting set to [USER1].
	[USER2]	Controls the power with the setting set to [USER2].
	[USER3]	Controls the power with the setting set to [USER3].
	[OFF]	Does not use the multi-display function.
	[USER1]	Displays four-screen display with the setting in [USER1].
[MULTI DISPLAY]	[USER2]	Displays four-screen display with the setting in [USER2].
	[USER3]	Displays four-screen display with the setting in [USER3].

\*1 This can be set when the optional Interface Board equipped with corresponding input is installed in <SLOT 1>.

\*2 This can be set when the optional Interface Board equipped with corresponding input is installed in <SLOT 2>.

\*3 This is displayed when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1>.

\*4 This is displayed when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 2>.

\*5 When the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the projector, its input

name is automatically reflected from [INPUT1] to [INPUT10]. When an item that does not reflect the input name is selected, it will be disabled. \*6 If you change the settings while using the projector, the duration until the light source luminance decreases by half may shorten or the luminance may decrease.

#### 11) Press the <ENTER> button.

- The command is fixed and is displayed at the left of the selected command.
- After the command is fixed, press the <MENU> button to close the detailed setting screen.

# 172 - ENGLISH

# 12) Press ▲▼◀▶ to select [STORE], and press the <ENTER> button.

# Note

- To delete a command that has been already set, press the <DEFAULT> button on the remote control while the screen in Step 5) is displayed, or select [DELETE] at the screen in Step 6) and press the <ENTER> button.
- If multiple commands have been set for the same time, they are executed in chronological order starting from the smallest command number.
- The operating time will be the local time. (
   page 170)
- If an operation is executed with the remote control or control panel of the projector or with a control command before the command set in [SCHEDULE] is executed, the command set with the schedule function may not be executed.

# [MULTI PROJECTOR SYNC]

Set the contrast synchronization function and the shutter synchronization function.

The contrast synchronization function is a function to display a combined screen with a balanced contrast by sharing the brightness level of the video signal input to each projector when a multi-display is constructed by combining the projected image of multiple projectors. The shutter synchronization function is a function to synchronize the shutter operation of the specified projector to other projectors, and the effect using the shutter function including the fade in/fade out operation can be synchronized.

To use the contrast synchronization function and the shutter synchronization function, it is necessary to connect the projectors targeted for synchronization in a loop with daisy chain connection using the <MULTI PROJECTOR SYNC IN> terminal and the <MULTI PROJECTOR SYNC OUT> terminal. For details of how to connect the projectors, refer to "Connecting example when using the contrast synchronization function/shutter synchronization function" (+ page 59).

## Note

• The contrast synchronization function and the shutter synchronization function can be used simultaneously.

• The operation of the mechanical shutter is not included in the shutter synchronization function.

• The menu items in the [PROJECTOR SETUP] menu → [MULTI PROJECTOR SYNC] are the same as the following setting items.

- − The [PICTURE] menu → [DYNAMIC CONTRAST] → [USER] → [MULTI PROJECTOR SYNC]
- − The [DISPLAY OPTION] menu  $\rightarrow$  [SHUTTER SETTING]  $\rightarrow$  [MULTI PROJECTOR SYNC]

# Setting the contrast synchronization function

# 1) Press ▲▼ to select [MULTI PROJECTOR SYNC].

- 2) Press the <ENTER> button.
  - The [MULTI PROJECTOR SYNC] screen is displayed.
- 3) Press ▲▼ to select [MODE].

# 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Select this item when the contrast synchronization function and the shutter synchronization function are not used.
[MASTER]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item only on one projector out of the projectors that are linked. The projector set as the [MASTER] will calculate the brightness level of the video signal to become optimum on the whole combined screen for each frame. All the projectors targeted for contrast synchronization will control the dynamic contrast function based on the calculation result.
[SLAVE]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item in all the linked projectors excluding the projector set as the [MASTER].

• When anything other than [OFF] is selected, the diagnostic result is displayed in [LINK STATUS], indicating if all the projectors including the projectors targeted for synchronization are correctly connected, and if [MODE] is correctly set.

[LINKED]	All the projectors are correctly connected, and correctly set. They are in the condition that the contrast synchronization function or the shutter synchronization function can be used.
[NO LINK]	The projectors are not correctly connected, or not correctly set. Check the cable connection status and the projector setting for each projector that is linked.

# 5) Press ▲▼ to select [CONTRAST SYNC].

# 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Select this item when the contrast synchronization function is not used.
[ON]	Select this item when the contrast synchronization function is used.

#### Note

- The contrast synchronization function will operate when all of the following conditions are fulfilled.
- All the projectors to be linked are connected in a loop with the daisy chain connection. (Maximum 64 projectors)
- [MODE] on only one projector that is linked is set to [MASTER], and [MODE] on all other projectors are set to [SLAVE].
- [CONTRAST SYNC] on the projectors to perform the contrast synchronization is set to [ON].
- It is possible to set [CONTRAST SYNC] to [OFF] for the projectors that are linked but not to synchronize.

#### Setting the shutter synchronization function

### 1) Press ▲▼ to select [MULTI PROJECTOR SYNC].

- 2) Press the <ENTER> button.
  - The [MULTI PROJECTOR SYNC] screen is displayed.

#### 3) Press ▲▼ to select [MODE].

### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

I IOFF1	Select this item when the contrast synchronization function and the shutter synchronization function are not used.
[MASTER]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item only on one of the linked projectors that becomes the synchronization source of the shutter operation.
[SLAVE]	Select this item when the contrast synchronization function or the shutter synchronization function is used. Set this item in all the linked projectors excluding the projector set as the [MASTER].

When anything other than [OFF] is selected, the diagnostic result is displayed in [LINK STATUS], indicating
if all the projectors including the projectors targeted for synchronization are correctly connected, and if
[MODE] is correctly set.

All the projectors are correctly connected, and correctly set. They are in the condition that the contrast synchronization function or the shutter synchronization function can be used.
The projectors are not correctly connected, or not correctly set. Check the cable connection status and the projector setting for each projector that is linked.

### 5) Press ▲▼ to select [SHUTTER SYNC].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Select this item when the shutter synchronization function is not used.
[ON]	Select this item when the shutter synchronization function is used.

#### Note

- The shutter synchronization function will operate when all of the following conditions are fulfilled.
- All the projectors to be linked are connected in a loop with the daisy chain connection. (Maximum 64 projectors)
- [MODE] on only one projector that is linked is set to [MASTER], and [MODE] on all other projectors are set to [SLAVE].
- [SHUTTER SYNC] on the projectors to perform the shutter synchronization is set to [ON].
- It is possible to set [SHUTTER SYNC] to [OFF] for the projectors that are linked but not to synchronize.
- The shutter operation by the shutter synchronization function will follow the setting of the [DISPLAY OPTION] menu → [SHUTTER SETTING] on the projector that [MODE] is set to [MASTER].
- When the input signal to each linked projector is not synchronized, the timing of the shutter operation between the projectors may shift up to
  1 frame while using the shutter synchronization function.
- The shutter function of the projector with [MODE] set to [SLAVE] can be operated individually. At that time, the shutter operation will follow the setting of the [DISPLAY OPTION] menu → [SHUTTER SETTING] set in that projector.

# 174 - ENGLISH

# [RS-232C]

Set the communication conditions of the <SERIAL IN>/<SERIAL OUT> terminals. For details on the connection method for RS-232C communication, refer to "<SERIAL IN>/<SERIAL OUT> terminal" (➡ page 249).

# Setting the communication condition of the <SERIAL IN> terminal

# 1) Press $\blacktriangle \forall$ to select [RS-232C].

- 2) Press the <ENTER> button.
  - The [RS-232C] screen is displayed.

### 3) Press ▲▼ to select [INPUT SELECT].

4) Press  $\triangleleft$  to switch the item.

[PROJECTOR]	Performs the RS-232C communication with the <serial in=""> terminal of the projector.</serial>
	Performs the RS-232C communication via the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) and the <digital lan="" link=""> terminal.</digital>

### 5) Press ▲▼ to select [(IN) BAUDRATE].

#### 6) Press **♦** to switch the item.

• The items will switch each time you press the button.

[9600]	
[19200]	Select the proper speed.
[38400]	

### 7) Press $\blacktriangle \forall$ to select [(IN) PARITY].

# 8) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[NONE]	
[EVEN]	Select the parity condition.
[ODD]	

# Setting the communication condition of the <SERIAL OUT> terminal

# 1) Press ▲▼ to select [RS-232C].

#### 2) Press the <ENTER> button.

• The [RS-232C] screen is displayed.

# 3) Press ▲▼ to select [(OUT) BAUDRATE].

### 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[9600]	
[19200]	Select the proper speed.
[38400]	

### 5) Press $\blacktriangle \blacksquare$ to select [(OUT) PARITY].

#### 6) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[NONE]	
[EVEN]	Select the parity condition.
[ODD]	

# Setting the response

- 1) Press ▲▼ to select [RS-232C].
- 2) Press the <ENTER> button.
   The [RS-232C] screen is displayed.
- 3) Press ▲▼ to select [RESPONSE(ID ALL)].
- 4) Press  $\triangleleft$  to switch the item.

[ON]	Returns the response when an ID is designated as ALL.
[OFF]	Does not return the response when an ID is designated as ALL.

- 5) Press  $\blacktriangle \forall$  to select [GROUP].
- 6) Press  $\triangleleft$  to switch the item.

	Controls multiple projectors simultaneously by sending the ID of RS-232C. You can set groups from
	[A] to [Z]. The projector responds when the ID of RS-232C matches the setting.

## 7) Press ▲▼ to select [RESPONSE(ID GROUP)].

#### 8) Press $\triangleleft$ to switch the item.

[ON]	Returns the response when an ID is designated as GROUP.
[OFF]	Does not return the response when an ID is designated as GROUP.

#### Note

- When [INPUT SELECT] is set to [DIGITAL LINK], communication using that serial terminal is available only when the corresponding device (such as the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G)) is connected to the <DIGITAL LINK/ LAN> terminal.
- When transferring logos via the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G), setting for "NO SIGNAL SLEEP" of the DIGITAL LINK output supported device should be set to "OFF" to avoid interruption of communication.
- When [INPUT SELECT] is set to [DIGITAL LINK], communication speed for input is fixed to 9 600 bps and the parity is fixed to "NONE".

# [REMOTE2 MODE]

You can set the <REMOTE 2 IN> terminal.

### 1) Press ▲▼ to select [REMOTE2 MODE].

- 2) Press **♦** to switch the item.
  - The items will switch each time you press the button.

[DEFAULT]	Uses pin assignment of the <remote 2="" in=""> terminal in standard setting. (➡ page 253)</remote>
[USER]	Changes the setting of the <remote 2="" in=""> terminal.</remote>

• When [USER] is selected, proceed to Step 3).

- 3) Press the <ENTER> button.
- 4) Press ▲▼ to select one from [PIN2] to [PIN8], and press ◀▶ to switch the setting.

# [FUNCTION BUTTON]

Set the function of the <FUNCTION> button on the remote control.

1) Press  $\blacktriangle \forall$  to select [FUNCTION BUTTON].

### 2) Press the <ENTER> button.

- The [FUNCTION BUTTON] screen is displayed.
- 3) Press  $\blacktriangle \nabla$  to select a function.

[DISABLE]	Disables the <function> button.</function>
[MULTI DISPLAY]	Switches the [MULTI DISPLAY MODE] setting. (+ page 183)

# 176 - ENGLISH

[SUB MEMORY]	Displays the sub memory list. (+ page 188)	
[SYSTEM SELECTOR]	<ul> <li>Switches the [SYSTEM SELECTOR] setting according to the input signal of the image being projected.</li> <li>When the input is SDI1 to SDI4 equipped on this projector as the standard projector. <ul> <li>The [DISPLAY OPTION] menu → [SDI IN] → [SINGLE LINK SETTING] → [SDI1]/[SDI2]/[SDI3]/ [SDI4] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SDI IN] → [DUAL LINK SETTING] → [SDI1-2]/[SDI3-4] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SDI IN] → [QUAD LINK SETTING] → [SYSTEM SELECTOR]</li> <li>When the input is SDI1 to SDI4 on the Interface Board</li> <li>The [DISPLAY OPTION] menu → [SLOT IN] → [SINGLE LINK SETTING] → [SDI1 [SLOT1]]/ [SDI2 [SLOT1]]/[SDI3 [SLOT2]]/[SDI4 [SLOT2]] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SLOT IN] → [DUAL LINK SETTING] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SLOT IN] → [DUAL LINK SETTING] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SLOT IN] → [QUAD LINK SETTING] → [SYSTEM SELECTOR]</li> <li>The [DISPLAY OPTION] menu → [SLOT IN] → [QUAD LINK SETTING] → [SYSTEM SELECTOR]</li> <li>When the input is anything other than SDI The [PICTURE] menu → [SYSTEM SELECTOR]</li> </ul> </li> </ul>	
[SYSTEM DAYLIGHT VIEW]	Switches the [SYSTEM DAYLIGHT VIEW] setting. ( page 97)	
[FREEZE]	Temporarily pauses the image. ( page 145)	
[WAVEFORM MONITOR]	Displays the waveform of the input signal. (+ page 145)	
[LENS MEMORY LOAD]	Loads the registered lens memory. (+ page 151)	
[PROJECTION METHOD]	Switches the [PROJECTION METHOD] setting. (+ page 148)	

# 4) Press the <ENTER> button.

# [STATUS]

Display the status of the projector.

- 1) Press ▲▼ to select [STATUS].
- 2) Press the <ENTER> button.

• The [STATUS] screen is displayed.

# 3) Press **♦** to switch the pages.

• The page will change each time you press the button.

[PROJECTOR TYPE]	Displays the projector type and serial number of the projector.		
[PROJECTOR RUNTIME]	Displays the runtime of the projector.		
[LIGHT RUNTIME]	Displays the runtime of the light source 1 and the light source 2.		
[MAIN/SUB VERSION]	Displays the main and sub versions of the firmware of the projector.		
[INTAKE AIR TEMP.]*1	Displays the status of the intake air temperature of the projector.		
[OPTICS MODULE TEMP.]*1	Displays the status of the internal temperature of the projector.		
[EXHAUST AIR TEMP.]*1	Displays the status of the exhaust air temperature of the projector.		
[LIGHT1-B TEMP.]*1	Diaplays the light source 1 temperature statue of the prejector		
[LIGHT1-S TEMP.]*1	Displays the light source 1 temperature status of the projector.		
[LIGHT2-B TEMP.]*1	Displays the light source 2 temperature status of the projector.		
[LIGHT2-S TEMP.]*1			
[SELF TEST]	Displays the status of the projector.		
[INPUT]	Displays the input terminal currently selected. Displays the representative input terminal when one image is displayed with multiple input signals.		
[SIGNAL NAME]	Displays the input signal name.		
[MEMORY NO.]	Displays the memory number of the input signal.		
[BACKUP INPUT STATUS]	Displays whether switching to the backup input signal is possible or not when [BACKUP INPUT MODE] is set to [OFF]. ( page 117)		
[NUMBER OF REGISTERED SIGNAL]	Displays the number of registered signals.		
[COOLING CONDITION]	Displays the set cooling conditions.		
[ATMOSPHERIC PRESSURE]	Displays the atmospheric pressure.		
[REMOTE2 STATUS]	Displays the control status of the REMOTE2.		
[AC VOLTAGE]	Displays the input supply voltage.		
[LENS TYPE] <sup>*2</sup>	Displays the type name (type of the projection lens) set to the projection lens.		

[LENS ID]*2	Displays the ID set to the project	ion lens	
[LENS NAME]*2	Displays the name set to the projection lens.		
[LENS THROW RATIO] <sup>*2</sup>		Displays the range of throw ratio supported by the projection lens in accordance with the [LENS	
[LENS ZOOM TYPE] <sup>*2</sup>	Displays the drive method of the	zoom motor attached to the projection lens.	
[ZOOM CALIBRATION]*2	Displays the zoom calibration result ([OK]/[FAILED]) and the calibration date.		
	[POWER ON TIMES]	Displays the number of times the power is turned on.	
[ON COUNT]	[MECHANICAL SHUTTER]	Displays the number of times the mechanical shutter is closed. It is counted when [MECHANICAL SHUTTER] is set to [ENABLE].	
[FILTER TYPE]	Displays the setting value of the TYPE].	Displays the setting value of the [PROJECTOR SETUP] menu $\rightarrow$ [FILTER SETTING] $\rightarrow$ [FILTER	
[FILTER COUNTER]*3*4	Displays the runtime of the filter (	(counter numeric value) and the recommend time to replace the filter.	
[OPERATING MODE]	Displays the setting value of the [OPERATING MODE].	$[PROJECTOR SETUP] \text{ menu} \rightarrow [OPERATION SETTING] \rightarrow$	
[HIGH]	Displays the runtime of the light s	source with [OPERATING MODE] set to [HIGH].	
[NORMAL]	Displays the runtime of the light s	source with [OPERATING MODE] set to [NORMAL].	
[LONG LIFE1]	Displays the runtime of the light s	source with [OPERATING MODE] set to [LONG LIFE1].	
[LONG LIFE2]	Displays the runtime of the light s	source with [OPERATING MODE] set to [LONG LIFE2].	
[LONG LIFE3]	Displays the runtime of the light s	source with [OPERATING MODE] set to [LONG LIFE3].	
[USER1]	Displays the runtime of the light source with [OPERATING MODE] set to [USER1].		
[USER2]	Displays the runtime of the light source with [OPERATING MODE] set to [USER2].		
[USER3]	Displays the runtime of the light source with [OPERATING MODE] set to [USER3].		
[CONSOLIDATED RUNTIME] <sup>.</sup> ⁵	Converts the total runtime of the light sources with [OPERATING MODE] set to each item into the time used with the [NORMAL] setting. The consolidated runtime is used for a rough indication about when to perform maintenance when the projector is used in combination of each item in [OPERATING MODE].		
	[ET-UK20]	Displays the activation status by the Upgrade Kit (Model No.: ET-UK20).	
[UPGRADE KIT]	[ET-CUK10]	Displays the activation status by the Auto Screen Adjustment Upgrade Kit (Model No.: ET-CUK10).	
[SLOT1]	Displays the product model number of the Interface Board installed in <slot 1="">. Also, the firmware version is displayed after the product model number.</slot>		
[SLOT2]	Displays the product model number of the Interface Board installed in <slot 2="">. Also, the firmware version is displayed after the product model number.</slot>		
	[INPUT]	Displays the input terminal used for the projected image. Displays the representative input terminal when one image is displayed with multiple input signals. [MULTI DISPLAY] is displayed while in the four-screen display mode.	
	[SIGNAL FORMAT]	Displays the format of the input signal.	
	[LINK]	Displays the settings of [SDI LINK], [HDMI LINK], and [DVI-D LINK]. Displays the determination result of the signal when set to [AUTO].	
[SIGNAL INFORMATION]	[SIMUL]	Displays the [SIMUL INPUT SETTING] setting. Displays the determination result of the signal when set to [AUTO(x2-speed)] or [AUTO(x4-speed)].	
	[4K DIVISION]	Displays the [4K DIVISION] setting. Displays the determination result of the signal when set to [AUTO].	
	[COLOR FORMAT]	Displays the color format of the input signal.	
	[SAMPLING]	Displays the sampling information of the input signal.	
	[BIT DEPTH]	Displays the gradation of the input signal.	
	[SIGNAL LEVEL]	Displays the signal level of the input signal.	

	[INPUT]	Displays the input terminal used for the projected image.
	[UPPER LEFT INPUT], [UPPER RIGHT INPUT], [LOWER LEFT INPUT], [LOWER RIGHT INPUT]	Displays the input terminal corresponding to each screen while in the four-screen display mode.
	[SIGNAL FORMAT]	Displays the format of the input signal.
[DETAILED INFORMATION]	[SIGNAL FREQUENCY]	Displays the frequency of the input signal.
	[SCAN TYPE]	Displays the scan type of the input signal.
	[TOTAL DOTS]	Displays the total dot count of the input signal.
	[DISPLAY DOTS]	Displays the number of input signal display dots.
	[TOTAL LINES]	Displays the total line count of the input signal.
	[DISPLAY LINES]	Displays the number of input signal display lines.
	[COLOR FORMAT]	Displays the color format of the input signal.
	[SAMPLING]	Displays the sampling information of the input signal.
	[BIT DEPTH]	Displays the gradation of the input signal.
	[SIGNAL LEVEL]	Displays the signal level of the input signal.

\*1 The temperature status is indicated with text color (green/yellow/red) and bar scale. Use the projector within the range that the indication is green.

\*2 This is displayed only when the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

\*3 In the following cases, the recommended time to replace the filter is not set, and it is not displayed. When the [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to [NORMAL], [USER1], [USER2], or [USER3], and the [PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER TYPE] is set to [LONG LIFE]. When the [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3].

\*4 If the runtime of the filter exceeds the recommended time to replace the filter, the runtime is displayed in red.

\*5 [CONSOLIDATED RUNTIME] can be obtained with the following calculation formula. Values obtained by the calculation formula contain a slight error.

#### Conversion formula for [CONSOLIDATED RUNTIME]

#### **A** x 2.5 + **B** x 1.0 + **C** x 0.5 + **D** x 0.3 + **E** x 0.2

• A: Runtime of the light source with [OPERATING MODE] set to [HIGH]

• B: Runtime of the light source with [OPERATING MODE] set to [NORMAL], [USER1], [USER2], or [USER3]

• C: Runtime of the light source with [OPERATING MODE] set to [LONG LIFE1]

- D: Runtime of the light source with [OPERATING MODE] set to [LONG LIFE2]
- E: Runtime of the light source with [OPERATING MODE] set to [LONG LIFE3]

### Note

- The content of the status can be sent to the E-mail address (up to two addresses) set in "[E-mail set up] page" (> page 213) when the <ENTER> button is pressed while displaying the pages 1/6 to 5/6 of the [STATUS] screen.
- The detailed information of the input signal is displayed when the <ENTER> button is pressed while displaying the page 6/6 of the **[STATUS]** screen. Information for multiple input signals may be displayed depending on the projected image. Press **↓** to switch pages.
- There are items that are displayed or not displayed in [SIGNAL INFORMATION] and [DETAILED INFORMATION] depending on the setting
  or the input signal.
- If any abnormality has occurred on the projector, press the <DEFAULT> button while the [STATUS] screen is displayed to display the detail screen of the error information.
- For details on the contents displayed in [SELF TEST], refer to "Self-diagnosis display" (> page 235).

# [AC VOLTAGE MONITOR]

Enable or disable the AC voltage monitor function. The value of input supply voltage is displayed on the selfdiagnosis display at the side of the projector when enabled.

### 1) Press ▲▼ to select [AC VOLTAGE MONITOR].

### 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the AC voltage monitor function.
[ON]	Enables the AC voltage monitor function.

#### Note

• When [ON] is set, the value of the input supply voltage is always displayed in the self-diagnosis display while the main power of the projector is turned on.

- Even when [OFF] is set, the value of input supply voltage can be displayed temporarily in the self-diagnosis display by operating the button on the remote control. (
   page 86)
- The value of input supply voltage cannot be displayed in the self-diagnosis display during standby when the [PROJECTOR SETUP] menu → [STANDBY MODE] (→ page 168) is set to [ECO].

# [FILTER SETTING]

Set the type of filter. The filter runtime (counter numeric value) can also be reset.

# Setting [FILTER TYPE]

Set the type of filter attached to the projector.

1) Press ▲▼ to select [FILTER SETTING].

# 2) Press the <ENTER> button.

• The [FILTER SETTING] screen is displayed.

# 3) Press ▲▼ to select [FILTER TYPE].

• The [FILTER TYPE] screen is displayed.

# 4) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[NORMAL]	Factory default setting. Select this item when the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory) is attached to the projector. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [HIGH], the recommended time to replace the filter is set to 2 000 hours. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [NORMAL], [USER1], [USER2], or [USER3], the recommended time to replace the filter is set to 4 000 hours. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the recommended time to replace the filter is not set.
[LONG LIFE]	Select this item when the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached to the projector. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [HIGH], the recommended time to replace the filter is set to 4 000 hours. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to anything other than [HIGH], the recommended time to replace the filter is not set.
[SMOKE CUT]	Select this item when the optional Smoke Cut Filter (Model No.: ET-SFR330) is attached to the projector. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [HIGH], the recommended time to replace the filter is set to 50 hours. When the [PROJECTOR SETUP] menu $\rightarrow$ [OPERATION SETTING] $\rightarrow$ [OPERATING MODE] is set to [NORMAL], [USER1], [USER2], or [USER3], the recommended time to replace the filter is set to 100 hours.

### Note

- The [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] cannot be set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when [FILTER TYPE] is set to [SMOKE CUT]. Set [OPERATING MODE] to [HIGH], [NORMAL], [USER1], [USER2], or [USER3] when using the optional Smoke Cut Filter (Model No.: ET-SFR330).
- If the runtime of the filter exceeds the recommended time to replace the filter that is set, the time is displayed in red in the following menu. Perform maintenance or replacement of the filter.
  - − [FILTER SETTING] → [FILTER COUNTER RESET]
  - [STATUS] → [FILTER COUNTER]
- Perform maintenance or replacement of the filter in the following cases.
- The filter is clogged, causing the filter replacement message to appear on the screen and the filter indicator <FILTER> to light in red.
- Continuing to use the projector with incorrect settings may cause failure.

# **Resetting [FILTER COUNTER]**

Reset the filter runtime (counter numeric value).

# 1) Press ▲▼ to select [FILTER SETTING].

2) Press the <ENTER> button.

• The [FILTER SETTING] screen is displayed.

3) Press ▲▼ to select [FILTER COUNTER RESET], and press the <ENTER> button.

# 180 - ENGLISH

- 4) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.
  - The [PROJECTOR SETUP] menu  $\rightarrow$  [STATUS]  $\rightarrow$  [FILTER COUNTER] is displayed as "0".

### Note

 If the recommended time to replace the filter is set, the filter runtime (counter numerical value) and the recommended time to replace the filter are displayed in [FILTER COUNTER RESET].

# [SAVE ALL USER DATA]

Save the various setting values as a backup in the built-in memory of the projector.

- 1) Press ▲▼ to select [SAVE ALL USER DATA].
- 2) Press the <ENTER> button.
  - The [SECURITY PASSWORD] screen is displayed.
- 3) Enter a security password and press the <ENTER> button.
- 4) When the confirmation screen is displayed, press ◀ to select [OK], and press the <ENTER> button.
   [PROGRESS] is displayed while saving data.

### Note

- Data set from the computer application is not included in [ALL USER DATA].
- The data saved by executing [SAVE ALL USER DATA] is not deleted even if the [PROJECTOR SETUP] menu → [INITIALIZE] → [ALL USER DATA] is executed.

# [LOAD ALL USER DATA]

Load the various setting values saved as a backup in the built-in memory of the projector.

- 1) Press  $\blacktriangle \forall$  to select [LOAD ALL USER DATA].
- 2) Press the <ENTER> button.
  - The [SECURITY PASSWORD] screen is displayed.
- 3) Enter a security password and press the <ENTER> button.
- 4) When the confirmation screen is displayed, press **(**) to select [OK], and press the **<ENTER>** button.

### Note

- The projector enters the standby mode to reflect the setting values when [LOAD ALL USER DATA] is executed.
- Data registered from a computer is not included in [ALL USER DATA].

# [INITIALIZE]

Return various setting values to their factory default settings.

- 1) Press ▲▼ to select [INITIALIZE].
- 2) Press the <ENTER> button.
  - The [SECURITY PASSWORD] screen is displayed.
- 3) Enter a security password and press the <ENTER> button.
  - The [INITIALIZE] screen is displayed.
- 4) Press  $\blacktriangle \nabla$  to select an item to initialize.

[ALL USER DATA]	Returns all setting values including [REGISTERED SIGNAL], [NETWORK/E-MAIL], and [LOGO IMAGE] to the factory default settings. The projector enters the standby mode to reflect the setting values.
[REGISTERED SIGNAL]	Deletes all the setting values saved for each input signal. To delete only a part of a registered signal, perform the procedure described in "Deleting the registered signal" ( page 186).
[NETWORK/E-MAIL]	Returns [NETWORK SETUP] and [E-mail set up] to factory default settings.
[LOGO IMAGE]	Deletes the image registered in [USER LOGO].

5) Press the <ENTER> button.

### 6) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.

### Note

- The security password is the password set in the [SECURITY] menu → [SECURITY PASSWORD CHANGE]. Initial password of the factory default setting: ▲▶▼◀▲▶▼◀
- The following settings are not initialized even if [ALL USER DATA] is executed.
- The [DISPLAY OPTION] menu  $\rightarrow$  [UNIFORMITY]
- The [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE]
- The [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [MAX LIGHT OUTPUT LEVEL]
- The [PROJECTOR SETUP] menu  $\rightarrow$  [STANDBY MODE]
- The [PROJECTOR SETUP] menu → [LENS] → [ACTIVE FOCUS OPTIMIZER] → [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK]
- [FILTER TYPE] and [FILTER COUNTER] in the [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]
- When a projection lens equipped with EEPROM is attached, following setting will not return to factory default setting even if [ALL USER DATA] is executed.
  - The [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS TYPE]
- The [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [LENS INFORMATION SETTING]  $\rightarrow$  [LENS ID] and [LENS NAME]
- To initialize the setting values of [FOCUS OFFSET BRIGHT] and [FOCUS OFFSET DARK] in the [PROJECTOR SETUP] menu -> [LENS]
- $\rightarrow$  [ACTIVE FOCUS OPTIMIZER], execute the [PROJECTOR SETUP] menu  $\rightarrow$  [LENS]  $\rightarrow$  [FOCUS OFFSET SETUP]  $\rightarrow$  [INITIALIZE].
- If [ALL USER DATA] is executed, the [INITIAL SETTING] screen is displayed when the projection is started the next time.

# [SERVICE PASSWORD]

This function is used by a service person.

# [MULTI DISPLAY] menu

On the menu screen, select [MULTI DISPLAY] from the main menu, and select an item from the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

# Using the multi-display function

Four images can be displayed simultaneously by dividing the projection screen into four.

- 1) Press ▲▼ to select [MULTI DISPLAY MODE].
- 2) Press the <ENTER> button.
  - The [MULTI DISPLAY MODE] screen is displayed.
- 3) Press  $\blacktriangle \blacksquare$  to select a function.

[OFF]	Does not use the multi-display function.	
[USER1]		
[USER2]	Displays four-screen display with the setting in "Setting the multi-display function" (> page 183).	
[USER3]		

### 4) Press the <ENTER> button.

### Setting the multi-display function

The setting of the multi-display function can be saved to [USER1], [USER2], or [USER3].

### Press ▲▼ to select [MULTI DISPLAY MODE].

- 2) Press the <ENTER> button.
  - The [MULTI DISPLAY MODE] screen is displayed.
- 3) Press ▲▼ to select the desired mode from [USER1], [USER2], and [USER3], and press the <ENTER> button.
- 4) Press ▲▼ to select [UPPER LEFT WINDOW], [UPPER RIGHT WINDOW], [LOWER LEFT WINDOW], or [LOWER RIGHT WINDOW], and press the <ENTER> button.
  - The [UPPER LEFT WINDOW] screen, the [UPPER RIGHT WINDOW] screen, the [LOWER LEFT WINDOW] screen, or the [LOWER RIGHT WINDOW] screen is displayed.
- 5) Press ▲▼ to select the input terminal to be displayed in the window, and press the <ENTER> button.
  - The input terminal that can be selected varies depending on the structure of the optional Interface Board installed in the slot.
- 6) Press ▲▼ to select [FRAME LOCK].

### 7) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[UPPER LEFT WINDOW]	Sets the frame lock for the input signal set to the upper left window.	
[UPPER RIGHT WINDOW]	Sets the frame lock for the input signal set to the upper right window.	
[LOWER LEFT WINDOW]	Sets the frame lock for the input signal set to the lower left window.	
[LOWER RIGHT WINDOW]	Sets the frame lock for the input signal set to the lower right window.	

### Note

- The image currently displayed in the four dividing screen is not projected correctly when the following video signal is input.
  - Video signal with resolution exceeding 1 920 x 1 200 dots
  - Video signal with dot clock frequency exceeding 162 MHz
- 6G-SDI signal, 12G-SDI signal
- Two input terminals of the Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) cannot be selected simultaneously as the input to be displayed in the four-screen display window. Only one of the input terminals can be selected.
- The appearance may vary for each when an image from one input terminal is displayed on multiple screens.
- The image adjustment values such as the [PICTURE] menu → [PICTURE MODE], [GAMMA], or [COLOR TEMPERATURE] that are set to the upper left screen are applied to all screens.
- The movement of the displayed image becomes discontinuous when [FRAME LOCK] is set for the still image signal.
- The movement of the displayed image may become discontinuous for the images where [FRAME LOCK] is not set.

### Chapter 4 Settings — [MULTI DISPLAY] menu

- [MULTI DISPLAY MODE] is fixed to [OFF] and the four-screen display is not possible in the following cases.
  - When the [DISPLAY OPTION] menu → [BACKUP INPUT SETTING] → [BACKUP INPUT MODE] is set to anything other than [OFF]
  - When the [DISPLAY OPTION] menu  $\rightarrow$  [SIMUL INPUT SETTING] is set to anything other than [OFF]
  - When the [DISPLAY OPTION] menu  $\rightarrow$  [SDI IN]  $\rightarrow$  [SDI LINK] is set to anything other than [SINGLE]
- When the [DISPLAY OPTION] menu  $\rightarrow$  [SLOT IN]  $\rightarrow$  [HDMI LINK]/[DVI-D LINK]/[SDI LINK] is set to anything other than [SINGLE]
- The setting in the [ADVANCED MENU] menu → [FRAME RESPONSE] is disabled and fixed to [NORMAL] while in the four-screen display mode.
- The setting in the [ADVANCED MENU] menu  $\rightarrow$  [FRAME CREATION] is disabled and fixed to [OFF] while in the four-screen display mode.
- The [ADVANCED MENU] menu  $\rightarrow$  [QUAD PIXEL DRIVE] is fixed to [ON] while in the four-screen display mode.

# [TEST PATTERN] menu

### On the menu screen, select [TEST PATTERN] from the main menu.

Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

# [TEST PATTERN]

Display the test pattern built-in to the projector.

Settings of position, size, and other factors will not be reflected in test patterns. Make sure to display the input signal before performing various adjustments.

### 1) Press **♦** to switch the [TEST PATTERN] item.

• The items will switch each time you press the button.

Menu screen + All white	
Menu screen + All black	
Menu screen + Window	
Menu screen + Window (inversion)	
Menu screen + Color bar (vertical)	Displays a test pattern with the menu screen. Select a desired test pattern.
Menu screen + Color bar (horizontal)	
Menu screen + 16:9/4:3 aspect frame	
Menu screen + Cross hatch	
Menu screen + Focus	
Menu screen + Input screen	Displays the menu screen and input signal. Built-in test patterns are not displayed.

### Note

- Press the <ON SCREEN> button on the remote control while the test pattern is displayed to hide the menu screen.

### Changing the color of the cross hatch test pattern

The color can be changed when the "Menu screen + Cross hatch" test pattern is displayed.

- 1) Press **(**) to select the "Menu screen + Cross hatch" test pattern.
- 2) Press the <ENTER> button.
  - The [TEST PATTERN COLOR] screen is displayed.
- 3) Press  $\blacktriangle \forall$  to select a color, and press the <ENTER> button.
  - The color of the cross hatch test pattern is changed to the selected color.

### Note

- The test pattern color settings return to [WHITE] when the projector is switched off.
- · Colors of the test patterns other than cross hatch test patterns cannot be changed.

# [SIGNAL LIST] menu

On the menu screen, select [SIGNAL LIST] from the main menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

Registered signal details

Memory number: A1 (1-2)

Sub memory number

When the address number (A1, A2, ... L7, L8) signal is registered

A name can be set for each sub memory (➡ page 188).

# **Registering new signals**

After a new signal is input and the <MENU> button on the remote control or the control panel is pressed, the registration is completed and the **[MAIN MENU]** screen is displayed.

### Note

- Up to 96 signals, including sub memories, can be registered to the projector.
- There are 12 pages (eight memories of A through L, with eight memories possible on each page) for memory numbers, and the signal is registered to the lowest number that is available. If there is no available memory number it will be overwritten from the oldest signal.
- The name to be registered is automatically determined by the input signal.
- If a menu is being displayed, the new signals will be registered at the instant they are input.

# Renaming the registered signal

Registered signals can be renamed.

- 1) Press ▲▼◀▶ to select the signal of which name is to be changed.
- 2) Press the <ENTER> button.
  - The [REGISTERED SIGNAL STATUS] screen is displayed.
  - The memory number, input terminal, input signal name, frequency, synch polarity, etc., are displayed.
  - Press the <MENU> button to return to the [REGISTERED SIGNAL LIST] screen.
- 3) Press the <ENTER> button.
  - The [REGISTERED SIGNAL SETUP] screen is displayed.
- 4) Press ▲▼ to select [SIGNAL NAME CHANGE].
- 5) Press the <ENTER> button.
  - The [SIGNAL NAME CHANGE] screen is displayed.
- 6) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the text, and press the <ENTER> button to enter the text.
- 7) After the name is changed, press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select [OK], and press the <ENTER> button.
  - The registration is completed and the [REGISTERED SIGNAL SETUP] screen returns.
  - When pressing ▲▼◀▶ to select [CANCEL] and pressing the <ENTER> button, the changed signal name will not be registered and an automatically registered signal name will be used.

# Deleting the registered signal

Registered signals can be deleted.

- 1) Press ▲▼◀▶ to select the signal to delete.
- 2) Press the <DEFAULT> button on the remote control.
  - The [REGISTERED SIGNAL DELETE] screen is displayed.
  - To cancel the deletion, press the <MENU> button to return to the [REGISTERED SIGNAL LIST] screen.

### 3) Press the <ENTER> button.

• The selected signal will be deleted.

### Note

• A registered signal can also be deleted from [REGISTERED SIGNAL DELETE] on the [REGISTERED SIGNAL SETUP] screen.

# Protecting the registered signal

- 1) Press ▲▼◀▶ to select the signal to protect.
- 2) Press the <ENTER> button.
  - The [REGISTERED SIGNAL STATUS] screen is displayed.
- 3) Press the <ENTER> button.
   The [REGISTERED SIGNAL SETUP] screen is displayed.
- 4) Press  $\blacktriangle \nabla$  to select [LOCK].

# 5) Press **I** to switch the item.

• The items will switch each time you press the button.

[OFF]	The signal is not protected.
[ON]	The signal is protected.

• A lock icon is displayed at the right of the **[REGISTERED SIGNAL LIST]** screen when [LOCK] is set to [ON].



### Note

 When [LOCK] is set to [ON], signal deletion, image adjustment, and automatic setup are not available. To perform these operations, set [LOCK] to [OFF].

- A signal can be registered to the sub memory even if it is protected.
- Even a protected signal will be deleted if [INITIALIZE] is executed.

# Expanding signal lock-in range

- 1) Press  $\blacktriangle \lor \blacklozenge \lor$  to select the signal to set.
- 2) Press the <ENTER> button.
  - The [REGISTERED SIGNAL STATUS] screen is displayed.
- 3) Press the <ENTER> button.
  - The [REGISTERED SIGNAL SETUP] screen is displayed.
- 4) Press ▲▼ to select [LOCK-IN RANGE].
- 5) Press **♦** to switch the item.
  - The items will switch each time you press the button.

[NARROW]	Select in most cases.
[WIDE]	Widens the lock-in range.

 An expansion icon is displayed at the right of the [REGISTERED SIGNAL LIST] screen when [LOCK-IN RANGE] is set to [WIDE].



### Note

- Switch the range where the signal to be input is determined to be the same signal as the already registered signal.
- To prioritize the determination that a signal is the same as the already registered signal, set this function to [WIDE].
- Use in cases such as when the synchronizing frequency of a signal to be input has changed slightly, or multiple signal lists are registered.
- This item can be set only for the DIGITAL LINK input signal, and the HDMI or DVI-D input signal of the optional Interface Board installed in the slot.
- When [WIDE] is set, the image may be distorted because a signal is recognized as the same even if its synchronizing frequency varies slightly.
- When a signal to be input corresponds to multiple signals set in [WIDE], a registered signal with a high memory number receives priority. Example: a signal to be input that corresponds to memory numbers A2, A4 and B1 will be determined to be B1.

- When a registration signal is deleted, the settings are also deleted.
- In an environment where multiple types of signals are input to the same terminal, signals are sometimes not determined correctly when the setting is set to [WIDE].

# Sub memory

The projector has a sub memory function that can register the multiple image adjustment data, even if it is recognized as the same signal by the frequency or format of the synchronization signal source.

Use this function when you need to switch the aspect or adjust the picture quality such as the white balance while using the same signal source. The sub memory includes all the data that can be adjusted for each signal, such as the screen aspect ratio and data adjusted in the [PICTURE] item (such as [CONTRAST], [BRIGHTNESS]).

### Registering to the sub memory

- 1) While in the normal screen (where no menu is displayed), press **(**).
  - The sub memory registration screen is displayed if the sub memory is not registered. Proceed to Step 3).
  - A list of sub memories registered to the signal currently input is displayed.
  - The <FUNCTION> button on the remote control can be used instead of the ◀▶ button when [SUB MEMORY] is selected from the [PROJECTOR SETUP] menu → [FUNCTION BUTTON].
- 2) Press ▲▼◀▶ to select the sub memory number to register in [SUB MEMORY LIST].
- 3) Press the <ENTER> button.
  - The [SIGNAL NAME CHANGE] screen is displayed.
- 4) Press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - To rename the registered signal, follow the procedure in Steps 6) and 7) in "Renaming the registered signal"
     (⇒ page 186).

### Switching to the sub memory

- While in the normal screen (where no menu is displayed), press <.</li>
  A list of sub memories registered to the signal currently input is displayed.
- 2) Press  $\blacktriangle \forall \blacklozenge \forall$  to select the signal to switch in [SUB MEMORY LIST].
- 3) Press the <ENTER> button.
  - This switches to the signal selected in Step 2).

### Deleting the sub memory

- 1) While in the normal screen (where no menu is displayed), press ◀▶.
  - The [SUB MEMORY LIST] screen is displayed.
- 2) Press ▲▼◀▶ to select the sub memory to be deleted, and press the <DEFAULT> button on the remote control.
  - The [REGISTERED SIGNAL DELETE] screen is displayed.
  - To cancel the deletion, press the <MENU> button to return to the [SUB MEMORY LIST] screen.

### 3) Press the <ENTER> button.

• The selected sub memory will be deleted.

# [SECURITY] menu

On the menu screen, select [SECURITY] from the main menu, and select an item from the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

When the projector is used for the first time
 Initial password: Press ▲▶▼◀▲▶▼◀ in order, and press the <ENTER> button.

### Attention

- When you select the [SECURITY] menu and press the <ENTER> button, entering a password is prompted. Enter the preset password and then continue operations of the [SECURITY] menu.
- When the password has been changed previously, enter the changed password, and press the <ENTER> button.

### Note

- The entered password is displayed with \* marks on the screen.
- An error message is displayed on the screen when the entered password is incorrect. Re-enter the correct password.

# [SECURITY PASSWORD]

Display the **[SECURITY PASSWORD]** screen when the power is turned on with the <MAIN POWER> switch set to the <OFF> side. When the entered password is incorrect, the operation will be restricted to the power standby <⊍> button, the <SHUTTER> button, and the <LENS> buttons (<FOCUS>, <ZOOM>, <SHIFT>).

### 1) Press ▲▼ to select [SECURITY PASSWORD].

### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Disables the security password entry.
[ON]	Enables the security password entry.

### Note

- The [SECURITY PASSWORD] setting is set to [OFF] by the factory default or when [ALL USER DATA] in [INITIALIZE] (
   page 181) is
   executed.
- Change the password periodically that is hard to guess.
- The security password is enabled after setting [SECURITY PASSWORD] to [ON] and turning the <MAIN POWER> switch to <OFF>.

# [SECURITY PASSWORD CHANGE]

Change the security password.

- 1) Press ▲▼ to select [SECURITY PASSWORD CHANGE].
- 2) Press the <ENTER> button.
  - The [SECURITY PASSWORD CHANGE] screen is displayed.
- 3) Press  $\blacktriangle \lor \blacklozenge \lor$  and the number (<0> <9>) buttons to set the password.

• Up to eight button operations can be set.

- 4) Press the <ENTER> button.
- 5) Re-enter the password for the confirmation.
- 6) Press the <ENTER> button.

### Note

- The entered password is displayed with \* marks on the screen.
- When numerical values are used for the security password, the security password is required to be initialized if the remote control is lost. Consult your dealer for the method of initialization.

# [DISPLAY SETTING]

Overlap the security message (text or image) over the projecting image.

1) Press  $\blacktriangle \forall$  to select [DISPLAY SETTING].

### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[OFF]	Hides the security message.
[TEXT]	Displays the text set in the [SECURITY] menu $\rightarrow$ [TEXT CHANGE].
[USER LOGO]	Displays the image registered by the user.

### Note

• To create/register the [USER LOGO] image, use "Logo Transfer Software" included in the supplied CD-ROM.

# [TEXT CHANGE]

Edit the text to be displayed when [TEXT] is selected in [DISPLAY SETTING].

- 1) Press ▲▼ to select [TEXT CHANGE].
- 2) Press the <ENTER> button.
  - The [TEXT CHANGE] screen is displayed.
- 3) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the text, and press the <ENTER> button to enter the text.
- 4) Press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - The text is changed.

# [CONTROL DEVICE SETUP]

Enable/disable the button operations on the control panel and the remote control.

### 1) Press ▲▼ to select [CONTROL DEVICE SETUP].

2) Press the <ENTER> button.

• The [CONTROL DEVICE SETUP] screen is displayed.

3) Press ▲▼ to select [CONTROL PANEL] or [REMOTE CONTROL].

[CONTROL PANEL]	You can set the limitation on the control from the control panel.
[REMOTE CONTROL]	You can set the limitation on the control from the remote control.

### 4) Press the <ENTER> button.

• The [CONTROL PANEL] screen or the [REMOTE CONTROL] screen is displayed.

### 5) Press ▲▼ to select [CONTROL PANEL] or [REMOTE CONTROL].

### 6) Press $\triangleleft$ to switch the item.

• You can set the operation restriction from the control panel or the remote control.

[ENABLE]	Enables all button operations.
[DISABLE]	Disables all button operations.
[USER]	Operation of all buttons can be enabled/disabled separately. Refer to "Enabling/disabling any button" (➡ page 190) for details.

### 7) Press $\blacktriangle \forall$ to select [APPLY], and press the <ENTER> button.

The confirmation screen is displayed.

### 8) Press **♦** to select [OK], and press the **<**ENTER> button.

### Enabling/disabling any button

- 1) Press  $\blacktriangle \forall$  to select [CONTROL DEVICE SETUP].
- 2) Press the <ENTER> button.
  - The [CONTROL DEVICE SETUP] screen is displayed.
- 3) Press ▲▼ to select [CONTROL PANEL] or [REMOTE CONTROL].

### 4) Press the <ENTER> button.

- The [CONTROL PANEL] screen or the [REMOTE CONTROL] screen is displayed.
- 5) Press ▲▼ to select [CONTROL PANEL] or [REMOTE CONTROL].

### 6) Press **♦** to switch [USER].

### 7) Press $\blacktriangle \lor$ to select the button item to set.

• When [INPUT SELECT BUTTON] is selected, press the <ENTER> button, and then press ▲▼ to select the button to set.

	Buttons tha	at can be set
	[CONTROL PANEL]	[REMOTE CONTROL]
[POWER BUTTON]	Power standby <⊍> button, power on <  > button	
[INPUT SELECT BUTTON]	<sdi 1="" 2=""> button, <sdi 3="" 4=""> button, <digital LINK&gt; button, <slot 1=""> button, <slot 2=""> button, <input menu=""/> button</slot></slot></digital </sdi></sdi>	<dvi-d> button, <hdmi> button, <displayport> button, <sdi> button, <digital link=""> button, <slot 1=""> button, <slot 2=""> button, <input menu=""/> button</slot></slot></digital></sdi></displayport></hdmi></dvi-d>
[MENU BUTTON]	<menu> button</menu>	
[LENS BUTTON]	<lens> button</lens>	Lens buttons ( <focus>, <zoom>, <shift>)</shift></zoom></focus>
[AUTO SETUP BUTTON]	<auto setup=""> button</auto>	
[SHUTTER BUTTON]	<shutter> button</shutter>	
[ASPECT BUTTON]	_	<aspect> button</aspect>
[ON SCREEN BUTTON]		<on screen=""> button</on>
[OTHER BUTTON]	▲▼◀▶, <enter> button</enter>	Buttons not listed above

### 8) Press $\triangleleft$ to switch the item.

[ENABLE]	Enables button operations.
[DISABLE]	Disables button operations.

• When [INPUT SELECT BUTTON] is selected in Step 7), the item that can be set varies depending on the selected button.

Refer to "Item that can be set with [INPUT SELECT BUTTON]" (→ page 192) for details.

Once the switching of the item is completed, press the <MENU> button to return to the **[CONTROL PANEL]** screen or the **[REMOTE CONTROL]** screen.

### 9) Press ▲▼ to select [APPLY], and press the <ENTER> button.

• The confirmation screen is displayed.

### 10) Press **♦** to select [OK], and press the <ENTER> button.

### Note

- When a button operation is performed on the device set to [DISABLE], the [CONTROL DEVICE PASSWORD] screen is displayed. Enter the control device password.
- The [CONTROL DEVICE PASSWORD] screen will disappear when there is no operation for approx. 10 seconds.
- If the operations of both [CONTROL PANEL] and [REMOTE CONTROL] are set to [DISABLE], the projector cannot be turned off (cannot enter standby).
- When the setting has completed, the menu screen will disappear. To operate continuously, press the <MENU> button to display the main menu.
- Even when you set button operations on the remote control disabled, operations of the <ID SET> and <ID ALL> buttons on the remote control are kept enabled.

### Item that can be set with [INPUT SELECT BUTTON]

When [INPUT SELECT BUTTON] is selected in Step **7**) of "Enabling/disabling any button" (
page 190), the item that can be selected varies depending on the button to set.
The item that can be selected when each button is set is as follows.

The item that can be selected when each button is set is a

# [SDI1/2 BUTTON]

[TOGGLE]	witches between [SDI1] and [SDI2] when the button is operated.	
[SDI1]	Fixes to selection operation of the SDI1 input.	
[SDI2]	Fixes to selection operation of the SDI2 input.	
[DISABLE]	Disables button operations.	

# [SDI3/4 BUTTON]

[TOGGLE]	Switches between [SDI3] and [SDI4] when the button is operated.	
[SDI3]	Fixes to selection operation of the SDI3 input.	
[SDI4]	Fixes to selection operation of the SDI4 input.	
[DISABLE]	Disables button operations.	

# [DVI-D BUTTON]

[DVI-D1 [SLOT1]] and [DVI-D2 [SLOT1]] can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in <SLOT 1>.

[DVI-D3 [SLOT2]] and [DVI-D4 [SLOT2]] can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in <SLOT 2>.

[TOGGLE]	Switches the items in following order when the button is operated. [DVI-D1 [SLOT1]] $\rightarrow$ [DVI-D2 [SLOT1]] $\rightarrow$ [DVI-D3 [SLOT2]] $\rightarrow$ [DVI-D4 [SLOT2]]	
[DVI-D1 [SLOT1]]	Fixes to selection operation of the DVI-D1 input of the Interface Board.	
[DVI-D2 [SLOT1]]	Fixes to selection operation of the DVI-D2 input of the Interface Board.	
[DVI-D3 [SLOT2]]	ixes to selection operation of the DVI-D3 input of the Interface Board.	
[DVI-D4 [SLOT2]]	Fixes to selection operation of the DVI-D4 input of the Interface Board.	
[DISABLE]	Disables button operations.	

# [HDMI BUTTON]

[HDMI1 [SLOT1]] and [HDMI2 [SLOT1]] can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in <SLOT 1>.

[HDMI3 [SLOT2]] and [HDMI4 [SLOT2]] can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in <SLOT 2>.

[TOGGLE]	Switches the items in following order when the button is operated. [HDMI1 [SLOT1]] $\rightarrow$ [HDMI2 [SLOT1]] $\rightarrow$ [HDMI3 [SLOT2]] $\rightarrow$ [HDMI4 [SLOT2]]		
[HDMI1 [SLOT1]]	es to selection operation of the HDMI1 input of the Interface Board.		
[HDMI2 [SLOT1]]	es to selection operation of the HDMI2 input of the Interface Board.		
[HDMI3 [SLOT2]]	ixes to selection operation of the HDMI3 input of the Interface Board.		
[HDMI4 [SLOT2]]	Fixes to selection operation of the HDMI4 input of the Interface Board.		
[DISABLE]	Disables button operations.		

# [DISPLAYPORT BUTTON]

[DisplayPort1 [SLOT1]] and [DisplayPort2 [SLOT1]] can be selected when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in <SLOT 1>.

[DisplayPort3 [SLOT2]] and [DisplayPort4 [SLOT2]] can be selected when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in <SLOT 2>.

[TOGGLE]	Switches the items in following order when the button is operated. [DisplayPort1 [SLOT1]] $\rightarrow$ [DisplayPort2 [SLOT1]] $\rightarrow$ [DisplayPort3 [SLOT2]] $\rightarrow$ [DisplayPort4 [SLOT2]]	
[DisplayPort1 [SLOT1]]	Fixes to selection operation of the DisplayPort1 input of the Interface Board.	
[DisplayPort2 [SLOT1]]	Fixes to selection operation of the DisplayPort2 input of the Interface Board.	
[DisplayPort3 [SLOT2]]	Fixes to selection operation of the DisplayPort3 input of the Interface Board.	

[DisplayPort4 [SLOT2]]	Fixes to selection operation of the DisplayPort4 input of the Interface Board.	
[DISABLE]	Disables button operations.	

# [SDI BUTTON]

The items from [SDI1 [SLOT1]] to [SDI4 [SLOT1]] can be selected when the optional Interface Board with the corresponding input (3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or Interface Board for 12G-SDI (Model No.: ET-MDN12G10)) is installed in <SLOT 1>.

The items from [SDI1 [SLOT2]] to [SDI4 [SLOT2]] can be selected when the optional Interface Board with the corresponding input (3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or Interface Board for 12G-SDI (Model No.: ET-MDN12G10)) is installed in <SLOT 2>.

[TOGGLE]	Switches the SDI input equipped on the projector as standard and the SDI input on the optional Interface Boards installed in <slot 1=""> and <slot 2=""> in turn when the button is operated.</slot></slot>			
[SDI1]	Fixes to selection operation of the SDI1 input.			
[SDI2]	Fixes to selection operation of the SDI2 input.			
[SDI3]	Fixes to selection operation of the SDI3 input.			
[SDI4]	Fixes to selection operation of the SDI4 input.			
[SDI1 [SLOT1]]	Fixes to selection operation of the SDI1 input of the Interface Board.			
[SDI2 [SLOT1]]	Fixes to selection operation of the SDI2 input of the Interface Board.			
[SDI3 [SLOT1]]	Fixes to selection operation of the SDI3 input of the Interface Board.			
[SDI4 [SLOT1]]	Fixes to selection operation of the SDI4 input of the Interface Board.			
[SDI1 [SLOT2]]	Fixes to selection operation of the SDI1 input of the Interface Board.			
[SDI2 [SLOT2]]	Fixes to selection operation of the SDI2 input of the Interface Board.			
[SDI3 [SLOT2]]	Fixes to selection operation of the SDI3 input of the Interface Board.			
[SDI4 [SLOT2]]	Fixes to selection operation of the SDI4 input of the Interface Board.			
[DISABLE]	Disables button operations.			

# [SLOT1 BUTTON]

The items from [SDI1 [SLOT1]] to [SDI4 [SLOT1]] can be selected when the optional Interface Board with the corresponding input (3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or Interface Board for 12G-SDI (Model No.: ET-MDN12G10)) is installed in <SLOT 1>.

[HDMI1 [SLOT1]] and [HDMI2 [SLOT1]] can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in <SLOT 1>.

[DVI-D1 [SLOT1]] and [DVI-D2 [SLOT1]] can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in <SLOT 1>.

[DisplayPort1 [SLOT1]] and [DisplayPort2 [SLOT1]] can be selected when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in <SLOT 1>.

r				
[TOGGLE]	Switches the input of the Interface Board installed in <slot 1=""> in turn when the button is operated.</slot>			
[SDI1 [SLOT1]]	ixes to selection operation of the SDI1 input of the Interface Board.			
[SDI2 [SLOT1]]	Fixes to selection operation of the SDI2 input of the Interface Board.			
[SDI3 [SLOT1]]	Fixes to selection operation of the SDI3 input of the Interface Board.			
[SDI4 [SLOT1]]	Fixes to selection operation of the SDI4 input of the Interface Board.			
[HDMI1 [SLOT1]]	Fixes to selection operation of the HDMI1 input of the Interface Board.			
[HDMI2 [SLOT1]]	Fixes to selection operation of the HDMI2 input of the Interface Board.			
[DVI-D1 [SLOT1]]	Fixes to selection operation of the DVI-D1 input of the Interface Board.			
[DVI-D2 [SLOT1]]	Fixes to selection operation of the DVI-D2 input of the Interface Board.			
[DisplayPort1 [SLOT1]]	Fixes to selection operation of the DisplayPort1 input of the Interface Board.			
[DisplayPort2 [SLOT1]]	Fixes to selection operation of the DisplayPort2 input of the Interface Board.			
[DISABLE]	Disables button operations.			

# [SLOT2 BUTTON]

The items from [SDI1 [SLOT2]] to [SDI4 [SLOT2]] can be selected when the optional Interface Board with the corresponding input (3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or Interface Board for 12G-SDI (Model No.: ET-MDN12G10)) is installed in <SLOT 2>.

[HDMI3 [SLOT2]] and [HDMI4 [SLOT2]] can be selected when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in <SLOT 2>.

[DVI-D3 [SLOT2]] and [DVI-D4 [SLOT2]] can be selected when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in <SLOT 2>.

[DisplayPort3 [SLOT2]] and [DisplayPort4 [SLOT2]] can be selected when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in <SLOT 2>.

[TOGGLE]	Switches the input of the Interface Board installed in <slot 2=""> in turn when the button is operated.</slot>			
[SDI1 [SLOT2]]	Fixes to selection operation of the SDI1 input of the Interface Board.			
[SDI2 [SLOT2]]	Fixes to selection operation of the SDI2 input of the Interface Board.			
[SDI3 [SLOT2]]	Fixes to selection operation of the SDI3 input of the Interface Board.			
[SDI4 [SLOT2]]	Fixes to selection operation of the SDI4 input of the Interface Board.			
[HDMI3 [SLOT2]]	Fixes to selection operation of the HDMI3 input of the Interface Board.			
[HDMI4 [SLOT2]]	Fixes to selection operation of the HDMI4 input of the Interface Board.			
[DVI-D3 [SLOT2]]	Fixes to selection operation of the DVI-D3 input of the Interface Board.			
[DVI-D4 [SLOT2]]	Fixes to selection operation of the DVI-D4 input of the Interface Board.			
[DisplayPort3 [SLOT2]]	Fixes to selection operation of the DisplayPort3 input of the Interface Board.			
[DisplayPort4 [SLOT2]]	Fixes to selection operation of the DisplayPort4 input of the Interface Board.			
[DISABLE]	Disables button operations.			

# [CONTROL DEVICE PASSWORD CHANGE]

The control device password can be changed.

- 1) Press ▲▼ to select [CONTROL DEVICE PASSWORD CHANGE].
- 2) Press the <ENTER> button.
  - The [CONTROL DEVICE PASSWORD CHANGE] screen is displayed.
- 3) Press  $\blacktriangle \lor \blacklozenge \lor \blacklozenge$  to select the text, and press the <ENTER> button to enter the text.
- 4) Press ▲▼◀▶ to select [OK], and press the <ENTER> button.
  - To cancel, select [CANCEL].

### Attention

• The initial password is "AAAA" by the factory default or when [ALL USER DATA] in [INITIALIZE] (+ page 181) is executed.

• Change the password periodically that is hard to guess.

# [NETWORK] menu

On the menu screen, select [NETWORK] from the main menu, and select an item from the sub-menu. Refer to "Navigating through the menu" (➡ page 88) for the operation of the menu screen.

# [DIGITAL LINK MODE]

Switch the communication method of the <DIGITAL LINK/LAN> terminal of the projector.

### 1) Press ▲▼ to select [DIGITAL LINK MODE].

### 2) Press **♦** to switch the item.

• The items will switch each time you press the button.

[AUTO]	Switches the communication method automatically to DIGITAL LINK, long reach, or Ethernet.	
[DIGITAL LINK]	ixes the communication method to DIGITAL LINK.	
[LONG REACH]	Fixes the communication method to long reach.	
[ETHERNET]	Fixes the communication method to Ethernet.	

### Possible communication modes

: Communication possible

-: Communication not possible

Setting		Communication possible			
		Video transfer (100 m (328'1"))	Video transfer (150 m (492'2"))	Ethernet	RS-232C
	For DIGITAL LINK	1	—	1	1
[AUTO]	For long reach	—	1	1	1
	For Ethernet	—	—	<b>√</b> *1	—
[DIGITAL LINK]		1	—	✓	1
[LONG REACH]		_	1	$\checkmark$	1
[ETHERNET]		—	—	<b>√</b> *1	—

\*1 Communication via a twisted-pair-cable transmitter is not available. Connect the projector to the network directly.

### Note

- The maximum transmission distance when connected with the long-reach communication method is 150 m (492'2"). In this case, the signal
  that the projector can receive is only up to 1080/60p (1 920 x 1 080 dots, dot clock frequency 148.5 MHz).
- When the communication method of the twist-pair-cable transmitter is set to long reach, the projector will connect with long-reach communication method when [DIGITAL LINK MODE] is set to [AUTO]. To connect with the optional DIGITAL LINK Switcher (Model No.: ET-YFB200G) with the long-reach communication method, set [DIGITAL LINK MODE] to [LONG REACH].
- Connection will not be made correctly if the twist-pair-cable transmitter is not supporting the long-reach communication method even if [DIGITAL LINK MODE] is set to [LONG REACH].

# [DIGITAL LINK STATUS]

Display the DIGITAL LINK connection environment.

### 1) Press ▲▼ to select [DIGITAL LINK STATUS].

- 2) Press the <ENTER> button.
  - The [DIGITAL LINK STATUS] screen is displayed.

[LINK STATUS]	Either [NO LINK], [DIGITAL LINK], [LONG REACH], or [ETHERNET] is displayed.			
[HDCP STATUS]	Either [NO SIGNAL], [OFF], or [ON] is displayed.			
[SIGNAL QUALITY]	<ul> <li>[SIGNAL QUALITY] is a numerical value of the amount of error, and the display color changes to green, yellow, or red depending on that value.</li> <li>Check the signal quality level while receiving a signal from the twisted-pair-cable transmitter.</li> <li>[MAX]/[MIN]: Maximum/minimum value of the amount of error</li> <li>Green (-12 dB or lower) → normal signal quality level.</li> <li>Yellow (-11 to -8 dB) → caution level that noise may appear on the screen.</li> <li>Red (-7 dB or higher) → abnormal level with interrupted synchronization and receiving not possible.</li> </ul>			

# [NETWORK SETUP]

Perform the initial setting of the network before using the network function.

### 1) Press ▲▼ to select [NETWORK SETUP].

- 2) Press the <ENTER> button.
  - The [NETWORK SETUP] screen is displayed.
- 3) Press ▲▼ to select an item, and change the settings according to the operation instructions of the menu.

[PROJECTOR NAME]	Allows to change the projector name. Enter the host name if it is required to use a DHCP server.			
	[0N]	If a DHCP server exists in the network where the projector is to be connected, obtains the IP address automatically.		
[DHCP]	[OFF]	If a DHCP server does not exist in the network where the projector is to be connected, set [IP ADDRESS], [SUBNET MASK], and [DEFAULT GATEWAY].		
[IP ADDRESS]	Enter the IP address when a DHCP server is not used.			
[SUBNET MASK]	Enter the subnet mask when a DHCP server is not used.			
[DEFAULT GATEWAY]	Enter the default gateway address when a DHCP server is not used.			

4) Press ▲▼ to select [STORE], and press the <ENTER> button.

### 5) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.

### Note

- When using a DHCP server, confirm that the DHCP server is running.
- Consult your network administrator regarding the IP address, subnet mask, and default gateway.
- When [Art-Net SETUP] is set to [ON(2.X.X.X)] or [ON(10.X.X.X)], [NETWORK SETUP] cannot be selected.

# [NETWORK CONTROL]

Set up the control method of the network.

### 1) Press ▲▼ to select [NETWORK CONTROL].

- 2) Press the <ENTER> button.
  - The [NETWORK CONTROL] screen is displayed.
- 3) Press ▲▼ to select an item, and press ◀▶ to change the setting.

[WEB CONTROL]	Set to [ON] to control with the web browser.			
[PJLink CONTROL]	Set to [ON] to control with the PJLink protocol.			
[COMMAND CONTROL]	Set to [ON] to control with the <serial in="">/<serial out=""> terminal control command format → page 252). Refer to "Control commands via LAN" (→ page 246).</serial></serial>			
[COMMAND PORT]	et the port number used for command control.			
[Crestron Connected(TM)]	Set to [ON] to control with Crestron Connected™ of Crestron Electronics, Inc.			
[AMX D.D.]	Set to [ON] to control with the controller of AMX Corporation. Setting this function to [ON] enables detection through "AMX Device Discovery". For details, visit the website of AMX Corporation. URL http://www.amx.com/			
Image: Construct of the state of t				

- 4) Press ▲▼ to select [STORE], and press the <ENTER> button.
- 5) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<**ENTER> button.

# [NETWORK STATUS]

Display the status of the projector network.

### 1) Press ▲▼ to select [NETWORK STATUS].

- 2) Press the <ENTER> button.
  - The [NETWORK STATUS] screen is displayed.

[DHCP]	Displays the status of use of the DHCP server.		
[IP ADDRESS]	splays the [IP ADDRESS].		
[SUBNET MASK]	plays the [SUBNET MASK].		
[DEFAULT GATEWAY]	splays the [DEFAULT GATEWAY].		
[DNS1]	isplays the address of the preferred DNS server.		
[DNS2]	Displays the address of the alternate DNS server.		
[MAC ADDRESS]	Displays the [MAC ADDRESS].		

# [DIGITAL LINK MENU]

When the optional DIGITAL LINK output supported device (Model No.: ET-YFB100G, ET-YFB200G) is connected to the <DIGITAL LINK/LAN> terminal, the main menu of the connected DIGITAL LINK output supported device is displayed. Refer to the Operating Instructions of the DIGITAL LINK output supported device for details.

### Note

- [DIGITAL LINK MENU] cannot be selected when [EXTRON XTP] is set to [ON].
- The operation guidance for the "RETURN" button is in the menu screen of the Digital Interface Box and DIGITAL LINK Switcher. The projector does not have the "RETURN" button, but the same operation is available with the <MENU> button.

# [Art-Net SETUP]

Make settings to use the Art-Net function.

### 1) Press ▲▼ to select [Art-Net SETUP].

### 2) Press $\triangleleft$ to switch the item.

• The items will switch each time you press the button.

[OFF]	sables the Art-Net function.		
[ON(2.X.X.X)]	ables the Art-Net function and sets the IP address to 2.X.X.X.		
[ON(10.X.X.X)] Enables the Art-Net function and sets the IP address to 10.X.X.X.			
[ON(MANUAL)]	Enables the Art-Net function and uses the IP address set in [NETWORK SETUP].		

• When other than [OFF] is selected, proceed to Step 3).

### 3) Press the <ENTER> button.

• The [Art-Net SETUP] screen is displayed.

### 4) Press $\blacktriangle \lor$ to select an item, and press $\blacklozenge \lor$ to switch the setting.

[NET]	nter [NET] to be used when the projector processes Art-Net.		
[SUB NET]	ter [SUB NET] to be used when the projector processes Art-Net.		
[UNIVERSE]	nter [UNIVERSE] to be used when the projector processes Art-Net.		
[START ADDRESS] Enter [START ADDRESS] to be used when the projector processes Art-Net.			

### 5) Press ▲▼ to select [STORE], and press the <ENTER> button.

### 6) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.

### Note

• If [ON(2.X.X.X)] or [ON(10.X.X.X)] is selected, IP address is calculated and set automatically.

# [Art-Net CHANNEL SETTING]

Set the assignment of the channel.

For the channel definitions used for controlling the projector with the Art-Net function, refer to "Using Art-Net function" (➡ page 240).

### 1) Press ▲▼ to select [Art-Net CHANNEL SETTING].

### 2) Press **I** to switch the item.

• The items will switch each time you press the button.

[2]	Jses the channel assignment in standard setting.			
<b>[3]</b> *1	ses the channel assignment with the setting that can numerically control the lens position.			
[USER]	Changes the channel assignment.			
[1]	Uses the channel assignment with DZ21K series compatible. DZ21K series: DZ21K series, DS20K series, DW17K series, DZ16K series			

\*1 This item can be set in following cases.

When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

- When anything other than [USER] is selected, the function assigned to the channel is displayed by pressing the <ENTER> button.
- When [USER] is selected, proceed to Step 3).

### 3) Press the <ENTER> button.

• The [Art-Net CHANNEL SETTING] screen is displayed.

### 4) Press $\blacktriangle \forall$ to select the channel to set, and press $\blacklozenge \flat$ to switch the item.

[LIGHT OUTPUT]	Adjusts the amount of light.				
[INPUT SELECT]	Switches the input.				
[LENS POSITION]	Moves the lens position.				
[LENS H SHIFT]	Adjusts the lens shift in the horizontal direction.				
[LENS V SHIFT]	Adjusts the lens shift in the vertical direction.				
[LENS FOCUS]	djusts the focus.				
[LENS ZOOM]	Adjusts the zoom.				
[POWER]	Controls the power status.				
[SHUTTER]	Controls the shutter.				
[FADE-IN]	Sets the fade-in time.				
[FADE-OUT]	Sets the fade-out time.				
[GEOMETRY]	Performs geometric adjustment.				
[CUSTOM MASKING]	erforms geometric adjustment using a computer. to use PC-1, PC-2, and PC-3, the optional Upgrade Kit (Model No.: ET-UK20) is required.				
[FREEZE]	Freezes the projected image.				
[COLOR]	Adjusts the color saturation.				
[TINT]	Adjusts the tint.				
[RASTER PATTERN]	Displays the raster pattern.				
[LENS H SHIFT MSB]*1	Coarsely adjusts the horizontal position of the lens.				
[LENS H SHIFT LSB] <sup>*1</sup>	Finely adjusts the horizontal position of the lens.				
[LENS V SHIFT MSB]*1	Coarsely adjusts the vertical position of the lens.				
[LENS V SHIFT LSB]*1	Finely adjusts the vertical position of the lens.				
[LENS FOCUS MSB]*1	Coarsely adjusts the focus position of the lens.				
[LENS FOCUS LSB]*1	Finely adjusts the focus position of the lens.				
[LENS ZOOM MSB]*1	Coarsely adjusts the zoom position of the lens.				
[LENS ZOOM LSB]*1	Finely adjusts the zoom position of the lens.				
[ENABLE/DISABLE]	Enables/disables the control of the projector with the Art-Net function.				
[NONE]	No definition				

\*1 These items can be selected in following case.

When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

The setting can be also made by pressing ▲▼ to select the channel, pressing the <ENTER> button to display the item list, pressing ▲▼◀▶ to select the item, and pressing the <ENTER> button.

• Same item cannot be set for multiple channels, except for [NONE].

### Note

- Assign each item of [LENS H SHIFT MSB], [LENS V SHIFT MSB], [LENS FOCUS MSB], and [LENS ZOOM MSB] to a channel together with [LENS H SHIFT LSB], [LENS V SHIFT LSB], [LENS FOCUS LSB], and [LENS ZOOM LSB]. These cannot be used when assigned to a channel by itself.
- Assign each item of [LENS H SHIFT LSB], [LENS V SHIFT LSB], [LENS FOCUS LSB], and [LENS ZOOM LSB] to a channel together with [LENS H SHIFT MSB], [LENS V SHIFT MSB], [LENS FOCUS MSB], and [LENS ZOOM MSB]. These cannot be used when assigned to a channel by itself.
- MSB: <u>Most</u> Significant Byte
- LSB: Least Significant Byte

# [Art-Net STATUS]

Display the content of control assigned to each channel and the received data of that channel.

- 1) Press ▲▼ to select [Art-Net STATUS].
- 2) Press the <ENTER> button.
  - The [Art-Net STATUS] screen is displayed.

# Chapter 5 **Operations**

This chapter describes how to use each function.

200 - ENGLISH

# **Network connection**

The projector is equipped with the network function, and following is possible by connecting to a computer.

### Web control

Setting, adjustment, and displaying status of the projector are possible by accessing the projector from a computer.

Refer to "Web control function" (→ page 204) for details.

### Smart Projector Control

The application software "Smart Projector Control" can be used, which enables to set and adjust the projector connected via LAN using a smartphone or tablet device.

Visit the Panasonic website (https://panasonic.net/cns/projector/) for details.

### Multi Monitoring & Control Software

"Multi Monitoring & Control Software", which is a software application to monitor and control multiple display devices (projector or flat panel display) connected via LAN, can be used.

Refer to the Operating Instructions of the "Multi Monitoring & Control Software" in the supplied CD-ROM for details.

### • Early Warning Software

"Early Warning Software", which is a software application to monitor the status of the display devices (projector or flat panel display) or the peripheral device within the intranet, and to notify the problem or to detect the sign of possible problem of the device, can be used.

Visit the Panasonic website (https://panasonic.net/cns/projector/pass/) for details.

### PJLink

Operation or status query of the projector can be performed from a computer using the PJLink protocol. Refer to "PJLink protocol" (
page 239) for details.

### Art-Net

Setting of the projector can be operated by the DMX controller or application software using the Art-Net protocol. Refer to "Using Art-Net function" (+ page 240) for details.


### Command control

Operation or status query of the projector can be performed from a computer using the control command. Refer to "Control commands via LAN" ( page 246) for details.

# Connecting to the network

This projector can receive the Ethernet signal from the twisted-pair-cable transmitter via the LAN cable.

# Example of a normal network connection



### Attention

• When a LAN cable is directly connected to the projector, the network connection must be made indoors.


### Note

• A LAN cable is required to use the network function.

<sup>•</sup> Use a straight or crossover LAN cable that is compatible with CAT5 or higher. Either the straight or the crossover cable, or both cables can be used depending on the system configuration. Consult your network administrator. The projector will determine the type of the cable (straight or crossover) automatically.

• Use a LAN cable of 100 m (328'1") or shorter.

### Example of network connections via a twisted-pair-cable transmitter



### Attention

When a LAN cable is directly connected to the projector, the network connection must be made indoors.

### Note

• For the LAN cable between the twisted-pair-cable transmitter and the projector, use a cable that meets the following criteria:

- Conforming to CAT5e or higher standards
- Shielded type (including connectors)
- Straight-through
- Single wire
- The maximum transmission distance between the twisted-pair-cable transmitter and the projector is 100 m (328'1") for the signal with resolution of 1 920 x 1 200 dots or less. It is possible to transmit up to 150 m (492'2") if the twisted-pair-cable transmitter supports the long-reach communication method. However, the signal that the projector can receive is only up to 1080/60p (1 920 x 1 080 dots, dot clock frequency 148.5 MHz) for the long-reach communication method. For the signal with the resolution exceeding 1 920 x 1 200 dots, the maximum transmission distance will be 50 m (164'1"). If these distances are exceeded, image may be disrupted or a malfunction may occur in LAN communication.
- When laying cables between the twisted-pair-cable transmitter and the projector, confirm that cable characteristics are compatible with CAT5e or higher using tools such as a cable tester or cable analyzer.
- When a relay connector is used, include it in the measurement.
- Do not use a hub between the twisted-pair-cable transmitter and the projector.
- Do not pull cables forcefully. Also, do not bend or fold cables unnecessarily.
- To reduce the effects of noise as much as possible, stretch out the cables between the twisted-pair-cable transmitter and the projector without any loops.
- Lay the cables between the twisted-pair-cable transmitter and the projector away from other cables, particularly power cables.
- When laying multiple cables, run them side by side along the shortest distance possible without bundling them together.
- After laying the cables, go to the [NETWORK] menu → [DIGITAL LINK STATUS] and confirm that the value of [SIGNAL QUALITY] is displayed in green which indicates normal quality.
- For twisted-pair-cable transmitters of other manufacturers of which the operation has been verified with the projector, visit the Panasonic website (https://panasonic.net/cns/projector/). Note that the verification for devices of other manufacturers has been made for the items set by Panasonic Corporation, and not all the operations have been verified. For operation or performance problems caused by the devices of other manufacturers, contact the respective manufacturers.

# Setting the projector

- 1) Connect the projector to a computer using a LAN cable.
- 2) Turn on the power of the projector.
- 3) Press the <MENU> button to open the [NETWORK] menu, select [NETWORK SETUP], and press the <ENTER> button.

### 4) Perform the [NETWORK SETUP] setting.

• Refer to [NETWORK SETUP] (→ page 196) for details.

### Note

To connect to an existing network, perform after consulting your network administrator.

# Factory default setting

• Following setting has been made as a factory default.

[DHCP]	OFF
[IP ADDRESS]	192.168.0.8
[SUBNET MASK]	255.255.255.0
[DEFAULT GATEWAY]	192.168.0.1
[DNS1]/[DNS2]	None

### Operating the computer

### 1) Turn on the power of the computer.

### 2) Perform the network setting following the instruction of your network administrator.

• Operation from the computer is possible by configuring the network setting of the computer as follows if the projector is in the factory default setting.

[IP ADDRESS]	192.168.0.10
[SUBNET MASK]	255.255.255.0
[DEFAULT GATEWAY]	192.168.0.1

# Web control function

Following operation is possible from a computer using the web control function.

- Setting and adjustment of the projector
- Display of the projector status
- · Sending E-mail messages when there is a problem with the projector

The projector supports "Crestron Connected<sup>™</sup>", and the following application software of Crestron Electronics, Inc. can be used.

- RoomView Express
- Fusion RV
- RoomView Server Edition

### Note

- Communication with an E-mail server is required to use the E-mail function. Confirm that the E-mail can be used beforehand.
- "Crestron Connected™" is a system of Crestron Electronics, Inc. that collectively manages and controls devices on multiple systems connected to a network using a computer.
- For details of the "Crestron Connected<sup>TM</sup>", visit the website of Crestron Electronics, Inc. (English only.) URL http://www.crestron.com
   Download "RoomView Express" from the Crestron Electronics, Inc. website. (English only.)
   URL http://www.crestron.com/getroomview

# Computer that can be used for setting

To use the web control function, a web browser is required. Confirm that the web browser can be used in advance.

OS	Compatible browser		
Windows	Internet Explorer 11.0, Microsoft Edge		
Mac OS	Safari 6.0/7.0/8.0/9.0		
iOS	Safari (version equipped with iOS 9 and iOS 10)		

# Accessing from the web browser

- 1) Start up the web browser on the computer.
- 2) Enter the IP address set on the projector into the URL entry field of the web browser.
- 3) Enter the user name and the password.
  - The factory default setting of the user name is user1 (user rights)/admin1 (administrator rights) and the password is panasonic (lower case).

Microsoft Edge				
Microsoft Edge				
The server 192.168.0.8 is asking for your user name and password. The server reports that it is from NAME1234.				
Warning: Your user name and password will be sent using basic that isn't secure.	c authentication on a connection			
R				
User name				
Password	l			
	OK Cancel			

### 4) Click OK.

• The [Projector status] page is displayed.

Projector control windo	× +					- 0	×
$\leftarrow \ \rightarrow \ \heartsuit \ \mid$	← → Ů   192.168.0.10/cgi-bin/main.cgi?page=MENU_STATUS86ang=e				□ ☆   =	Z O	
Projector Cont	rol Window						
Status	Projector status Netwo	rk statas Aco	ns error log Mail erroe	log			
Projector	PROJECTOR TYPE	RQ32K	SERIAL NUMBER	123456789012			
control	MAIN VERSION	1.00					
	POWER	<b>ON</b> STANDBY	REMOTE2 STATUS	ENABLE DISABLE			
Detailed set up	SHUTTER	CLOSE OPEN	OSD				
	OPERATING MODE	NORMAL	AC VOLTAGE	203 V			
Change password	MAX LIGHT OUTPUT LEVE		LIGHT OUTPUT	8.0 %			
passworu	INPUT		SDI1 (kHz/Hz)				
Crestron	INTAKE AIR TEMPERATUR	æ	26°C / 78°F				
Connected (114)	OPTICS MODULE TEMPER.		28°C / \$2°F				
	EXHAUST AIR TEMPERATU	URE	28°C/\$2°F				
	LIGHTIRUNTIME		5 H				
Japanese	LIGHT1-B O	N OFF	28°C / 82°F				
	LIGHT1-S O	N OFF	28°C / 82°F				
	LIGHT2RUNTIME		5 H				
	LIGHT2-B O	N OFF	29°C / \$4°F				
	LIGHT2-S O	N OFF	28°C / \$2°F				
	PROJECTOR RUNTIME	4 H	SELF TEST				

### Note

- If you use a web browser to control the projector, set the [NETWORK] menu → [NETWORK CONTROL] → [WEB CONTROL] to [ON].
- Do not perform setting or control simultaneously by starting up multiple web browsers. Do not set or control the projector from multiple computers.
- Change the password first. ( page 217)
- Access will be locked for few minutes when an incorrect password is entered three times consecutively.
- Some items on the projector setting page use the Javascript function of the web browser. Correct control may not be possible when the web browser is set not to use this function.
- If the screen for the web control is not displayed, consult your network administrator.
- While updating the screen for the web control, the screen may appear white for a moment, but it is not a malfunction.
- Screenshot of a computer

The size or the display of the screen may be different from this manual depending on the OS or the web browser, or the type of computer in use.


### Rights for each account

The administrator rights allow use of all functions. There is a limitation in the rights that can be used with the user rights. Select the rights depending on the purpose.

The function that has  $\checkmark$  in the administrator rights/user rights column indicates that it can be operated with that rights.

Item	Function	Administrator rights	User rights	Page
	[Projector status]	1	1	206
	Error information page	✓	1	207
[Status]	[Network status]	✓	1	207
	[Access error log]	✓	—	207
	[Mail error log]	✓	—	208
[Projector control]	[Basic control]	1	1	208
[Projector control]	[Detail control]	1	—	209
	[Network config]	1	—	211
	[Adjust clock]	1	—	212
[Detailed set up]	[Ping test]	1	—	212
	[E-mail set up]	1	—	213
	[Authentication set up]	1	—	214
	User name of [Administrator]	1	—	217
	User name of [User]	✓	—	218
[Change password]	Password of [Administrator]	✓	—	217
	Password of [User]	1	$\checkmark$	218, 218
	Operation page	1	_	219
	[Tools]	1	_	219
[Crestron Connected(TM)]	[Info]		_	220
	[Help]	1	_	220

## **Descriptions of items**



### 1 Page tab

Switches pages by clicking this item.

- **2** [Status] The status of the projector is displayed by clicking this item. **3** [Projector control]
- 3 [Projector control] The [Projector control] page is displayed by clicking this item.
- 4 [Detailed set up]


The [Detailed set up] page is displayed by clicking this item.

- 5 [Change password] The [Change password] page is displayed by clicking this item.
- 6 [Crestron Connected(TM)] The operation page of Crestron Connected™ is displayed by clicking this item.

### [Projector status] page

# Click [Status] $\rightarrow$ [Projector status].

Display the status of the projector for the following items.



### 1 [PROJECTOR TYPE]

Displays the type of the projector.

### 2 [MAIN VERSION]

Displays the firmware version of the projector.

### 3 [POWER]

Displays the status of the power.

### 4 [SHUTTER]

Displays the status of the shutter. ([CLOSE]: Shutter function enabled; [OPEN]: Shutter function disabled)

### 5 [OPERATING MODE] Displays the setting status of [OPERATING MODE].

6 [MAX LIGHT OUTPUT LEVEL] Displays the setting status of [MAX LIGHT OUTPUT LEVEL].

# 7 [SERIAL NUMBER]

Displays the serial number of the projector.

# 8 [REMOTE2 STATUS]

Displays the control status of the <REMOTE 2 IN> terminal. 9 [OSD]

Displays the status of on-screen display function. ([ON]: Display; [OFF]: Hide)

# 10 [AC VOLTAGE]

Displays the input supply voltage. 11 [LIGHT OUTPUT]

Displays the setting status of [LIGHT OUTPUT].

### 12 [INPUT]

Displays the status of the selected input.

13 [INTAKE AIR TEMPERATURE] Displays the status of the intake air temperature of the projector.


- 14 [OPTICS MODULE TEMPERATURE] Displays the status of the internal temperature of the projector.
- 15 [EXHAUST AIR TEMPERATURE] Displays the status of the exhaust air temperature of the projector.
- 16 [LIGHT1RUNTIME] Displays the runtime of light source 1.
- 17 [LIGHT1-B], [LIGHT1-S] Displays the lighting status and temperature status of light source 1.
- 18 [LIGHT2RUNTIME] Displays the runtime of light source 2.
- **19 [LIGHT2-B], [LIGHT2-S]** Displays the lighting status and temperature status of light source 2.
- 20 [SELF TEST] Displays the self-diagnosis information.
- 21 [PROJECTOR RUNTIME] Displays the runtime of the projector.

206 - ENGLISH

### Error information page

When [Error (Detail)] or [Warning (Detail)] is displayed in the [SELF TEST] display field of the **[Projector status]** screen, click it to display the content of the error/warning.

The projector may go into the standby status to protect the projector depending on the contents of the error.




Displays the alphanumeric symbols and content of errors/ warnings that occur. Refer to "Self-diagnosis display" (> page 235) for the display details.

### [Network status] page

Click [Status]  $\rightarrow$  [Network status].

The current network setting status is displayed.



### [Access error log] page

Click [Status]  $\rightarrow$  [Access error log].


The error log on the web server is displayed such as access to the pages that do not exist or access with unauthorized user names or passwords.

Projector control windo	× +			-	0	×
$\leftarrow \  \  \rightarrow \  \   \mho \  \    $	192.168.0.8 (kgi bin/main.ogi/page=ERR_LOG8dang=e	□ ☆	=	$\mathbb{N}$	۵	
Projector Con	trol Window					
	Projector status Network status Access error log Mail error log					
Projector control	Web server error log					
Detailed set up	(See Her 12 13:47:35 2004)[error][clisen: 192.165.0.103]Forbidden: */ [See Her 12 13:47:39 2014][error][clisen: 192.165.0.103]Forbidden: */					
Change password						
Crestron Connected (TM)						
Japanese						

# [Mail error log] page

Click [Status] → [Mail error log].

E-mail error log is displayed if periodic E-mail sending has failed.



### Note

- [Access error log] and [Mail error log] display the recent few thousand accesses/requests. All information may not be displayed when many accesses/requests are made at once.
- . Logs in [Access error log] and [Mail error log] are deleted from the oldest when exceeding a certain amount.
- · Check [Access error log] and [Mail error log] periodically.

### [Basic control] page

Click [Projector control]  $\rightarrow$  [Basic control].



### 1 [POWER]

Turns off/on the power.

2 [SHUTTER]

Switches the status of the shutter. ([CLOSE]: Shutter function enabled; [OPEN]: Shutter function disabled)

3 [OSD]

Switches the status of the on-screen display function. ([OFF]: Hide; [ON]: Display)

### 4 [SYSTEM]

Switches the system method.

#### 5 On-screen display of the projector

Displays the same items as shown on the on-screen display of the projector. You can check or change the settings of the menus. It is displayed even if the on-screen display function is set to off (hide).

### 6 [INPUT SELECT]

Switches the input of the image to project. The display content for the input selection button varies depending on the optional Interface Board installed in the slot.

# [Detail control] page

Click [Projector control]  $\rightarrow$  [Detail control].



### 1 [MULTI DISPLAY MODE]

Switches the setting of the multi-display mode.

2 Control of the projector

The projector is controlled by clicking the buttons in the same way as the buttons on the remote control. After control, the onscreen display of the projector at the right of the control page is updated.

- 3 [SUB MEMORY] Switches the sub memory.
- 4 [SYSTEM DAYLIGHT VIEW] Switches to system daylight view settings.
- 5 [FREEZE] Temporarily pauses the image.

6 [WAVEFORM MONITOR]

Displays the waveform of the input signal.

- 7 [PROJECTION METHOD]
  - Switches the setting of the projection method.
- 8 [LENS]

Displays the [LENS] page.

9 [TEST PATTERN]

Displays the test pattern.

Click the test pattern to display in the projected image from the patters displayed on the right side of the control page. The display of the test pattern disappears if [Exit] is clicked.

10 [GET OSD]

Updates the on-screen display of the projector at the right of the control page.

# [LENS] page

Click [Projector control]  $\rightarrow$  [Detail control]  $\rightarrow$  [LENS].



### 1 [SET POSITION]

The lens position setting page is displayed.

### 2 [HOME POSITION]

Moves the projection lens to the home position.

3 [SHIFT]

Click ▲▼◀▶ to adjust the lens shift (vertical position and horizontal position).

The adjustment can be performed faster by holding down the button for approximately three seconds or longer.

### 4 [FOCUS]

### Press ◀▶ to adjust the focus.

The adjustment can be performed faster by holding down the button for approximately six seconds or longer.

5 [ZOOM]

Click  $\triangleleft$  to adjust the zoom.

### 6 [LENS MEMORY SAVE]

Saves the current lens position (vertical position, horizontal position, focus position, and zoom position). Click the number of the lens memory to save.

### 7 [LENS MEMORY LOAD]


Loads the lens position (vertical position, horizontal position, focus position, and zoom position). Click the number of the lens memory to load.

### 8 [Back]

Returns to the [Detail control] page.

### Lens position setting page

Click [Projector control]  $\rightarrow$  [Detail control]  $\rightarrow$  [LENS]  $\rightarrow$  [SET POSITION].



### 1 [Get]

Acquires the current lens position and displays the acquired values in the lens position information field.

2 Lens position information field Enter the lens position (vertical position, horizontal position, focus position, and zoom position).

### 3 [Apply]

Moves to the lens position displayed in the lens position information field.

4 [Back] Returns to the [LENS] page.

# Note


• The zoom position is displayed in the lens position information field only in following case.

When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

# [Network config] page

Click [Detailed set up]  $\rightarrow$  [Network config].

- Click [Network config] to display the [CAUTION!] screen.
- Click the [Next] button to display the current settings.
- Click the [Change] button to display the setting change screen.



- 1 [PROJECTOR NAME] Enter the name of the projector. Enter the host name if it is required when using a DHCP server etc.
- [DHCP ON], [DHCP OFF] To enable the DHCP client function, set to [DHCP ON].
   [IP ADDRESS]

Enter the IP address when not using a DHCP server.

4 [SUBNET MASK] Enter the subnet mask when not using a DHCP server.

5 [DEFAULT GATEWAY]

Enter the default gateway address when not using a DHCP server.

6 [DNS1]

Enter the DNS1 server address. Permissible characters for the entry of DNS1 server address (primary): Numbers (0 - 9), period (.) (Example: 192.168.0.253)

### 7 [DNS2]

Enter the DNS2 server address. Available characters for the entry of DNS2 server address (secondary): Numbers (0 - 9), period (.) (Example: 192.168.0.254)

8 [Back], [Next]


Click the [Back] button to return to the original screen. Click the [Next] button to display the setting confirmation screen. Click the [Submit] button to update the setting.

### Note

- When you use the "Forward" and "Back" functions of your browser, a warning message "Page has Expired" may appear. In that case, click [Network config] again since the following operation will not be guaranteed.
- Changing LAN settings while connected to the LAN may cause the connection to cut out.

# [Adjust clock] page

Click [Detailed set up]  $\rightarrow$  [Adjust clock].



5

6

7

[Date]

[Time]

[Submit]

Enter the date to be changed.

Enter the time to be changed.

Updates the date and time settings.

- 1 [Time Zone] Select the time zone.
- 2 [Set time zone] Updates the time zone setting.
- 3 [NTP SYNCHRONIZATION] Set to [ON] when setting the date and time automatically.

### 4 [NTP SERVER NAME] Enter the IP address or server name of the NTP server when you set to adjust the date and time manually. (To enter the server name, the DNS server needs to be set up.)


### Note

• The replacement of the battery inside the projector is required when the time goes out of alignment right after correcting the time. Consult your dealer.

# [Ping test] page

Check whether the network is connected to the E-mail server, POP server, DNS server, etc.

Click [Detailed set up]  $\rightarrow$  [Ping test].



1 [Input IP address] Enter the IP address of the server to be tested.

2 [Submit]


Executes the connection test.

3 Example of display when the connection has succeeded

4 Example of display when the connection has failed

# [E-mail set up] page

Send an E-mail to preset E-mail addresses (up to two addresses) when a problem has occurred. Click [Detailed set up]  $\rightarrow$  [E-mail set up].



### 1 [ENABLE]

Select [ENABLE] to use the E-mail function.

### 2 [SMTP SERVER NAME]


Enter the IP address or the server name of the E-mail server (SMTP). To enter the server name, the DNS server needs to be set up.

### 3 [MAIL FROM]

Enter the E-mail address of the projector. (Up to 63 characters in single byte)

### 4 [MEMO]

Enter information such as the location of the projector that notifies the sender of the E-mail. (Up to 63 characters in single byte)



### 7 [E-MAIL ADDRESS 1], [E-MAIL ADDRESS 2]


Enter the E-mail address to be sent. Leave [E-MAIL ADDRESS 2] blank when two E-mail addresses are not to be used.

### 5 [MINIMUM TIME]

Change the minimum interval for the temperature warning E-mail. The default value is 60 minutes. In this case, another E-mail will not be sent for 60 minutes after sending the temperature warning E-mail even if it reaches the warning temperature.

### 6 [INTAKE AIR TEMPERATURE]

Change the temperature setting for the temperature warning mail. A temperature warning E-mail is sent when the temperature exceeds this value.



8 Settings of the conditions to send E-mail Select the conditions to send E-mail.
[MAIL CONTENTS]: Select either [NORMAL] or [SIMPLE].
[ERROR]: Send an E-mail when an error occurred in the self-diagnosis.
[INTAKE AIR TEMPERATURE]: Send an E-mail when the intake air temperature has reached the value set at the above field.
[PERIODIC REPORT]:


Place a check mark on this to send an E-mail periodically. An E-mail will be sent on the day and time with the check mark.

### 9 [Submit]

Updates the settings and sends the details by E-mail.

## [Authentication set up] page

Set the authentication items when POP authentication or SMTP authentication is necessary to send an E-mail. Click [Detailed set up]  $\rightarrow$  [Authentication set up].



### 1 [Auth]

Select the authentication method specified by your Internet service provider.

### 2 [SMTP Auth] Set when the SMTP authentication is selected.

### 3 [POP server name]

Enter the POP server name. Allowed characters: Alphanumerics (A - Z, a - z, 0 - 9) Minus sign (-) and period (.)

### 4 [User name]

Enter the user name for the POP server or the SMTP server.

### 5 [Password]

Enter the password for the POP server or the SMTP server.

### 6 [SMTP server port] Enter the port number of the SMTP server.

(Normally 25)
7 [POP server port] Enter the port number of the POP server. (Normally 110)

8 [Submit] Update the settings.

### **Contents of E-mail sent**

### Example of the E-mail sent when E-mail is set

The following E-mail is sent when the E-mail settings have been established.

== Panasonic projector report(CONFIGURE) === : RQ32K : 123456789012 Projector Type Serial No E-mail setup data --TEMPERATURE WARNING SETUP MINIMUM TIME a at [ 60] minutes interval INTAKE AIR TEMPERATURE Over [46 degC / 114 degF ] [ OFF ] [ OFF ] ERROR INTAKE AIR TEMPERATURE PERIODIC REPORT Sunday [ON] Monday [ON] Tuesday [ON] Wednesday [ON] Thursday [ON] Friday [ON] Saturday [ON] 02:00 [ ON 06:00 [ ON 10:00 [ ON 14:00 [ ON 18:00 [ ON 22:00 [ ON 00:00 [ON] 01:00 [ON] 03:00 [ON] 
 00:00
 [ON]
 00:00
 [ON]
 02:00
 [ON]
 03:00
 [ON]

 08:00
 [ON]
 09:00
 [ON]
 06:00
 [ON]
 07:00
 [ON]

 08:00
 [ON]
 99:00
 [ON]
 10:00
 [ON]
 11:00
 [ON]

 12:00
 [ON]
 13:00
 [ON]
 14:00
 [ON]
 15:00
 [ON]

 16:00
 [ON]
 17:00
 [ON]
 18:00
 [ON]
 19:00
 [ON]

 20:00
 [ON]
 21:00
 [ON]
 22:00
 [ON]
 23:00
 [ON]
 ----- ERROR INFORMATION ----: 25 degC / 77 degF : 28 degC / 82 degF : 29 degC / 84 degF : 28 degC / 82 degE Intake air temperature Optics module temperature Exhaust air temperature Light1-B temperature Light1-S temperature Light2-B temperature Light2-S temperature : 28 degC / 82 degF PROJECTOR RUNTIME POWER ON 7 H 132 times LIGHT1 RUNTIME LIGHT1 ON 7 H 174 times LIGHT2 RUNTIME LIGHT2 ON 7 H 177 times ----- Current status ----MAIN VERSION 1.00 SUB VERSION LIGHT STATUS 1.00 LIGHT1-B=ON LIGHT1-S=ON LIGHT2-B=ON LIGHT2-S=ON SDI1 INPUT SIGNAL NAME ----kHz / ----Hz SIGNAL FREQUENCY ----KHZ / ---DISABLE REMOTE2 STATUS -- Wired Network configuration -ICP Client OFF DHCP Client 192.168.0.8 IP address MAC address 12:34:56:78:90:12 Mon Jan 01 12:34:56 20XX ----- Memo -----


## Example of the E-mail sent for an error

The following E-mail is sent when an error has occurred.

=== Panasonic projector re Projector Type Serial No	: RQ32K : 123456789012		
ERROR INFORMAT U21 Intake air temp. error			
Error code 00 00 00 00 00 00 00 00 00 00 00 00 00	0 00 00 00 00 00 00 00		
00 00 00 00 00 00 00 00 00 00 00 00 00			
Intake air temperature	: 25 degC / 7	7 dogE	
Optics module temperature			
Exhaust air temperature	: 28 degC / 82		
Light1-B temperature	: 28 degC / 82		
Light1-S temperature	: 28 degC / 82		
Light2-B temperature	: 29 degC / 84	1 degF	
Light2-S temperature	: 28 degC / 82	2 degF	
PROJECTOR RUNTIME	7 H		
POWER ON	132 times		
LIGHT1 RUNTIME	7 H		
LIGHT1 ON LIGHT2 RUNTIME	174 times 7 H		
LIGHT2 ON	177 times		
<b>A A A A</b>			
Current status MAIN VERSION	1.00		
SUB VERSION	1.00		
LIGHT STATUS	1.00		
LIGHT1-B=OFF LIGHT1-	S=OFF		
LIGHT2-B=OFF LIGHT2-	S=OFF		
INPUT	SDI1		
SIGNAL NAME			
SIGNAL FREQUENCY	kHz /Hz		
REMOTE2 STATUS	DISABLE		
Wired Network configu			
DHCP Client	OFF		
IP address	192.168.0.8		
MAC address	12:34:56:78:90:12		
Mon Jan 01 12:34:56 20XX			
Memo			

# [Change password] page

Click [Change password].



3

#### 1 [Administrator]


Used to change the setting of the [Administrator].

# [Next] Used to change the setting of the password.

2 [User]

Used to change the setting of the [User].

#### [Administrator] account



#### 1 [Account]

Displays the account to change.

#### 2 [Current]

[User name]: Enter the user name before the change. [Password]: Enter the current password. 3 [New]

**[User name]:** Enter the desired new user name. (Up to 16 characters in single byte)

#### [Password]:


Enter the desired new password. (Up to 16 characters in single byte)

[Password(Retype)]: Enter the desired new password again.

4 [OK]

Determines the change of password.

### [User] account



#### [Account] 1

Displays the account to change.


#### 2 [New]

[User name]:

Enter the desired new user name. (Up to 16 characters in single bvte) [Password]: Enter the desired new password. (Up to 16 characters in single byte) [Password(Retype)]: Enter the desired new password again.

#### [Change password] (For user rights)

Only the change of password is enabled under the user rights.



#### Note

byte)

1

2

• To change the account of the [Administrator], entry of [User name] and [Password] in [Current] is required.


# [Crestron Connected(TM)] page

The projector can be monitored/controlled with Crestron Connected™.


It is necessary to access with the administrator rights to start the operation screen of Crestron Connected™ from the web control screen. (The [Crestron Connected(TM)] button is not displayed in the web control screen with the user rights.)

The operation page of Crestron Connected<sup>™</sup> is displayed by clicking [Crestron Connected(TM)].

It is not displayed if Adobe® Flash® Player is not installed on your computer, or the browser you use does not support Flash. In such a case, click [Back] in the operation page to go back to the previous page.



#### **Operation page**



- 1 [Tools], [Info], [Help] Tabs for selecting the setting, information, or help page of the projector.
- 2 [POWER]

Turns on/off the power.

3 [SHUTTER]

Switches the status of the shutter. ([CLOSE]: Shutter function enabled; [OPEN]: Shutter function disabled)


- 4 [Input Select] Controls input selection. Not available when the power of the projector is turned off.
- 5 Menu screen control buttons Navigates the menu screen.
- 6 Freeze/image quality adjustment Controls items related to freeze/image quality.
- 7 [Back] Returns to the previous page.

#### Note

• When the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1> or <SLOT 2>, switching to the SDI2 input or the SDI4 input on the Interface Board for 12G-SDI is not possible by operating [Input Select].

#### [Tools] page

#### Click [Tools] in the operation page.



#### 1 [Control System]

Set the information required for communicating with the controller to be connected with the projector.

#### 2 [User Password]

Set the user rights password for the operation page of Crestron Connected  $^{\text{TM}}$ 

#### 3 [Admin Password]

Set the administrator rights password for the operation page of Crestron Connected<sup>TM</sup>.

#### 4 Network status


Displays the settings of wired LAN. [DHCP] Displays the current setting. [Ip Address] Displays the current setting. [Subnet Mask] Displays the current setting. [Default Gateway] Displays the current setting. [DNS Server] Displays the current setting.

[Exit] Returns to the operation page.

5

# [Info] page

Click [Info] in the operation page.



# [Help] page

#### Click [Help] in the operation page.

The [Help Desk] window is displayed.



#### 1 [Help Desk]

A message can be sent/received with the administrator using the Crestron Connected  $\ensuremath{^{\text{TM}}}$  .

# Chapter 6 Maintenance

This chapter describes methods of inspection when there are problems, maintenance, and replacement of the units.


# Light source/temperature/filter indicators

# When an indicator lights up

If a problem occurs inside the projector, the light source indicators <LIGHT1>/<LIGHT2>, temperature indicator <TEMP>, or filter indicator <FILTER> will inform you by lighting or blinking in red. Check the status of the indicators and take following measures.

### Attention

• When switching off the projector to deal with problems, make sure to follow the procedure in "Switching off the projector" (+ page 72).



# Light source indicators <LIGHT1>/<LIGHT2>

Indicator status	Status	Solution	
Lighting in red	<ul> <li>Some of the elements of the light source are defective and the light output has decreased.</li> </ul>	<ul> <li>Turn the <main power=""> switch to <off> (⇒ page 72), and turn on the power again.</off></main></li> </ul>	
Blinking in red (1 time)	<ul> <li>The light source is turned off since the projection lens cannot be detected.</li> </ul>	<ul> <li>Turn off the power and mount the projection lens again. (⇒ page 50)</li> <li>Turn the <main power=""> switch to <off> (⇒ page 72), and turn on the power again.</off></main></li> </ul>	
Blinking in red (2 times)	The light source does not light up,	• The light source does not light up,	<ul> <li>Turn the <main power=""> switch to <off> (➡ page 72), and turn on the</off></main></li> </ul>
Blinking in red (3 times)	or the light source turns off while the projector is in use.	power again.	

#### Note

 If the light source indicators <LIGHT1>/<LIGHT2> are still lit or blinking after taking the measures, set the <MAIN POWER> switch to <OFF>, and ask your dealer for repairs.

• The light source indicator corresponding to the light source being lit will light up in green if the projector is in projection mode and there is no indication of problem by lighting or blinking in red.

#### Temperature indicator <TEMP>

Indicator status	Status	Solution
Lighting in red	• Warm-up status	<ul> <li>Wait five minutes when the power is turned on while the temperature is low (approximately 0 °C (32 °F)).</li> <li>Install the projector in a location with the operating environment temperature between 0 °C (32 °F) and 45 °C (113 °F)<sup>-1</sup>.</li> </ul>
	<ul> <li>Internal temperature is high (warning).</li> </ul>	<ul> <li>Remove any objects if they are blocking the air intake/exhaust port.</li> <li>Install the projector in a location with the operating environment temperature</li> </ul>
Blinking in red (2 times)	<ul> <li>Internal temperature is high (standby</li> </ul>	between 0 °C (32 °F) and 45 °C (113 °F)*1, and ambient humidity between 10 % and 80 % (no condensation).
	status).	<ul> <li>Perform maintenance<sup>12</sup> or replace the filter if the filter indicator <filter> lights up. (     page 225)</filter></li> </ul>
Blinking in red (3 times)	<ul> <li>The cooling fan has stopped.</li> </ul>	<ul> <li>Turn the <main power=""> switch to <off> (⇒ page 72), and consult your dealer.</off></main></li> </ul>

\*1 The operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F) if the projector is used at an altitude between 1 400 m (4 593') and 4 200 m (13 780') above sea level. When the [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F), regardless of the altitude. When the Smoke Cut Filter is used, the operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F).

When the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the projector cannot be used at an altitude of 2 700 m (8 858') or higher above sea level. When the Smoke Cut Filter is used, the projector cannot be used at an altitude of 1 400 m (4 593') or higher above sea level.

\*2 Maintenance of the Smoke Cut Filter is not possible. Replace with new one.

#### Note

If the temperature indicator <TEMP> is still lit or blinking after taking the measures, ask your dealer for repair.

# Filter indicator <FILTER>

#### ■ When the air filter unit/Replacement Filter Unit (Model No.: ET-EMF330) is attached

Indicator status	Status	Solution
Lighting in red	<ul> <li>The filter is clogged.</li> <li>The runtime of the filter exceeds the recommended time to replace the filter.</li> <li>The temperature around or outside the projector is abnormally high.</li> </ul>	<ul> <li>Perform maintenance or replacement of the filter in the following cases.</li> <li>(+) page 225)</li> <li>The filter is dirty.</li> <li>The recommended time to replace the filter has been exceeded.</li> <li>Remove any objects if they are blocking the air intake/exhaust port.</li> <li>Do not use the projector at an altitude of 4 200 m (13 780')*1 or higher above sea level.</li> </ul>
Blinking in red	<ul> <li>The air filter unit is not attached.</li> <li>The Long Life Filter Unit or Smoke Cut Filter is not attached.</li> </ul>	<ul> <li>Attach the air filter unit/Replacement Filter Unit.</li> </ul>

\*1 When the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the projector cannot be used at an altitude of 2 700 m (8 858') or higher above sea level.

# When the Long Life Filter Unit (Model No.: ET-EMFU330) is attached

Indicator status	Status	Solution
Lighting in red	<ul> <li>The filter is clogged.</li> <li>The runtime of the filter exceeds the recommended time to replace the filter.<sup>*1</sup></li> <li>The temperature around or outside the projector is abnormally high.</li> </ul>	<ul> <li>Perform maintenance or replacement of the filter in the following cases.</li> <li>(+) page 225)</li> <li>The filter is dirty.</li> <li>The recommended time to replace the filter has been exceeded.<sup>*1</sup></li> <li>Remove any objects if they are blocking the air intake/exhaust port.</li> <li>Do not use the projector at an altitude of 4 200 m (13 780')<sup>*2</sup> or higher above sea level.</li> </ul>
Blinking in red	• [FILTER TYPE]*3 is set to [NORMAL].	Set [FILTER TYPE]*3 to [LONG LIFE].

\*1 If the following two conditions are fulfilled, the recommended time to replace the filter is not set.

• The [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to anything other than [HIGH]. • The [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]  $\rightarrow$  [FILTER TYPE] is set to [LONG LIFE].

• The [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]  $\rightarrow$  [FILTER TYPE] is set to [LONG LIFE]. \*2 When the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG

LIFE3], the projector cannot be used at an altitude of 2 700 m (8 858') or higher above sea level.

\*3 [FILTER TYPE] can be set in the [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]  $\rightarrow$  [FILTER TYPE].

# ■ When the Smoke Cut Filter (Model No.: ET-SFR330) is attached

Indicator status	Status	Solution
Lighting in red	<ul> <li>The filter is clogged.</li> <li>The runtime of the filter exceeds the recommended time to replace the filter.</li> <li>The temperature around or outside the projector is abnormally high.</li> </ul>	<ul> <li>Replace the Smoke Cut Filter in the following cases. (     page 284)     The filter is dirty.     The recommended time to replace the filter has been exceeded.</li> <li>Remove any objects if they are blocking the air intake/exhaust port.</li> <li>Do not use the projector at an altitude of 1 400 m (4 593') or higher above sea level.</li> </ul>
Blinking in red	• [FILTER TYPE] <sup>*1</sup> is set to [NORMAL].	<ul> <li>Set [FILTER TYPE]<sup>*1</sup> to [SMOKE CUT].</li> </ul>

\*1 [FILTER TYPE] can be set in the [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]  $\rightarrow$  [FILTER TYPE].

#### Note

• If the filter indicator <FILTER> is still lit or blinking after taking the measures, ask your dealer for repair.

# Maintenance/replacement

# Before performing maintenance/replacement

- Make sure to turn off the power before maintaining or replacing the unit.
- When switching off the projector, make sure to follow the procedures in "Switching off the projector" (> page 72).

# Maintenance

#### **Outer case**

Wipe off dirt and dust with a soft, dry cloth.

- If the dirt is persistent, soak the cloth with water and wring it thoroughly before wiping. Dry off the projector with a dry cloth.
- Do not use benzene, thinner, or rubbing alcohol, other solvents, or household cleaners. Doing so may
  deteriorate the outer case.
- When using chemically treated dust cloths, follow the instructions written on its packaging.

#### Lens front surface

Wipe off dirt and dust from the front surface of the lens with a soft clean cloth.

- Do not use a cloth that is fluffy, dusty, or soaked with oil/water.
- Since the lens is fragile, do not use excessive force when wiping the lens.

#### Attention

• The lens is made of glass. Impacts or excessive force when wiping may scratch its surface. Handle with care.

# Maintenance of filter

The filter indicator <FILTER> lights up in red in the following cases. Perform maintenance of the filter.

- The filter is clogged.
- The runtime of the filter exceeds the recommended time to replace the filter defined according to the setting in the [PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER TYPE].

This will not apply if the following two conditions are fulfilled.

- The [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to anything
  other than [HIGH].
- The [PROJECTOR SETUP] menu  $\rightarrow$  [FILTER SETTING]  $\rightarrow$  [FILTER TYPE] is set to [LONG LIFE].

#### Attention

- Make sure to turn off the power before performing maintenance of the filter. (+ pages 62, 72)
- Make sure that the projector is stable, and perform the maintenance in a safe place even if the filter falls accidentally.


#### Note

- The runtime of the filter can be checked in the [PROJECTOR SETUP] menu → [STATUS] → [FILTER COUNTER].
- Air filter replacement is recommended after cleaning the unit two times.
- The dust-proof properties may be reduced after each cleaning.
- The time until clogging of the air filter unit varies greatly depending on the usage environment.
- The Smoke Cut Filter (Model No.: ET-SFR330) cannot be reused by performing maintenance. Replace with new one. (+ page 284)

### For the air filter unit

The section describes the maintenance of the standard air filter unit attached to the projector. This air filter unit is the same as the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory).

#### Removing the air filter unit



#### 1) Turn off the power of the projector.

 When switching off the projector, make sure to follow the procedures in "Switching off the projector" (> page 72).

#### 2) Open the air filter cover. (Fig. 1)

- Use a Phillips screwdriver to turn the air filter cover fixing screw counterclockwise until it turns freely, and open the air filter cover for approximately 90°.
- Loosen the air filter cover fixing screw while holding the air filter cover with your hand.


#### 3) Pull out the air filter unit.

- i) Pull out the air filter unit from the tabs on the projector body (c) while slightly pressing the grip on the air filter unit (a) inward as described with the arrow. (Fig. 2)
- ii) Pull out the air filter unit. (Fig. 3)
  - When pulling out, confirm that the air filter unit comes off from the tabs on the projector body (d).
  - After pulling out the air filter unit, remove large foreign objects and dust from the air filter unit compartment and the air intake port of the projector body if there are any.
  - When the air filter unit is removed, proceed to "Performing maintenance of the air filter unit" (> page 227) next.

#### Attention

• Take care not to touch the radiator fin, etc., when removing dirt or dust.

#### Performing maintenance of the air filter unit



#### 1) Wash the air filter unit. (Fig. 1)

- i) Soak the air filter unit in cold or warm water and then lightly rinse it.
  - Do not use cleaning tools such as brushes.
  - When rinsing, hold the frame of the air filter unit without putting strong pressure on the filter unit.
- ii) Rinse the air filter unit two to three times using fresh water each time.
  - Insufficient rinsing may result in odors.
- 2) Dry the air filter unit. (Fig. 2)
  - Let the air filter unit naturally dry off in a well-ventilated place where there is little dust and is not exposed to direct sunlight.
  - Do not dry using drying devices such as dryers.
  - After the air filter is dried, proceed to "Attaching the air filter unit" (> page 227) next.


#### Attention

- After washing the air filter unit, dry it thoroughly before attaching it back to the projector. Attaching a wet unit will cause an electric shock or malfunction.
- Do not disassemble the air filter unit.

#### Note

• Replace the air filter unit with a new Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory) if it is damaged or if the dirt does not come off even after washing.

#### Attaching the air filter unit



- 1) Attach the air filter unit to the projector. (Fig. 1)
  - The air filter unit has no difference between top and bottom, but is two-sided. Match the protrusion position of the air filter unit with the grooves on the projector body.

- Hook the air filter unit frame at the bottom side to the tabs on the projector body (d), and perform Step 3) in "Removing the air filter unit" (→ page 226) in the reverse order to attach.
- Confirm that the tabs on the projector body (c) and (d) are hooked to the air filter unit frame.
- 2) Slide the air filter cover toward the direction of the arrow to close (Fig. 2), and tighten the air filter cover fixing screw using a Phillips screwdriver.
  - When the air filter unit is attached to the projector, proceed to "Resetting the filter counter" (
     page 228) next.

#### Note

- Make sure that the air filter unit is properly attached before using the projector. If it is not attached, the projector will suck in dirt and dust causing a malfunction.
- When the projector is used without the air filter unit attached, the filter indicator <FILTER> lights up in red.

#### Resetting the filter counter

- 1) Turn on the power of the projector.
- 2) Press the <MENU> button on the remote control or control panel.
  - The [MAIN MENU] screen is displayed.
- 3) Press ▲▼ to select [PROJECTOR SETUP].
- 4) Press the <ENTER> button.
  - The [PROJECTOR SETUP] screen is displayed.
- 5) Press  $\blacktriangle \lor$  to select [FILTER SETTING].
- 6) Press the <ENTER> button.
  - The [FILTER SETTING] screen is displayed.
- 7) Press ▲▼ to select [FILTER COUNTER RESET], and press the <ENTER> button.
- 8) When the confirmation screen is displayed, press <> to select [OK], and press the <ENTER> button.
   The [PROJECTOR SETUP] menu → [STATUS] → [FILTER COUNTER] is displayed as "0".


#### Note

• When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.

#### For the Long Life Filter Unit

This section describes the maintenance of the air filter unit when the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached instead of the standard air filter unit attached to the projector. The Long Life Filter Unit uses two of the same standard air filter units attached to the projector or the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory).

#### Removing the air filter unit



#### 1) Turn off the power of the projector.

 When switching off the projector, make sure to follow the procedures in "Switching off the projector" (> page 72).

# 228 - ENGLISH

#### 2) Remove the long life filter cover. (Fig. 1)

- Remove the long life filter cover fixing screws (two locations at right and left) by turning them counterclockwise, and remove the long life filter cover from the long life filter mount clasp.
- When loosening the long life filter cover fixing screws, hold the screws with your hand so they will not fall.


#### 3) Remove the two air filter units from the long life filter cover. (Fig. 2)

- The method to remove the two air filter units is the same.
- Hold the outer frame of the air filter unit and pull out in the direction of the arrow.
- After pulling out the air filter unit, remove large foreign objects and dust from the long life filter cover, air filter unit compartment and the air intake port of the projector body if there are any.
- When the air filter unit is removed, proceed to "Performing maintenance of the air filter unit" (
   page 229) next.

#### Attention

- Do not lose the two long life filter cover fixing screws that have been removed.
- Take care not to touch the radiator fin, etc., when removing dirt or dust.

#### Performing maintenance of the air filter unit



#### 1) Wash the air filter unit. (Fig. 1)

- i) Soak the air filter unit in cold or warm water and then lightly rinse it.
  - Do not use cleaning tools such as brushes.
  - When rinsing, hold the frame of the air filter unit without putting strong pressure on the filter unit.
- ii) Rinse the air filter unit two to three times using fresh water each time.
  - Insufficient rinsing may result in odors.

#### 2) Dry the air filter unit. (Fig. 2)

- Let the air filter unit naturally dry off in a well-ventilated place where there is little dust and is not exposed to direct sunlight.
- Do not dry using drying devices such as dryers.
- After the air filter is dried, proceed to "Attaching the air filter unit" (> page 230) next.


#### Attention

- After washing the air filter unit, dry it thoroughly before attaching it back to the long life filter cover. Attaching a wet unit will cause an electric shock or malfunction.
- Do not disassemble the air filter unit.

#### Note

 Replace the air filter unit with a new Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory) if it is damaged or if the dirt does not come off even after washing.

#### Attaching the air filter unit




#### 1) Attach the two air filter units to the long life filter cover. (Fig. 1)

- Attach the two air filter units to the long life filter cover. The method to attach the two air filter units is the same.
- Align the position so that the grips on the air filter unit (a) and (b) will be outside the guides on the long life filter cover (e) and (f), and push in the direction of the arrow by holding the outer frame of the air filter unit. (Fig. 2)
- When the two air filter units are attached (Fig. 3), proceed to "Attaching the long life filter cover" (
   page 230) next.

#### Note

• Make sure that the air filter unit is properly attached before using the projector. If it is not attached, the projector will suck in dirt and dust causing a malfunction.

#### Attaching the long life filter cover



- 1) Attach the long life filter cover to the long life filter mount clasp. (Fig. 1)
  - Attach the long life filter cover (with the two air filter units attached) to the long life filter mount clasp on the projector body.
  - The long life filter cover has no difference between top and bottom.
- 2) Secure the long life filter cover. (Fig. 2)
  - Securely fix with the two long life filter cover fixing screws (knurled head screws) removed in Step 2) in "Removing the air filter unit" (+ page 228).
  - When the long life filter cover is secured, proceed to "Resetting the filter counter" (> page 231) next.

#### Resetting the filter counter

- 1) Turn on the power of the projector.
- 2) Press the <MENU> button on the remote control or control panel.
  The [MAIN MENU] screen is displayed.
- 3) Press ▲▼ to select [PROJECTOR SETUP].
- 4) Press the <ENTER> button.
   The [PROJECTOR SETUP] screen is displayed.
- 5) Press ▲▼ to select [FILTER SETTING].
- 6) Press the <ENTER> button.
  - The [FILTER SETTING] screen is displayed.
- 7) Press ▲▼ to select [FILTER COUNTER RESET], and press the <ENTER> button.
- 8) When the confirmation screen is displayed, press **(**) to select [OK], and press the **(ENTER)** button.

• The [PROJECTOR SETUP] menu  $\rightarrow$  [STATUS]  $\rightarrow$  [FILTER COUNTER] is displayed as "0".

#### Note

• When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.

# Replacing the unit

#### Filter

If dirt does not come off even after the air filter unit is maintained, it is time for the unit to be replaced. The Replacement Filter Unit (Model No.: ET-EMF330) is an optional accessory. To purchase the product, consult your dealer.

#### Attention

- Make sure to turn off the power before replacing the filter. (➡ pages 62, 72)
- Make sure that the projector is stable, and perform the maintenance in a safe place even if the filter falls accidentally.

#### Note

• The replacement cycle of the air filter unit varies greatly depending on the usage environment.

#### For the air filter unit

The section describes the replacement procedure of the standard air filter unit attached to the projector. This air filter unit is the same as the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory).

#### 1) Remove the air filter unit.

- Refer to "Removing the air filter unit" (+ page 226) of the standard air filter unit.
- Attach the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory) to the projector.
  - Refer to "Attaching the air filter unit" (> page 227) of the standard air filter unit.

#### 3) Reset the filter counter.

• Refer to "Resetting the filter counter" (→ page 228) of the standard air filter unit.

#### Attention

• When switching on the projector, make sure that the air filter unit is attached. If it is not attached, the projector will suck in dirt and dust causing a malfunction.

• When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.

When the projector is used without the air filter unit attached, the filter indicator <FILTER> lights up in red.

#### For the Long Life Filter Unit

This section describes the replacement procedure of the air filter unit when the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached instead of the standard air filter unit attached to the projector. The Long Life Filter Unit uses two of the same standard air filters attached to the projector or the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory).

#### 1) Remove the two air filter units from the long life filter cover.

Refer to "Removing the air filter unit" (➡ page 228) of the Long Life Filter Unit.

- 2) Attach the two Replacement Filter Units (Model No.: ET-EMF330) (accessory/optional accessory) to the long life filter cover.
  - Refer to "Attaching the air filter unit" (➡ page 230) of the Long Life Filter Unit.

#### 3) Attach the long life filter cover to the long life filter mount clasp.

• Refer to "Attaching the long life filter cover" (→ page 230) of the Long Life Filter Unit.

#### 4) Resetting the filter counter

Refer to "Resetting the filter counter" (➡ page 231) of the Long Life Filter Unit.

#### Note

- When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.
- Refer to "Attaching the Long Life Filter Unit (optional)" (
   page 281) for the procedure to attach the optional Long Life Filter Unit (Model No.: ET-EMFU330) instead of the standard air filter unit attached to the projector.

<sup>•</sup> When switching on the projector, make sure that the air filter unit is attached. If it is not attached, the projector will suck in dirt and dust causing a malfunction.

# Troubleshooting

Review the following points. For details, see the corresponding pages.

Problems	Points to be checked	Page
	Is the power plug firmly inserted into the outlet?	_
	<ul> <li>Is the <main power=""> switch set to <off>?</off></main></li> </ul>	72
Power does not turn on.	Is the wall outlet supplying electricity?	_
	Have the circuit breakers tripped?	_
	• Are the light source indicators <light1>/<light2> or the temperature indicator</light2></light1>	222
	<temp> lighting or blinking?  Are connections to external devices correctly performed?</temp>	53
	Is the image input selected correctly?	73
	<ul> <li>Is the [BRIGHTNESS] adjustment setting at a minimum?</li> </ul>	94
	<ul> <li>Is the external device that is connected to the projector working properly?</li> </ul>	
No image appears.	<ul> <li>Is the shutter function in use?</li> </ul>	83
		50
	Is the projection lens attached correctly?	50
	• If the power indicator <on (g)="" (r)="" standby=""> is blinking in red, consult your dealer.</on>	_
	Is the lens cover still attached to the lens?	64
	Is the lens focus set correctly?	75
mage is fuzzy.	Is the projection distance appropriate?	41
•	• Is the lens dirty?	22
	Is the projector installed perpendicular to the screen?	
Color is pale or grayish.	Are [COLOR] and [TINT] adjusted correctly?	94
	Is the external device connected to the projector adjusted correctly?	53
	Are the batteries depleted?	_
	<ul> <li>Is the polarity of the batteries set correctly?</li> </ul>	36
	• Is the button operation disabled by sliding the <lock> button on the remote control?</lock>	28
Remote control does not	• Are there any obstructions between the remote control and the remote control signal receiver of the projector?	28
respond.	• Is the remote control being used beyond its effective operation range?	29
	• Are other forms of light, such as fluorescent light, affecting the projection?	29
	<ul> <li>Is the [REMOTE CONTROL] setting in [CONTROL DEVICE SETUP] set to [DISABLE]?</li> </ul>	190
	<ul> <li>Is the <remote 2="" in=""> terminal used for contact control?</remote></li> </ul>	253
	Is the ID number setting operation correct?	86
Menu screen does not appear.	Is the on-screen display function turned off (hidden)?	139
Buttons on the control	Is the [CONTROL PANEL] setting in [CONTROL DEVICE SETUP] set to [DISABLE]?	190
panel do not operate.	<ul> <li>Is the <remote 2="" in=""> terminal used for contact control?</remote></li> </ul>	253
	Is the [SYSTEM SELECTOR] selection set correctly?	100, 121, 134
mage does not display	<ul> <li>Is there a problem with the external device to output images?</li> </ul>	
correctly.	<ul> <li>Is a signal which is not compatible with the projector being input?</li> </ul>	255
····· <b>,</b> ·	<ul> <li>Are the settings for [SDI IN], [DIGITAL LINK IN], and [SLOT IN] made correctly?</li> </ul>	
	Is the cable too long?	
Image from a computer does not appear.	<ul> <li>Is the external video output on the laptop computer set correctly? (Ex.: The external output settings may be switched by pressing the "Fn" + "F3" or "Fn" + "F10" simultaneously. Since the method varies depending on the computer type, refer to the user manual provided with your computer.)</li> </ul>	_
	<ul> <li>Is [DVI-D LINK] in [SLOT IN] set correctly? Also, if it is set to [AUTO], the condition may improve by changing the setting to anything other than [AUTO].</li> </ul>	127
mage output from DVI-D	<ul> <li>Is the [EDID SELECT] setting in [SLOT IN] set to [EDID3] or [EDID2:PC]?</li> </ul>	127
of the computer does not appear.	<ul> <li>The graphics accelerator driver of the computer may need to be updated to the latest version.</li> </ul>	_
	<ul> <li>The condition may improve by setting [EDID SELECT] in [SLOT IN] and then restarting the computer.</li> </ul>	127
Video from HDMI	Is the HDMI cable connected securely?	53
compatible device does	<ul> <li>Turn the power of the projector and the external device off and on.</li> </ul>	
not appear or it appears		255
umbled.	<ul> <li>Is a signal which is not compatible with the projector being input?</li> </ul>	255

# Chapter 6 Maintenance — Troubleshooting

Problems	Points to be checked	Page
Image output from	<ul> <li>If connecting the projector to a computer that uses an early-type chipset or graphics card compatible with DisplayPort, the projector or computer may not be operated properly.</li> </ul>	261
DisplayPort of the computer does not appear.	• The graphics accelerator driver of the computer may need to be updated to the latest version.	—
	<ul> <li>Turn the power of the projector and the external device off and on.</li> </ul>	_
	Is a signal which is not compatible with the projector being input?	260
Lens shift cannot be	Perform [LENS CALIBRATION].	159
adjusted.	Is the Fixed-focus Lens (Model No.: ET-D75LE50) attached?	_
Geometric adjustment is	<ul> <li>Is [QUAD PIXEL DRIVE] set to [OFF]?</li> </ul>	104
not possible.	<ul> <li>Is [SIMUL INPUT SETTING] set to [AUTO(x2-speed)] or [AUTO(x4-speed)]?</li> </ul>	104
Cannot control the	• Are the connections between the twisted-pair-cable transmitter and an external device, and between the twisted-pair-cable transmitter and projector correctly done?	—
projector with Art-Net.	<ul> <li>Is [Art-Net SETUP] set to other than [OFF]?</li> </ul>	197
	<ul> <li>Are [NET], [SUB NET], [UNIVERSE], and [START ADDRESS] set correctly?</li> </ul>	197
	Is the cable compatible to the condition of the projector used?	58
The DIGITAL LINK input	• Are the connections between the twisted-pair-cable transmitter and the projector or an external device correctly done?	—
image is not displayed.	<ul> <li>Is [DIGITAL LINK MODE] set to [AUTO] or [DIGITAL LINK]? Is it set to [ETHERNET]?</li> </ul>	195
	• Is a signal which is not compatible with a twisted-pair-cable transmitter being input?	—
Cannot switch to the input	<ul> <li>Is the Interface Board correctly installed in the slot?</li> </ul>	287
of the Interface Board.	<ul> <li>When the 3G-SDI Terminal Board with Audio is installed, is the firmware version of the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) 2.00 or later?</li> </ul>	35

# Attention

• If problems persist even after checking the preceding points, consult your dealer.

# Self-diagnosis display

There is a self-diagnosis display on the side of the projector. Self-diagnosis display will automatically display the value of the input supply voltage, or details of errors or warnings when they occur. ( $\Rightarrow$  page 31) The following list shows the alphanumeric symbol that is displayed when an error or a warning has occurred and its details. Confirm "Action number", and follow the measure in "Measure for error and warning" ( $\Rightarrow$  page 237). The input supply voltage is displayed only with the numeric value.

Error/warning alphanumeric symbol	Error/warning alphanumeric symbol content	Action number
U04	Filter clogging	1
U11	Intake temperature warning	2
U12	Optical module temperature warning	2
U13	Exhaust air temperature warning	3
U14	Low temperature warning	4
U16	Light source 1-B temperature warning	2
U17	Light source 1-S temperature warning	2
U18	Light source 2-B temperature warning	2
U19	Light source 2-S temperature warning	2
U21	Intake temperature error	2
U22	Optical module temperature error	2
U23	Exhaust air temperature error	3
U24	Low temperature error	4
U25	Light source 1-B temperature error	2
U26	Light source 1-S temperature error	2
U27	Light source 2-B temperature error	2
U28	Light source 2-S temperature error	2
U81	Low AC voltage warning (below 90 V)	5
U84	<dc 1="" out=""> terminal power supply error</dc>	6
U85	<dc 2="" out=""> terminal power supply error</dc>	6
U90	Projection lens not attached	7
UA0	Power supply temperature warning	2
UA1	FPGA temperature warning	2
UA4	Power supply temperature error	2
UA5	FPGA temperature error	2
H01	Battery replacement for the internal clock	8
H11	Intake air temperature sensor error	9
H12	Optical module temperature sensor error	9
H13	Exhaust air temperature sensor error	9
H14	Light source 1-B temperature sensor error	9
H15	Light source 1-S temperature sensor error	9
H16	Light source 2-B temperature sensor error	9
H17	Light source 2-S temperature sensor error	9
H18	Clog sensor error	9
F00	Liquid cooling pump R warning	9
F01	Liquid cooling pump G warning	9
F02	Liquid cooling pump B warning	9
F03	Liquid cooling pump b warning	9
F04	Liquid cooling pump light source 1-S warning	9
F05	Liquid cooling pump light source 2-B warning	9
F06	Liquid cooling pump light source 2-5 warning	9
F11	Shutter error	9
F15	Luminance sensor error	9
F15		9
F50	QUAD PIXEL DRIVE unit error	9
	Radiator fan 1 warning	
F51	Radiator fan 2 warning	9
F52	Radiator fan 3 warning	9
F53	Radiator fan 4 warning	9
F54	Radiator fan 5 warning	9
F55	Radiator fan 6 warning	9

Error/warning alphanumeric symbol	Error/warning alphanumeric symbol content	Action number
F56	Radiator fan 7 warning	9
F57	Radiator fan 8 warning	9
F58	Radiator fan 9 warning	9
F59	Radiator fan 10 warning	9
F70	Radiator fan 11 warning	9
F71	Radiator fan 12 warning	9
F72	Exhaust fan 1 warning	9
F73	Exhaust fan 2 warning	9
F74	Exhaust fan 3 warning	9
F75	Exhaust fan 4 warning	9
F76	Intake fan 1 warning	9
F77	Intake fan 2 warning	9
F78	Color prism fan 1 warning	9
F79	Color prism fan 2 warning	9
F61	Light source 1-B driver communication error	9
F62	Light source 1-S driver communication error	9
F63	Light source 2-B driver communication error	9
F64	Light source 2-S driver communication error	9
F96	Lens mounter error	9
FA0	Color prism fan 3 warning	9
FA1	Color prism fan 4 warning	9
FA2	Engine exhaust fan 1 warning	9
FA3	Phosphor wheel fan 1 warning	9
FA4	Phosphor wheel fan 2 warning	9
FA5	Circuit intake fan 1 warning	9
FA6	Circuit intake fan 2 warning	9
FA7	Light source driver fan 1 warning	9
FA8	Light source 1-B error	9
FC3	Light source driver fan 2 warning	9
FC4	Engine exhaust fan 2 warning	9
FC8	Light source 1-S error	9
FH7	Light source 2-B error	9
FH8	Light source 2-S error	9
FFI FE1	Radiator fan 1 error	
FE1		9
FE3	Radiator fan 2 error Radiator fan 3 error	9
FE4	Radiator fan 4 error	9
FE5	Radiator fan 5 error	9
FE6	Radiator fan 6 error	9
FE7	Radiator fan 7 error	9
FE8	Radiator fan 8 error	9
FE9	Radiator fan 9 error	9
FF0	Radiator fan 10 error	9
FF1	Radiator fan 11 error	9
FF2	Radiator fan 12 error	9
FF3	Exhaust fan 1 error	9
FF4	Exhaust fan 2 error	9
FF5	Exhaust fan 3 error	9
FF6	Exhaust fan 4 error	9
FF7	Intake fan 1 error	9
FF8	Intake fan 2 error	9
FF9	Color prism fan 1 error	9
FE0	Color prism fan 2 error	9
FH0	Phosphor wheel 1 error SUB	9
FH1	Phosphor wheel 1 error FPGA	9
FH2	Phosphor wheel 2 error SUB	9
FH3	Phosphor wheel 2 error FPGA	9

Chapter 6	Maintenance —	<ul> <li>Self-diagnosis</li> </ul>	display
-----------	---------------	------------------------------------	---------

Error/warning alphanumeric symbol	Error/warning alphanumeric symbol content	Action number
FJ0	Liquid cooling pump R error	9
FJ1	Liquid cooling pump G error	9
FJ2	Liquid cooling pump B error	9
FJ3	Liquid cooling pump light source 1-B error	9
FJ4	Liquid cooling pump light source 1-S error	9
FJ5	Liquid cooling pump light source 2-B error	9
FJ6	Liquid cooling pump light source 2-S error	9
FL1	Light source 1-B unit error	9
FL2	Light source 1-S unit error	9
FL3	Light source 2-B unit error	9
FL4	Light source 2-S unit error	9
FP8	Color prism fan 3 error	9
FP9	Color prism fan 4 error	9
FU0	Engine exhaust fan 1 error	9
FU1	Phosphor wheel fan 1 error	9
FU2	Phosphor wheel fan 2 error	9
FU3	Circuit intake fan 1 error	9
FU4	Circuit intake fan 2 error	9
FU5	Light source driver fan 1 error	9
FU6	Light source driver fan 2 error	9
FU7	Engine exhaust fan 2 error	9

#### Note

The self-diagnosis display and the details of the malfunction may vary.For errors and warnings that are not described in the table, consult your dealer.

# Measure for error and warning

Action number	Measure
1	Perform maintenance or replacement of the filter. (> page 225)
2	The operating environment temperature is too high. Use the projector in an appropriate operating environment temperature*1.
3	The operating environment temperature is too high, or the air exhaust port may be blocked. Use the projector in an appropriate operating environment temperature <sup>*1</sup> . Or remove any objects that are blocking the air exhaust port.
4	The operating environment temperature is too low. Use the projector in an appropriate operating environment temperature*1.
5	The input supply voltage is low. Use electric wiring that can sufficiently withstand the power consumption of the projector.
6	The output of the <dc 1="" out=""> terminal/<dc 2="" out=""> terminal is too high. Devices that require a power source exceeding DC 5 V/900 mA may be connected. If the display does not clear after the device is removed, consult your dealer.</dc></dc>
7	The projection lens cannot be detected. Turn off the power and attach the projection lens again. If the display does not clear after switching the power off and on, consult your dealer.
8	Battery replacement is required. Consult your dealer.
9	If the display does not clear after switching the main power off and on, consult your dealer.

\*1 Refer to "Operating environment temperature" (> page 276) for the operating environment temperature of the projector.

# Chapter 7 Appendix

This chapter describes the specification of the projector, how to install the optional Interface Board, and after-sales service.

# **Technical information**

# PJLink protocol

The network function of this projector supports the PJLink class 1, and the PJLink protocol can be used to perform projector setting and projector status query operations from a computer.

# **Control commands**

The following table lists the PJLink protocol commands that can be used to control the projector. • x characters in tables are non-specific characters.

Command	Control details	Parameter/response string		Remark		
POWR		0	Standby			
POWR	Power supply control	1	Power on			
	Device events status	0	Standby			
POWR?	Power supply status query	1	Power on	Power on		
		2	Preparing for switching off the projector			
		31	SDI1			
	32		SDI2			
INPT	Input selection	33	SDI3			
		34	SDI4			
		35	DIGITAL LINK			
		36	SLOT1-1 (inpu	it 1 of the Interface Board installed in	<slot 1="">)*1</slot>	
INPT?		37	SLOT1-2 (inpu	It 2 of the Interface Board installed in	<slot 1="">)*2</slot>	
INF I ?	Input selection query	38	SLOT2-3 (inpu	it 3 of the Interface Board installed in	<slot 2="">)*1</slot>	
		39	SLOT2-4 (inpu	it 4 of the Interface Board installed in	<slot 2="">)*2</slot>	
AVMT	Shutter control	30	Shutter functio	n disabled (shutter: open)		
AVMT?	Shutter status query	31	Shutter functio	n enabled (shutter: closed)	-	
	Error status query		1st byte	Indicates fan errors, and returns 0 - 2.	• 0 = No error is detected	
		Error status query xxxxxx		2nd byte	Indicates light source errors, and returns 0 or 2.	<ul> <li>1 = Warning</li> <li>2 = Error</li> </ul>
ERST?			xxxxxx	3rd byte	Indicates temperature errors, and returns 0 - 2.	
				4th byte	Returns 0.	
				5th byte	Indicates filter errors, and returns 0 - 2.	
				6th byte	Indicates other errors, and returns 0 - 2.	
LAMP?	Light source status query	xxxxxxxxxx	1st number (1 - 5 digits): Light source 1 runtime 2nd number: 0 = Light source 1 off, 1 = Light source 1 on 3rd number (1 - 5 digits): Light source 2 runtime 4th number: 0 = Light source 2 off, 1 = Light source 2 on			
INST?	Input selection list query	31 32 33 34 35 36 37 38 39	_			
NAME?	Projector name query	ххххх	Returns the name set in [PROJECTOR NAME] of [NETWORK SETUP].			
INF1?	Manufacturer name query	Panasonic	Returns manufacturer name.			
INF2?	Model name query	RQ32K	Returns model name.			
INF0?	Other information queries	xxxxx	Returns information such as version number.			
CLSS?	Class information query	1	Returns class	for PJLink.		

\*1 When the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed, this corresponds to the input switch for the <SDI 1 IN> terminal. Switching to the <SDI 2 IN/1 OUT> terminal or the <SDI 4 IN/3 OUT> terminal is not possible.

\*2 When the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed, this corresponds to the input switch for the <SDI 3 IN> terminal. Switching to the <SDI 2 IN/1 OUT> terminal or the <SDI 4 IN/3 OUT> terminal is not possible.

# PJLink security authentication

The password used for PJLink is the same as that of the password set for web control.

When using the projector without security authentication, do not set a password for web control.

• For specifications related to PJLink, visit the website of Japan Business Machine and Information System Industries Association.

URL http://pjlink.jbmia.or.jp/english/

# **Using Art-Net function**

Since the network function of the projector supports the Art-Net function, you can control the projector settings with the DMX controller and application software using the Art-Net protocol.

#### **Channel definition**

The following table lists the channel definitions used for controlling the projector with the Art-Net function. Channel settings can be switched using the [NETWORK] menu  $\rightarrow$  [Art-Net CHANNEL SETTING] ( $\Rightarrow$  page 198). The control details assigned to each channel are listed in the following table.

• Channel assignment for [USER] is in factory default setting. Assignment can be changed.

Channel		Contro	details	
Channel	[1]	[2]	[3]	[USER]
CHANNEL1	SHUTTER	LIGHT OUTPUT	LIGHT OUTPUT	LIGHT OUTPUT
CHANNEL2	INPUT SELECT	INPUT SELECT	INPUT SELECT	INPUT SELECT
CHANNEL3	LENS FUNCTION SELECT	LENS POSITION	LENS POSITION	LENS POSITION
CHANNEL4	LENS CONTROL	LENS H SHIFT	LENS H SHIFT	LENS H SHIFT
CHANNEL5	POWER	LENS V SHIFT	LENS V SHIFT	LENS V SHIFT
CHANNEL6	LIGHT OUTPUT	LENS FOCUS	LENS FOCUS MSB	LENS FOCUS
CHANNEL7	ENABLE/DISABLE	LENS ZOOM	LENS FOCUS LSB	LENS ZOOM
CHANNEL8	FADE-IN	POWER	LENS ZOOM MSB	POWER
CHANNEL9	FADE-OUT	GEOMETRY	LENS ZOOM LSB	GEOMETRY
CHANNEL10	CUSTOM MASKING	CUSTOM MASKING	SHUTTER	CUSTOM MASKING
CHANNEL11	GEOMETRY	ENABLE/DISABLE	ENABLE/DISABLE	ENABLE/DISABLE
CHANNEL12	NONE	NONE	NONE	NONE

#### Content that can be controlled by each Art-Net channel setting

✓: Can be controlled

O a set sa La la fa lla		Art-Net cha	nnel setting	
Control details	[1]	[2]	[3]	[USER]
LIGHT OUTPUT	$\checkmark$	1	1	1
INPUT SELECT	$\checkmark$	✓	1	1
LENS FUNCTION SELECT	$\checkmark$	—	_	—
LENS CONTROL	✓	—	—	—
LENS POSITION	—	$\checkmark$	✓	1
LENS H SHIFT	—	$\checkmark$	✓	✓
LENS V SHIFT	—	✓	✓	1
LENS FOCUS	_	✓	_	1
LENS ZOOM	_	✓	_	1
POWER	$\checkmark$	✓	_	✓
SHUTTER	$\checkmark$	_	✓	✓
FADE-IN	$\checkmark$	—	_	✓
FADE-OUT	✓	—	_	1
GEOMETRY	✓	✓	_	1
CUSTOM MASKING	$\checkmark$	✓	_	1
FREEZE	—	—	—	✓
COLOR	_	—	—	1
TINT		_	_	✓

# Chapter 7 Appendix — Technical information

Control details		Art-Net channel setting			
	[1]	[2]	[3]	[USER]	
RASTER PATTERN	_	—	_	✓ <i>✓</i>	
LENS H SHIFT MSB	_	_	_	<b>√</b> *1	
LENS H SHIFT LSB	_	_	_	<b>√</b> *1	
LENS V SHIFT MSB	_	_	_	<b>√</b> *1	
LENS V SHIFT LSB	_	_	_	✓*1	
LENS FOCUS MSB	_	_	1	✓*1	
LENS FOCUS LSB	_	_	1	✓*1	
LENS ZOOM MSB	_	_	1	✓*1	
LENS ZOOM LSB	_	_	1	<b>√</b> *1	
ENABLE/DISABLE	1	1	1	1	

\*1 These items can be controlled in following case.

When the standard DC motor unit installed in the Zoom Lens (Model No.: ET-D75LE6, ET-D75LE8, ET-D75LE10, ET-D75LE20, ET-D75LE30, ET-D75LE40, etc.) is replaced with the stepping motor unit using the Stepping Motor Kit (Model No.: ET-D75MKS10), or when a projection lens with the stepping motor is attached.

### **Control details**

# LIGHT OUTPUT

This can be set in 256 steps between 100 % and 0 %.

Performance	Parameter	Default value
100 %	0	
		0
0 %	255	

# ■ INPUT SELECT (when [Art-Net CHANNEL SETTING] is set to [1])

Performance	Parameter	Default value
No operation	0-47	
SDI1	48-55	
SDI2	56-63	0
No operation	64-255	

# ■ INPUT SELECT (when [Art-Net CHANNEL SETTING] is set to anything other than [1])

Performance	Parameter	Default value
No operation	0-39	
DIGITAL LINK	40-47	
SDI1	48-55	
SDI2	56-63	
SDI3	64-71	
SDI4	72-79	
SLOT1-1*1	80-87	
SLOT1-2*1	88-95	
SLOT2-3*2	96-103	
SLOT2-4*2	104-111	
No operation	112-119	
MULTI DISPLAY OFF	120-127	- 0
Execute MULTI DISPLAY, USER1	128-135	0
Execute MULTI DISPLAY, USER2	136-143	
Execute MULTI DISPLAY, USER3	144-151	
SLOT1-1*3	152-159	
SLOT1-2*3	160-167	
SLOT1-3*3	168-175	
SLOT1-4*3	176-183	
SLOT2-1*4	184-191	
SLOT2-2*4	192-199	
SLOT2-3*4	200-207	
SLOT2-4*4	208-215	
No operation	216-255	

When the Interface Board equipped with two inputs is installed in <SLOT 1>, the input is switched to the specified input of the Interface Board. When the Interface Board equipped with two inputs is installed in <SLOT 2>, the input is switched to the specified input of the Interface Board. When the Interface Board equipped with four inputs is installed in <SLOT 1>, the input is switched to the specified input of the Interface Board. When the Interface Board equipped with four inputs is installed in <SLOT 1>, the input is switched to the specified input of the Interface Board.

\*1 \*2 \*3 \*4 When the Interface Board equipped with four inputs is installed in <SLOT 2>, the input is switched to the specified input of the Interface Board.

# ■ LENS FUNCTION SELECT

Operate together with LENS CONTROL.

Performance	Parameter	Default value
No operation	0-15	
LENS H SHIFT	16-31	
LENS V SHIFT	32-47	
LENS FOCUS	48-63	
LENS ZOOM	64-79	0
Move to the home position	80-95	0
Load LENS MEMORY 1	96-111	
Load LENS MEMORY 2	112-127	
Load LENS MEMORY 3	128-143	
No operation	144-255	

# LENS CONTROL

Operate together with LENS FUNCTION SELECT.

Performance		Parameter	Default value
	(-) High speed	0-31	
Lens adjustment	(-) Low speed	32-63	
	(-) Fine adjustment	64-95	
Operation stop		96-127	100
	(+) Fine adjustment	128-159	100
Lens adjustment	(+) Low speed	160-191	
	(+) High speed	192-223	
Execute command action		224-255	

# LENS POSITION

Performance	Parameter	Default value
No operation	0-31	
Move to the home position	32-63	
Load LENS MEMORY 1	64-79	
Load LENS MEMORY 2	80-95	
Load LENS MEMORY 3	96-111	
Load LENS MEMORY 4	112-127	
Load LENS MEMORY 5	128-143	0
Load LENS MEMORY 6	144-159	
Load LENS MEMORY 7	160-175	
Load LENS MEMORY 8	176-191	
Load LENS MEMORY 9	192-207	
Load LENS MEMORY 10	208-223	
No operation	224-255	

# LENS H SHIFT, LENS V SHIFT, LENS FOCUS, LENS ZOOM

Performance		Parameter	Default value
	(-) High speed	0-31	
Lens adjustment	(-) Low speed	32-63	
	(-) Fine adjustment	64-95	
Operation stop		96-159	128
	(+) Fine adjustment	160-191	
Lens adjustment	(+) Low speed	192-223	
	(+) High speed	224-255	

# POWER

Performance	Parameter	Default value
Standby	0-63	
No operation	64-191	128
Power on	192-255	

# SHUTTER

Performance	Parameter	Default value
SHUTTER: Open	0-63	
No operation	64-191	128
SHUTTER: Closed	192-255	

# ■ FADE-IN, FADE-OUT

Operate together with SHUTTER.

Performance	Parameter	Default value
OFF	0-15	
0.5s	16-31	
1.0s	32-47	
1.5s	48-63	
2.0s	64-79	
2.5s	80-95	
3.0s	96-111	255
3.5s	112-127	
4.0s	128-143	
5.0s	144-159	
7.0s	160-175	
10.0s	176-191	
No operation	192-255	

# GEOMETRY

Performance	Parameter	Default value
OFF	0-15	
KEYSTONE	16-31	
CURVED CORRECTION	32-47	
PC-1	48-63	055
PC-2	64-79	255
PC-3	80-95	
CORNER CORRECTION	96-111	
No operation	112-255	

# CUSTOM MASKING

To use PC-1, PC-2, or PC-3, the optional Upgrade Kit (Model No.: ET-UK20) is required.

Performance	Parameter	Default value
OFF	0-31	
PC-1	32-63	
PC-2	64-95	255
PC-3	96-127	
No operation	128-255	

# FREEZE

Performance	Parameter	Default value
No operation	0-31	
OFF	32-95	
No operation	96-159	128
ON	160-223	
No operation	224-255	

# COLOR, TINT

Performance	Parameter	Default value	
No operation	0-31		
Factory default setting	32-63		
-31	64		
0	128-129	0	
+31	191		
No operation	192-255		

# RASTER PATTERN

Performance	Parameter	Default value
No operation	0-15	
OFF	16-31	
WHITE	32-47	
YELLOW	48-63	
CYAN	64-79	
GREEN	80-95	
MAGENTA	96-111	- 0
RED	112-127	]
BLUE	128-143	
BLACK	144-159	
USER LOGO	160-175	
No operation	176-255	

# LENS H SHIFT MSB, LENS V SHIFT MSB, LENS FOCUS MSB, LENS ZOOM MSB

Operate LENS H SHIFT MSB together with LENS H SHIFT LSB. Operate LENS V SHIFT MSB together with LENS V SHIFT LSB. Operate LENS FOCUS MSB together with LENS FOCUS LSB. Operate LENS ZOOM MSB together with LENS ZOOM LSB.

Performance	Parameter	Default value
No operation	0-15	0
Coarse adjustment	16-255	0

# LENS H SHIFT LSB, LENS V SHIFT LSB, LENS FOCUS LSB, LENS ZOOM LSB

Operate LENS H SHIFT LSB together with LENS H SHIFT MSB. Operate LENS V SHIFT LSB together with LENS V SHIFT MSB. Operate LENS FOCUS LSB together with LENS FOCUS MSB. Operate LENS ZOOM LSB together with LENS ZOOM MSB.

Performance	Parameter	Default value	
No operation	0-15	0	
Fine adjustment	16-255	0	

### ENABLE/DISABLE

Operation for all channels is not accepted when set to "Disable".

Performance	Parameter	Default value
Disable	0-127	0
Enable	128-255	0

Note

- If the projector is operated using the remote control or the control panel, or by the control command while controlling the projector using the Art-Net function, the setting of the DMX controller or computer application may be different from the projector status. To reflect the controls of all channels to the projector, set "ENABLE/DISABLE" of channel 11 to "Disable" and then back to "Enable".
- To create/register the USER LOGO image, use "Logo Transfer Software" included in the supplied CD-ROM.

# **Control commands via LAN**

#### When web control administrator rights password is set (Protect mode)

# Connecting

1) Obtain the IP address and port number (Initial set value = 1024) of the projector and request a connection to the projector.

• You can obtain both the IP address and the port number from the menu screen of the projector.

IP address	Obtain from the [NETWORK] menu $\rightarrow$ [NETWORK STATUS].	
Port number	Obtain from the [NETWORK] menu $\rightarrow$ [NETWORK CONTROL] $\rightarrow$ [COMMAND PORT].	

#### 2) Check the response from the projector.

	Data section	Blank	Mode	Blank	Random number section	Termination symbol
Command	"NTCONTROL"	· ,	·1'	· ,	"ZZZZZZZZZ	(CR)
example	(ASCII string)	0x20	0x31	0x20	(ASCII code hex number)	0x0d
Data length	9 bytes	1 byte	1 byte	1 byte	8 bytes	1 byte

• Mode: 1 = Protect mode

• Example: Response during protect mode (random number section is undefined value) "NTCONTROL 1 23181e1e" (CR)

#### 3) Generate a 32-byte hash value from the following data using MD5 algorithm.

"xxxxx:yyyyy:zzzzzz"

xxxxxx         Administrator rights user name for the web control (default user name is "admin1")	
ууууу	Password of above administrator rights user (default password is "panasonic")
2222222	8-byte random number obtained in Step 2)

#### **Command transmission method**

Transmit using the following command formats.

### Transmitted data

	Header			Data section	Termination symbol
Command	Hash value	ʻ0'	·0'	Control command	(CR)
example	"Connecting" (➡ page 246)	0x30	0x30	(ASCII string)	0x0d
Data length	32 bytes	1 byte	1 byte	Undefined length	1 byte

 Example: Transmission of power supply status acquisition command (hash value is calculated from default user name, password, and acquired random number)
 "dbdd2dabd3d4d68c5dd970ec0c29fa6400QPW" (CR)

# Received data

	Header		Data section	Termination symbol
Command example	'0' 0x30	'0' 0x30	Control command (ASCII string)	(CR) 0x0d
Data length	1 byte	1 byte	Undefined length	1 byte

• Example: The projector is powered on "00001" (CR)

# Error response

	String	Details	Termination symbol
	"ERR1" Undefined control command		
	"ERR2"	Out of parameter range	
Magazara	"ERR3"	Busy state or no-acceptable period	(CR)
Message	"ERR4"	Timeout or no-acceptable period	0x0d
	"ERR5"	Wrong data length	
	"ERRA"	Password mismatch	
Data length	4 bytes	_	1 byte

#### When web control administrator rights password is not set (Non-protect mode)

#### Connecting

1) Obtain the IP address and port number (Initial set value = 1024) of the projector and request a connection to the projector.

• You can obtain both the IP address and the port number from the menu screen of the projector.

IP address	Obtain from the [NETWORK] menu $\rightarrow$ [NETWORK STATUS].	
Port number	Obtain from the [NETWORK] menu $\rightarrow$ [NETWORK CONTROL] $\rightarrow$ [COMMAND PORT].	

#### 2) Check the response from the projector.

	Data section	Blank	Mode	Termination symbol
Command	"NTCONTROL"	£ 3	·0'	(CR)
example	(ASCII string)	0x20	0x30	0x0d
Data length	9 bytes	1 byte	1 byte	1 byte

- Mode: 0 = Non-protect mode
- Example: Response during non-protect mode "NTCONTROL 0" (CR)

# Command transmission method

Transmit using the following command formats.

# Transmitted data

	Header		Data section	Termination symbol
Command	ʻ0'	ʻ0'	Control command	(CR)
example	0x30	0x30	(ASCII string)	0x0d
Data length	1 byte	1 byte	Undefined length	1 byte

• Example: Transmission of power supply status acquisition command "00QPW" (CR)

# Received data

	Header		Data section	Termination symbol
Command	·O'	ʻ0'	Control command	(CR)
example	0x30	0x30	(ASCII string)	0x0d
Data length	1 byte	1 byte	Undefined length	1 byte

• Example: The power of the projector is in standby status "00000" (CR)

# Error response


	String	Details	Termination symbol
	"ERR1" Undefined control command		
	"ERR2"	Out of parameter range	
Magaaga	"ERR3"	Busy state or no-acceptable period	(CR)
Message	"ERR4"	Timeout or no-acceptable period	0x0d
	"ERR5"	Wrong data length	
	"ERRA"	Password mismatch	
Data length	4 bytes	—	1 byte

# SERIAL IN>/<SERIAL OUT> terminal

The <SERIAL IN>/<SERIAL OUT> terminal of the projector conforms with RS-232C so that the projector can be connected to and controlled from a computer.

# Connection

#### Single projector



- The destination of [RS-232C] (+ page 175) must be set according to the connection method.
- To control the projector with standby mode when connecting utilizing the DIGITAL LINK compatible device, set the [PROJECTOR SETUP] menu → [STANDBY MODE] (→ page 168) to [NORMAL].

When [STANDBY MODE] is set to [ECO], the projector cannot be control during standby.

#### Pin assignments and signal names

D-Sub 9-pin (female) Outside view	Pin No.	Signal name	Details
	(1)	_	NC
(6) → (9)	(2)	TXD	Transmitted data
	(3)	RXD	Received data
	(4)	_	NC
	(5)	GND	Earth
	(6)	_	NC
	(7)	CTS	
(1) → (5)	(8)	RTS	Connected internally
	(9)	—	NC

#### Chapter 7 Appendix — Technical information


D-Sub 9-pin (male) Outside view	Pin No.	Signal name	Details
	(1)	—	NC
(9) 🔶 (6)	(2)	RXD	Received data
	(3)	TXD	Transmitted data
	(4)	—	NC
	(5)	GND	Earth
	(6)	—	NC
	(7)	RTS	Connected internally
(5) 🔶 (1)	(8)	CTS	Connected internally
	(9)	—	NC

# **Communication conditions (Factory default)**


Signal level	RS-232C-compliant
Sync. method	Asynchronous
Baud rate	9 600 bps
Parity	None
Character length	8 bits
Stop bit	1 bit
X parameter	None
S parameter	None

# **Basic format**

Transmission from the computer starts with STX, then the ID, command, parameter, and ETX are sent in this order. Add parameters according to the details of control.



# Basic format (has subcommands)



\*1 When transmitting a command which does not need a parameter, an operation (E) and parameter are not necessary.

# 250 - ENGLISH

#### Attention

- If a command is sent after the light source starts lighting, there may be a delay in response or the command may not be executed. Try
  sending or receiving any command after 60 seconds.
- When transmitting multiple commands, be sure to wait until 0.5 seconds has elapsed after receiving the response from the projector before sending the next command. When transmitting a command which does not need a parameter, a colon (:) is not necessary.

#### Note

- If a command cannot be executed, the "ER401" response is sent from the projector to the computer.
- If an invalid parameter is sent, the "ER402" response is sent from the projector to the computer.
- ID transmission in RS-232C supports ZZ (ALL) and 01 to 64, as well as 0A to 0Z groups.
- If a command is sent with an ID designated, a response will be sent to the computer only in the following cases.
- It matches the projector ID
- ID is designated as ALL and [RESPONSE(ID ALL)] is set to [ON]
- ID is designated as GROUP and [RESPONSE(ID GROUP)] is set to [ON]
- STX and ETX are character codes. STX shown in hexadecimal is 02, and ETX shown in hexadecimal is 03.

#### When multiple projectors are controlled

#### When multiple projectors are all controlled

When controlling multiple projectors together via RS-232C, perform the following settings.

- 1) Set a different ID for each projector.
- 2) Set [RESPONSE(ID ALL)] to [ON] in only one projector.
- 3) Set [RESPONSE(ID ALL)] to [OFF] for all other projectors set in Step 2).

#### When multiple projectors are all controlled by group unit

When controlling multiple projectors by group unit via RS-232C, perform the following settings.

- 1) Set a different ID for each projector.
- 2) Set the same setting for [GROUP] in each group.
- 3) Set [RESPONSE(ID GROUP)] to [ON] in only one projector.
- 4) Set [RESPONSE(ID GROUP)] to [OFF] for all other projectors set in Step 3).


#### Note

· Response is not made correctly if [RESPONSE(ID ALL)] is set to [ON] in two or more projectors.


- When setting multiple groups, set [RESPONSE(ID GROUP)] to [ON] in only one projector in each group.
   Response is not made correctly if [RESPONSE(ID GROUP)] is set to [ON] in two or more projectors of the same group.

#### **Cable specification**

#### When connected to a computer



#### When multiple projectors are connected



#### **Control command**

The following table lists the commands that can be used to control the projector using a computer.

#### Projector control command

Command	Details	Parameter/response string	Remark (parameter)
PON	Power on		To check if the power is on, use the "Power query" command.
POF	Power standby	—	To check if the power is on, use the Power query command.
QPW	Power query	000	STANDBY
<b>⊲</b> (1 ¥ ¥		001	Power on
		SD1	SDI1
		SD2	SDI2
		SD3	SDI3
		SD4	SDI4
		DL1	DIGITAL LINK
		AU1,SD1*1	SDI1 [SLOT1]
		AU1,SD2*1	SDI2 [SLOT1]
		AU1,SD3 <sup>*2</sup>	SDI3 [SLOT1]
		AU1,SD4*2	SDI4 [SLOT1]
		AU2,SD1*3	SDI1 [SLOT2]
		AU2,SD2 <sup>*3</sup>	SDI2 [SLOT2]
	Switching the input	AU2,SD3*4	SDI3 [SLOT2]
IIS	Switching the input signal	AU2,SD4*4	SDI4 [SLOT2]
		AU1,HD1 <sup>*1</sup>	HDMI1 [SLOT1]
		AU1,HD2 <sup>*1</sup>	HDMI2 [SLOT1]
		AU2,HD3 <sup>*4</sup>	HDMI3 [SLOT2]
		AU2,HD4 <sup>*4</sup>	HDMI4 [SLOT2]
		AU1,DV1 <sup>*1</sup>	DVI-D1 [SLOT1]
		AU1,DV2 <sup>*1</sup>	DVI-D2 [SLOT1]
		AU2,DV3*4	DVI-D3 [SLOT2]
		AU2,DV4*4	DVI-D4 [SLOT2]
		AU1,DP1 <sup>*1</sup>	DisplayPort1 [SLOT1]
		AU1,DP2 <sup>*1</sup>	DisplayPort2 [SLOT1]
		AU2,DP3 <sup>*4</sup>	DisplayPort3 [SLOT2]
		AU2,DP4 <sup>*4</sup>	DisplayPort4 [SLOT2]
OSH	Shutter control	0	OPEN
QSH	Shutter status query	1	CLOSE
VSE	Aspect ratio switch	0	DEFAULT
		1	4:3
		2	16:9
		5	THROUGH
	Aspect ratio settings query	6	HV FIT
QSE		9	H FIT
		10	V FIT
OCS	Sub memory switch		
QSB	Sub memory status query	01 - 96	Sub memory number

\*1 This can be used when the optional Interface Board equipped with corresponding input is installed in <SLOT 1>.

\*2 This can be used when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 1>.

\*3 This can be used when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in <SLOT 2>.

\*4 This can be used when the optional Interface Board equipped with corresponding input is installed in <SLOT 2>.

#### Projector control command (with sub command)

Command	Sub command	Details	Remark
VXX	MDMI1	Execute MULTI DISPLAY	
QVX	MDMI1	MULTI DISPLAY MODE query	+00000 = OFF, +00001 = USER1, +00002 = USER2, +00003 = USER3


#### Lens control command

Command	Sub command	Details	Remark
VXX	LNSI2	Lens H shift	
VXX	LNSI3		+00000 = Fine adjustment 1+, +00001 = Fine adjustment 1-, +00100
VXX	LNSI4	L one feelle	= Fine adjustment 2+, +00101 = Fine adjustment 2-, +00200 = Coarse adjustment+, +00201 = Coarse adjustment-
VXX	LNSI5	Lens zoom	

## <REMOTE 2 IN> terminal

It is possible to control the projector remotely (by external contact) from a control panel located away from the projector where remote control signals cannot reach.

Use the <REMOTE 2 IN> terminal on the connecting terminals of the projector to connect to the control panel.



Installation locations in meeting rooms, etc.

Remote control board in another location

### Pin assignments and signal names

D-Sub 9-pin Outside view	Pin No.	Signal name	Open (H)	Short (L)
	(1)	GND	_	GND
	(2)	POWER	OFF	ON
$(6) \rightarrow (9)$	(3)	SDI1	Other	SDI1
	(4)	SDI2	Other	SDI2
	(5)	SDI3	Other	SDI3
	(6)	SDI4	Other	SDI4
	(7)	DIGITAL LINK	Other	DIGITAL LINK
$(1) \rightarrow (5)$	(8)	SHUTTER	OFF	ON
	(9)	ENABLE / DISABLE	Controlled by remote control	Controlled by external contact

#### Attention

- When controlling, make sure to short-circuit pins (1) and (9).
- When pins (1) and (9) are short-circuited, the following buttons on the control panel and the remote control are disabled. Commands for RS-232C and network functions corresponding to these functions are also disabled.
- Power on <I> button, power standby <</li>
   button, <SHUTTER> button
   When pins (1) and (9) are short-circuited, and then any pins from (3) to (7) and the pin (1) are short-circuited, the following buttons on the control panel and the remote control are disabled. Commands for RS-232C and network functions corresponding to these functions are also disabled.

Power on <1> button, power standby <0> button, <DIGITAL LINK> button, <DVI-D> button, <HDMI> button, <SDI> button, <SDI 1/2> button, <SDI 3/4> button, <DISPLAYPORT> button, <SLOT 1> button, <SLOT 2> button, <INPUT MENU> button, <SHUTTER> button

Note

```
• For pin (2) to pin (8) settings, you can make changes if you set [REMOTE2 MODE] to [USER]. (+ page 176)
```

# Control device password

To initialize your password, consult your distributor.

# Upgrade Kit

If the optional Upgrade Kit (Model No.: ET-UK20) is applied, the following functions are extended.

Function	Standard status	When the Upgrade Kit is applied
Adjustment range of [VERTICAL KEYSTONE]	Maximum of ±40°*1	Maximum of ±45°*1
Adjustment range of [HORIZONTAL KEYSTONE]	Maximum of ±15°*1	Maximum of ±40°*1
Adjustment range of [CURVED CORRECTION]	Vertical arc, Maximum ±50*1 Horizontal arc, Maximum ±50*1	Vertical arc, Maximum ±100 <sup>*1</sup> Horizontal arc, Maximum ±100 <sup>*1</sup>
[CUSTOM MASKING]	Cannot be used.	The image is masked in optional form.
[PC CORRECTION] of [UNIFORMITY]	Cannot be used.	Correct the brightness and color unevenness of the entire screen.

\*1 The adjustment range of the menu. Refer to "[GEOMETRY] projection range" (+ page 43) for the possible projection range.

# List of compatible signals

The following table specifies the video signals that the projector can project.

For details of DisplayPort signal, refer to "List of DisplayPort compatible signals" (> page 260).

For details of SDI signal, refer to "List of single link SDI compatible signals" (+ page 262), "List of dual link SDI

compatible signals" (➡ page 267), "List of quad link SDI compatible signals" (➡ page 271).

This projector supports the signal with  $\checkmark$  in the compatible signal column.

- The content of the compatible signal column is as follows.
  - 1: Single link (displays one image using one input signal.)
  - 2: Dual link (displays one image using two input signals.)
  - 3: Quad link (displays one image using four input signals.)

Scanning freq. Compatible signal											
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	Dot clock freq. (MHz)	DIGITAL LINK		HDMI*1			DVI-D*2	
		(1112)	(112)	(,	1	1	2	3	1	2	3
480/60i	720 (1 440) x 480i*3	15.7	59.9	27.0	<ul> <li>✓</li> </ul>	1			1		
576/50i	720 (1 440) x 576i*3	15.6	50.0	27.0	1	1			1	_	—
480/60p	720 x 480	31.5	59.9	27.0	1	1			1		
576/50p	720 x 576	31.3	50.0	27.0	1	1			1	-	—
720/60p	1 280 x 720	45.0	60.0	74.3	1	1			1	-	—
720/50p	1 280 x 720	37.5	50.0	74.3	1	1	_	_	1	—	—
1080/60i	1 920 x 1 080i	33.8	60.0	74.3	1	1			1		—
1080/50i	1 920 x 1 080i	28.1	50.0	74.3	1	1	_	_	1	_	—
1080/24p	1 920 x 1 080	27.0	24.0	74.3	1	1	—	_	1	_	_
1080/24sF	1 920 x 1 080i	27.0	48.0	74.3	1	1	—	—	1	_	—
1080/25p	1 920 x 1 080	28.1	25.0	74.3	1	1	—	—	1	_	—
1080/30p	1 920 x 1 080	33.8	30.0	74.3	1	1	—	_	1	_	_
1080/60p	1 920 x 1 080	67.5	60.0	148.5	1	1	_	_	1	_	_
1080/50p	1 920 x 1 080	56.3	50.0	148.5	1	1	_	_	1	_	_
2K/24p	2 048 x 1 080	27.0	24.0	74.3	1	1	_	_	1	_	_
2K/25p	2 048 x 1 080	28.1	25.0	74.3	1	1	_	_	1	_	_
2K/30p	2 048 x 1 080	33.8	30.0	74.3	1	1	_	_	1	_	_
2K/48p	2 048 x 1 080	54.0	48.0	148.5	1	1	_	_	1	_	_
2K/60p	2 048 x 1 080	67.5	60.0	148.5	1	1	_	_	1	_	_
2K/50p	2 048 x 1 080	56.3	50.0	148.5	1	1	_	_	1	_	
3840 x 2160/24p	3 840 x 2 160	54.0	24.0	297.0	1	1	1	1	_	1	1
3840 x 2160/25p	3 840 x 2 160	56.3	25.0	297.0	1	1	1	1	_	1	1
3840 x 2160/30p	3 840 x 2 160	67.5	30.0	297.0	1	1	1	1	_	1	1
	3 840 x 2 160	135.0	60.0	297.0	<b>√</b> *4	∕*4	_	_	_	_	
3840 x 2160/60p	3 840 x 2 160	135.0	60.0	594.0	_	1	1	1	_	_	1
	3 840 x 2 160	112.5	50.0	297.0	✓*4	∕*4	_	_	_	_	
3840 x 2160/50p	3 840 x 2 160	112.5	50.0	594.0	_	1	1	1	_	_	1
4096 x 2160/24p	4 096 x 2 160	54.0	24.0	297.0	1	1	1	1	_	1	1
4096 x 2160/25p	4 096 x 2 160	56.3	25.0	297.0	1	1	1	1	_	1	1
4096 x 2160/30p	4 096 x 2 160	67.5	30.0	297.0	1	1	1	1	_	1	1
	4 096 x 2 160	135.0	60.0	297.0	✓*4	∕*4	_	_	_	_	_
4096 x 2160/60p	4 096 x 2 160	135.0	60.0	594.0	_	1	1	1	_	_	1
	4 096 x 2 160	112.5	50.0	297.0	✓*4	∕*4	_	_	_	_	_
4096 x 2160/50p	4 096 x 2 160	112.5	50.0	594.0	_	· ·	1	1	_	_	1
640 x 400/70	640 x 400	31.5	70.1	25.2	1	1	_	_	1	_	
640 x 400/85	640 x 400	37.9	85.1	31.5	✓ ✓	1			<i>\</i>	_	_
640 x 480/60	640 x 480	31.5	59.9	25.2	· ·	1	_		<i>\</i>	_	_
640 x 480/67	640 x 480	35.0	66.7	30.2	· ·	1		_	· ·	_	
640 x 480/73	640 x 480	37.9	72.8	31.5	· ·	<i>✓</i>			· ·	_	
640 x 480/75	640 x 480	37.5	75.0	31.5	· ·	1		_	· ·	_	
640 x 480/85	640 x 480	43.3	85.0	36.0	✓ ✓	<i>✓</i>			✓ ✓	_	
800 x 600/56	800 x 600	35.2	56.3	36.0	✓ ✓	<i>✓</i>		_	✓ ✓	_	
000 x 000/00		00.2	00.0	00.0	v	<b>v</b>	I		•		

		Scannii	ng freq.	Detail	Compatible signal						
Signal name	Resolution	Horizontal	Vertical	Dot clock freq.	DIGITAL		HDMI*1			DVI-D*2	
(SIGNAL FORMAT)	(Dots)	(kHz)	(Hz)	(MHz)	LINK 1	1	2	3	1	2	3
800 x 600/60	800 x 600	37.9	60.3	40.0			_	_		_	_
800 x 600/72	800 x 600	48.1	72.2	50.0	1	1	_	_	1	_	<u> </u>
800 x 600/75	800 x 600	46.9	75.0	49.5	1	1	_	_	1	_	<u> </u>
800 x 600/85	800 x 600	53.7	85.1	56.3	1	✓		_	1	_	_
832 x 624/75	832 x 624	49.7	74.6	57.3	· ·	· ·	_	_	· ·	_	_
1024 x 768/50	1 024 x 768	39.6	50.0	51.9	· ·	<i>\</i>	_	_	· ·	_	_
1024 x 768/60	1 024 x 768	48.4	60.0	65.0	· ·	· ·	_	_	· ·	_	_
1024 x 768/70	1 024 x 768	56.5	70.1	75.0	<i>✓</i>	√ 		_	· ·	_	_
1024 x 768/75	1 024 x 768	60.0	75.0	78.8	· ·	· ·		_	· ·	_	<b>—</b>
1024 x 768/82	1 024 x 768	65.5	81.6	86.0	· ·	· ·		_	· ·	_	_
1024 x 768/85	1 024 x 768	68.7	85.0	94.5	· ·	· ·		_	· ·	_	<u> </u>
1024 x 768/100	1 024 x 768	81.4	100.0	113.3	✓ ✓	<i>·</i>					_
1024 x 768/120	1 024 x 768	98.8	120.0	139.1	✓ ✓	<i>·</i>					
1152 x 864/60	1 152 x 864	53.7	60.0	81.6	✓ ✓	✓ ✓			✓ ✓		
1152 x 864/70	1 152 x 864	64.0	70.0	94.2	✓ ✓	✓ ✓			✓ ✓		
1152 x 864/75	1 152 x 864	67.5	75.0	108.0	✓ ✓	✓ ✓			1		
		77.1				✓ ✓					-
1152 x 864/85	1 152 x 864		85.0	119.7		-					-
1152 x 870/75	1 152 x 870	68.7	75.1	100.0		1				-	<u> </u>
1280 x 720/50	1 280 x 720	37.1	49.8	60.5		<i>\</i>				-	
1280 x 720/60	1 280 x 720	44.8	59.9	74.5	<ul> <li>✓</li> </ul>	<i>\</i>	—			-	
1280 x 720/100	1 280 x 720	76.3	100.0	131.8	✓ ✓	<i>\</i>	—			-	
1280 x 720/120	1 280 x 720	92.6	120.0	161.6	<ul> <li>✓</li> </ul>	<ul> <li>Image: A start of the start of</li></ul>			<ul> <li>✓</li> </ul>	<u> </u>	-
1280 x 768/50	1 280 x 768	39.6	49.9	65.3	<ul> <li>✓</li> </ul>	<ul> <li>Image: A start of the start of</li></ul>			<ul> <li>✓</li> </ul>	<u> </u>	
1280 x 768/60	1 280 x 768	47.8	59.9	79.5	<ul> <li>✓</li> </ul>	✓ ✓				<u> </u>	
	1 280 x 768 <sup>*5</sup>	47.4	60.0	68.3	<ul> <li>✓</li> </ul>	✓ ✓				<u> </u>	
1280 x 768/75	1 280 x 768	60.3	74.9	102.3	<ul> <li>✓</li> </ul>	✓ ✓	—			-	
1280 x 768/85	1 280 x 768	68.6	84.8	117.5	✓	1	—		<ul> <li>Image: A state of the state of</li></ul>	-	<u> </u>
1280 x 800/50	1 280 x 800	41.3	50.0	68.0	<ul> <li>✓</li> </ul>	1	—			-	
1280 x 800/60	1 280 x 800	49.7	59.8	83.5	1	1			<ul> <li>✓</li> </ul>		
	1 280 x 800 <sup>*5</sup>	49.3	59.9	71.0	1	1				<u> </u>	
1280 x 800/75	1 280 x 800	62.8	74.9	106.5	<ul> <li>✓</li> </ul>	1			<ul> <li>✓</li> </ul>	<u> </u>	
1280 x 800/85	1 280 x 800	71.6	84.9	122.5	1	1			<ul> <li>✓</li> </ul>		
1280 x 960/60	1 280 x 960	60.0	60.0	108.0	1	1			<ul> <li>✓</li> </ul>		
1280 x 1024/50	1 280 x 1 024	52.4	50.0	88.0	1	1			<ul> <li>✓</li> </ul>	<u> </u>	
1280 x 1024/60	1 280 x 1 024	64.0	60.0	108.0	1	1			<ul> <li>✓</li> </ul>	<u> </u>	
1280 x 1024/66	1 280 x 1 024	72.3	66.3	125.0	1	1			<ul> <li>✓</li> </ul>	<u> </u>	
1280 x 1024/72	1 280 x 1 024	78.2	72.0	135.1	1	1			<ul> <li>✓</li> </ul>		
1280 x 1024/75	1 280 x 1 024	80.0	75.0	135.0	1	1			<ul> <li>✓</li> </ul>		
1280 x 1024/85	1 280 x 1 024	91.1	85.0	157.5	1	1			1		
1366 x 768/50	1 366 x 768	39.6	49.9	69.0	1	$\checkmark$			1		
1366 x 768/60	1 366 x 768	47.7	59.8	85.5	1	$\checkmark$			1	<u> </u>	
1400 x 1050/50	1 400 x 1 050	54.1	50.0	99.9	1	1			✓		
F	1 400 x 1 050	64.0	60.0	108.0	1	1			1	<u> </u>	<u> </u>
1400 x 1050/60	1 400 x 1 050	65.3	60.0	121.8	1	1			1	<u> </u>	<u> </u>
	1 400 x 1 050	65.2	60.0	122.6	1	1			1		
1400 x 1050/72	1 400 x 1 050	78.8	72.0	149.3	1	1			1		<u> </u>
1400 x 1050/75	1 400 x 1 050	82.2	75.0	155.9	1	1			1		
1440 x 900/50	1 440 x 900	46.3	49.9	86.8	1	~		_	1		
1440 x 900/60	1 440 x 900	55.9	59.9	106.5	1	$\checkmark$	—	_	1		
1600 x 900/50	1 600 x 900	46.4	49.9	96.5	1	1	_	_	1	_	
1600 x 900/60	1 600 x 900	55.9	60.0	119.0	1	1	_	_	1	_	_
1600 x 1200/50	1 600 x 1 200	61.8	49.9	131.5	1	1	_	_	1	_	_
1600 x 1200/60	1 600 x 1 200	75.0	60.0	162.0	1	1	_	_	1	_	_

Chapter 7 Appendix — Technical information

		Scannii	ng freq.				Com	patible s	signal		
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal	Vertical	Dot clock freq. (MHz)	DIGITAL LINK		HDMI*1		DVI-D*2		
		(kHz)	(Hz)	(10112)	1	1	2	3	1	2	3
1680 x 1050/50	1 680 x 1 050	54.1	50.0	119.5	<ul> <li>Image: A set of the set of the</li></ul>	$\checkmark$	—	_	1	-	—
1680 x 1050/60	1 680 x 1 050	65.3	60.0	146.3	<ul> <li>Image: A set of the set of the</li></ul>	1	_	_	1	_	_
1920 x 1080/50	1 920 x 1 080	55.6	49.9	141.5	<ul> <li>✓</li> </ul>	$\checkmark$	_	_	1	_	_
1000 × 1000/00	1 920 x 1 080⁵⁵	66.6	59.9	138.5	<ul> <li>Image: A set of the set of the</li></ul>	1	_	_	1	_	_
1920 x 1080/60	1 920 x 1 080	67.2	60.0	173.0	<	1	—	_	—	_	—
1920 x 1200/50	1 920 x 1 200	61.8	49.9	158.3	<	$\checkmark$	—	—	1	_	—
1920 x 1200/60	1 920 x 1 200	74.6	59.9	193.3	<	$\checkmark$	—	—	—	—	—
1920 x 1200/60RB	1 920 x 1 200*5	74.0	60.0	154.0	<	$\checkmark$	—	—	1	—	—
2560 x 1600/50	2 560 x 1 600	82.4	50.0	286.0	<	1	_	—	—	_	—
2560 x 1600/60	2 560 x 1 600*₅	98.7	60.0	268.5	<	$\checkmark$	_	_	—	_	—
3840 x 2400/30	3 840 x 2 400*5	73.0	30.0	286.2	<	1	_	_	_	_	_
3840 x 2400/60	3 840 x 2 400	148.1	60.0	616.0	—	_	_	1	_	_	1
3840 x 2400/60	3 840 x 2 400*5	148.1	60.0	592.5	—	1	_	_	_	_	_
3840 x 2400/50	3 840 x 2 400	123.6	49.9	633.0	_	_	_	1	_	_	1
3840 x 2400/50	3 840 x 2 400*5	122.9	50.0	481.6	_	1	_	_	_	_	_

Chapter 7 Appendix — Technical information

\*1 This is supported when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in the slot. Quad link is supported only when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed on both <SLOT 1> and <SLOT 2>.

\*2 This is supported when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in the slot. Quad link is supported only when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed on both <SLOT 1> and <SLOT 2>.

- \*3 Pixel-Repetition signal (dot clock frequency 27.0 MHz) only
- \*4 YP<sub>B</sub>P<sub>R</sub> 4:2:0 format only
- \*5 VESA CVT-RB (Reduced Blanking)-compliant

#### Note

• A signal with a different resolution is converted to the number of display dots. The number of display dots is as follows.

- When the [ADVANCED MENU] menu  $\rightarrow$  [QUAD PIXEL DRIVE] is set to [ON]: 5 120 x 3 200

- When the [ADVANCED MENU] menu  $\rightarrow$  [QUAD PIXEL DRIVE] is set to [OFF]: 2 560 x 1 600

• The "i" at the end of the resolution indicates an interlaced signal.

• When interlaced signals are connected, flickering may occur on the projected image.

### List of plug and play compatible signals

The following table specifies the video signals compatible with plug and play.

Signal with  $\checkmark$  in the plug and play compatible signal column is the signal described in the EDID (extended display identification data) of the projector. For the signal without  $\checkmark$  in the plug and play compatible signal column, the resolution may not be selected on the computer even if the projector is supporting it.

Signal name	Resolution		ning eq.	Dot clock			Plug	and pla	iy comp	atible s	signal		
(SIGNAL FORMAT)	(Dots)	Horizontal	Vertical	freq.	DIC	GITAL LI	NK		HDMI*1			DVI-D*2	
		(kHz)	(Hz)	(MHz)	4K/60p	4K/30p	2K	4K/60p*3	4K/30p	2K	EDID1	EDID2	EDID3
480/60i	720 (1 440) x 480i*4	15.7	59.9	27.0	_	_	_		_	—	_	_	_
576/50i	720 (1 440) x 576i*4	15.6	50.0	27.0	_	_	_	_	_	_		_	_
480/60p	720 x 480	31.5	59.9	27.0	<ul> <li>✓</li> </ul>	1	1	1	1	$\checkmark$	1	_	1
576/50p	720 x 576	31.3	50.0	27.0	1	1	$\checkmark$	1	1	$\checkmark$	1	—	1
720/60p	1 280 x 720	45.0	60.0	74.3	1	~	1	1	~	1	1	—	<ul> <li>✓</li> </ul>
720/50p	1 280 x 720	37.5	50.0	74.3	1	~	1	1	~	✓	1	_	<ul> <li>✓</li> </ul>
1080/60i	1 920 x 1 080i	33.8	60.0	74.3	1	1	1	1	1	1	1	_	1
1080/50i	1 920 x 1 080i	28.1	50.0	74.3	1	1	1	1	1	1	1	_	1
1080/24p	1 920 x 1 080	27.0	24.0	74.3	1	1	1	1	1	1	1	_	1
1080/24sF	1 920 x 1 080i	27.0	48.0	74.3	_	_	_	_	_	_	—	_	
1080/25p	1 920 x 1 080	28.1	25.0	74.3	1	1	1	1	1	1	1	_	1
1080/30p	1 920 x 1 080	33.8	30.0	74.3	1	1	1	1	1	1	1	_	1
1080/60p	1 920 x 1 080	67.5	60.0	148.5			1	1		1	1	_	
1080/50p	1 920 x 1 080	56.3	50.0	148.5		· ·	1	· ·	· ·		· ·	_	
2K/24p	2 048 x 1 080	27.0	24.0	74.3	_	_	_	_	_	_			_
2K/25p	2 048 x 1 080	28.1	25.0	74.3	_	_	_	_	_		<u> </u>	_	
2K/30p	2 048 x 1 080	33.8	30.0	74.3	_	_	_	_	_		<u> </u>	_	
2K/48p	2 048 x 1 080	54.0	48.0	148.5	_	_		_	_	_	<u> </u>	_	
2K/60p	2 048 x 1 080	67.5	60.0	148.5	_	_		_	_	_		_	
2K/50p	2 048 x 1 080	56.3	50.0	148.5	_	_		_	_		_	_	
3840 x 2160/24p	3 840 x 2 160	54.0	24.0	297.0	1	1		1	1	_		_	
3840 x 2160/25p	3 840 x 2 160	56.3	25.0	297.0		· ·			· ·	_	<u> </u>	_	
3840 x 2160/30p	3 840 x 2 160	67.5	30.0	297.0		· ·		· ·	· ·		_		
	3 840 x 2 160	135.0	60.0	297.0	✓ ✓*5		_	✓*5		_	<u> </u>		
3840 x 2160/60p	3 840 x 2 160	135.0	60.0	594.0				✓ - ✓			<u> </u>		
	3 840 x 2 160	112.5	50.0	297.0	<b>√</b> *5			✓ ✓*5					
3840 x 2160/50p	3 840 x 2 160	112.5	50.0	594.0	<b>∨</b> <sup>3</sup>					_		_	
4096 x 2160/24p	4 096 x 2 160	54.0	24.0	297.0		_		-	_	_			<u> </u>
· · ·										_			
4096 x 2160/25p	4 096 x 2 160	56.3	25.0	297.0			_			_			—
4096 x 2160/30p	4 096 x 2 160	67.5	30.0	297.0						_	-	-	
4096 x 2160/60p	4 096 x 2 160	135.0	60.0	297.0	✓*5	—	_	✓*5		_	-		
	4 096 x 2 160	135.0	60.0	594.0		—	_	✓ ✓		_	-		
4096 x 2160/50p	4 096 x 2 160	112.5	50.0	297.0	✓*5		_	<b>√</b> *5		_	<u> </u>		
	4 096 x 2 160	112.5	50.0	594.0		—		<ul> <li>✓</li> </ul>	_	_	—		
640 x 400/70	640 x 400	31.5	70.1	25.2		—	_	<u> </u>		—	<u> </u>		
640 x 400/85	640 x 400	37.9	85.1	31.5		—		<u> </u>			<u> </u>	_	
640 x 480/60	640 x 480	31.5	59.9	25.2		1	1	<ul> <li>✓</li> </ul>	1	1			
640 x 480/67	640 x 480	35.0	66.7	30.2	-						<u>                                     </u>	—	
640 x 480/73	640 x 480	37.9	72.8	31.5		<ul> <li>Image: A state of the state of</li></ul>	✓ ✓	✓ ✓	<ul> <li>Image: A state of the state of</li></ul>	<u> </u>	-		
640 x 480/75	640 x 480	37.5	75.0	31.5	<ul> <li>✓</li> </ul>		1		1	1	<u> </u>		
640 x 480/85	640 x 480	43.3	85.0	36.0	-	—	_	-	—	_	<u> </u>	-	-
800 x 600/56	800 x 600	35.2	56.3	36.0		1	1	1	<ul> <li>Image: A state of the state of</li></ul>	~	—		<b>√</b>
800 x 600/60	800 x 600	37.9	60.3	40.0	<ul> <li>✓</li> </ul>	1	1	1	1	1	-	1	1
800 x 600/72	800 x 600	48.1	72.2	50.0	1	1	1	1	1	$\checkmark$	<u> </u>	1	1
800 x 600/75	800 x 600	46.9	75.0	49.5	1	1	1	1	1	1	<u> </u>	1	1
800 x 600/85	800 x 600	53.7	85.1	56.3		—	—		—	_	—	_	_

(SIGMAL FORMAT)         Normal (Normal)         Normal (Normal)         DIDITIAL LINE         IDUITIAL LINE         ID	Signal name	Resolution		nning eq.	Dot clock			Plug	and pla	ay comp	atible	signal				
B32 x 624/75         B32 x 824         49.7         74.6         57.3         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2         2 <th2< th="">         2</th2<>	•		Horizontal	Vertical		DIGITAL LINK			HDMI*1			DVI-D*2				
1024 x 78950         1 024 x 788         39.6         50.0         51.9         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -           1024 x 788         1			(kHz)	(Hz)	(MHz)	4K/60p	4K/30p	2K	4K/60p*3	4K/30p	2K	EDID1	EDID2	EDID3		
1024 x 788400         1024 x 788         644         60.0         65.0         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓          1024 x 7868	832 x 624/75	832 x 624	49.7	74.6	57.3	1	~	1	1	1	1	—	1	1		
1024 x 768/70         1024 x 768         56.5         70.1         75.0         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         7         1024 x 768         7         88         100         10         7         7         10         7         10         7         10         7         10         7         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10         10	1024 x 768/50	1 024 x 768	39.6	50.0	51.9		—	—		_			_			
1024 x 788/75         1 024 x 788         60.0         75.0         78.8         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         V         <	1024 x 768/60	1 024 x 768	48.4	60.0	65.0	1	~	1	1	1	1		1	1		
1024 x 768/82         1024 x 768         65.5         81.6         96.0	1024 x 768/70	1 024 x 768	56.5	70.1	75.0	1	~	1	1	1	1		1	1		
11024 x 768/50         1024 x 768         88.7         80.0         94.5                                                                            1152 x 86/70         1152 x 86/7         75.0         1080	1024 x 768/75	1 024 x 768	60.0	75.0	78.8	1	1	1	1	1	1	—	1	1		
1024 x 788/100         1024 x 789         81.4         1000         113.3         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -	1024 x 768/82	1 024 x 768	65.5	81.6	86.0	—	—		—	—		—	_			
1024 x 768/120         1024 x 768         98         1200         1391         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓         ✓ <th< td=""><td>1024 x 768/85</td><td>1 024 x 768</td><td>68.7</td><td>85.0</td><td>94.5</td><td></td><td>—</td><td>_</td><td></td><td></td><td></td><td></td><td></td><td></td></th<>	1024 x 768/85	1 024 x 768	68.7	85.0	94.5		—	_								
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	1024 x 768/100	1 024 x 768	81.4	100.0	113.3		—									
1152 x 864/70         1152 x 864         64.0         70.0         94.2         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -          1280 x 72078.0	1024 x 768/120	1 024 x 768	98.8	120.0	139.1	1	1	1	1	1	1		1	<ul> <li>✓</li> </ul>		
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	1152 x 864/60	1 152 x 864	53.7	60.0	81.6		—	_								
1152 x 864/85         1152 x 864         77.1         85.0         119.7         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         <	1152 x 864/70	1 152 x 864	64.0	70.0	94.2	<u> </u>	—		<u> </u>							
1152 x 870/75       1152 x 870       68.7       75.1       100.0       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓       ✓	1152 x 864/75	1 152 x 864	67.5	75.0	108.0		—	_			—		-			
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	1152 x 864/85	1 152 x 864	77.1	85.0	119.7	<u> </u>	—		<u> </u>					—		
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	1152 x 870/75	1 152 x 870	68.7	75.1	100.0	1	1	1	1	1	1		1	1		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	1280 x 720/50	1 280 x 720	37.1	49.8	60.5		—	_			—		-			
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	1280 x 720/60	1 280 x 720	44.8	59.9	74.5	<u> </u>	—									
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	1280 x 720/100	1 280 x 720	76.3	100.0	131.8		—									
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	1280 x 720/120	1 280 x 720	92.6	120.0	161.6	<u> </u>		_	<u> </u>							
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	1280 x 768/50			49.9		<u> </u>			<u> </u>							
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	1280 x 768/60	1 280 x 768	47.8	59.9		<u> </u>	—		<u> </u>			<u> </u>				
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$		1 280 x 768*6	47.4			<u> </u>	—		<u> </u>							
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$			60.3	74.9		<u> </u>			<u> </u>				-			
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	1280 x 768/85	1 280 x 768	68.6	84.8	117.5	-			—	—		<u> </u>		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1280 x 800/50		-			<u> </u>			<u> </u>			<u> </u>		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1280 x 800/60		-			<u> </u>	—	_	<u> </u>			<u> </u>				
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$						<u> </u>			<u> </u>			<u> </u>		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$				-					<u> </u>			<u> </u>		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$					-				<u> </u>	<u> </u>		-		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$						-			<u> </u>	-		-	-	1		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$									-			<u> </u>	-	<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$												-		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$													-	<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		1				-	_	_	-				-			
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$												1		1		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$																
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$							_							1		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$																
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1400 X 1030/30															
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	1400 x 1050/60		1				_									
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1400 x 1030/00		1						1		./	<u> </u>				
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1400 x 1050/72						• —					<u> </u>				
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$						<u> </u>	_		<u> </u>			<u> </u>		<u> </u>		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$							_		1_			_	_	<u> </u>		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$							_		1			1		<u> </u>		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$																
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$																
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$						1		_	<u> </u>	· _	_	1_	· _	<u> </u>		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$								1	1	1	1	_	1	1		
1680 x 1050/60         1 680 x 1 050         65.3         60.0         146.3						· _	-	-	· -	· _	- -	1_	· -	<u> </u>		
1920 x 1080/50         1 920 x 1 080         55.6         49.9         141.5         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -		1				_	_	_	_	_	_	_	_	<u> </u>		
1920 x 1080/60         1 920 x 1 080 <sup>-6</sup> 66.6         59.9         138.5							_	_			_	<u> </u>	_			
1920 x 1080/60 1 920 x 1 080 67.2 60.0 173.0							_	_								
	1920 x 1080/60						_	_				1				
	1920 x 1200/50															

Chapter 7 Appendix — Technical information

Chapter 7	Appendix —	Technical	information
-----------	------------	-----------	-------------

Signal name Resolution		Scanning freq.		Dot clock		Plug and play compatible signal							
(SIGNAL FORMAT)	(Dots)	Horizontal	Vertical	freq.	DIC	DIGITAL LINK		HDMI*1			DVI-D*2		
		(kHz)	(Hz)	(MHz)	4K/60p	4K/30p	2K	4K/60p*3	4K/30p	2K	EDID1	EDID2	EDID3
1920 x 1200/60	1 920 x 1 200	74.6	59.9	193.3	_	—	_		—	_	_	_	_
1920 x 1200/60RB	1 920 x 1 200*6	74.0	60.0	154.0	1	1	1	1	1	1	_	1	~
2560 x 1600/50	2 560 x 1 600	82.4	50.0	286.0	_	—	_	_	—	_	_	_	—
2560 x 1600/60	2 560 x 1 600*6	98.7	60.0	268.5	1	1	_	1	1	_	_	_	_
3840 x 2400/30	3 840 x 2 400*6	73.0	30.0	286.2	_	_	_	_	—	_		_	_
3840 x 2400/60	3 840 x 2 400	148.1	60.0	616.0	_	—	_	—	—	_	_	_	—
3840 x 2400/60	3 840 x 2 400*6	148.1	60.0	592.5	_	_	_		—	_		_	_
3840 x 2400/50	3 840 x 2 400	123.6	49.9	633.0	_	_	_	_	_	_	_	_	_
3840 x 2400/50	3 840 x 2 400*6	122.9	50.0	481.6	_	—	_	—	—	_	_	_	_

\*1 This is supported when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in the slot.

\*2 This is supported when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in the slot.

\*3 4K/60p indicates 4K/60p/SDR and 4K/60p/HDR.

\*4 Pixel-Repetition signal (dot clock frequency 27.0 MHz) only

\*5 YP<sub>B</sub>P<sub>B</sub> 4:2:0 format only

\*6 VESA CVT-RB (Reduced Blanking) compliant

#### List of DisplayPort compatible signals

The following table specifies the DisplayPort signals that the projector can project. This is supported when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in the slot.

Signal with  $\checkmark$  in the plug and play compatible signal column is the signal described in the EDID (extended display identification data) of the projector. For the signal without  $\checkmark$  in the plug and play compatible signal column, the resolution may not be selected on the computer even if the projector is supporting it.

Signal name	Resolution		ning eq.	Dot clock	Plug	ignal	
(SIGNAL FORMAT)	(Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K/60p/HDR 4K/60p/SDR	4K/30p	2K
720/60p	1 280 x 720	45.0	60.0*1	74.3	✓	1	✓
720/50p	1 280 x 720	37.5	50.0	74.3	✓	1	✓
1080/24p	1 920 x 1 080	27.0	24.0*1	74.3	✓	1	✓
1080/25p	1 920 x 1 080	28.1	25.0	74.3	✓	1	<ul> <li>Image: A set of the set of the</li></ul>
1080/30p	1 920 x 1 080	33.8	30.0*1	74.3	1	1	1
1080/60p	1 920 x 1 080	67.5	60.0 <sup>*1</sup>	148.5	1	1	1
1080/50p	1 920 x 1 080	56.3	50.0	148.5	1	1	1
2K/24p	2 048 x 1 080	27.0	24.0*1	74.3	_	_	_
2K/25p	2 048 x 1 080	28.1	25.0	74.3	—	_	—
2K/30p	2 048 x 1 080	33.8	30.0*1	74.3	—	—	—
2K/48p	2 048 x 1 080	54.0	48.0*1	148.5	—	—	—
2K/60p	2 048 x 1 080	67.5	60.0*1	148.5	—	—	—
2K/50p	2 048 x 1 080	56.3	50.0	148.5	—	—	—
3840 x 2160/24p	3 840 x 2 160	54.0	24.0*1	297.0	✓	1	—
3840 x 2160/25p	3 840 x 2 160	56.3	25.0	297.0	<i>✓</i>	1	—
3840 x 2160/30p	3 840 x 2 160	67.5	30.0*1	297.0	✓	1	—
3840 x 2160/60p	3 840 x 2 160	135.0	60.0*1	594.0	✓	—	_
3840 x 2160/50p	3 840 x 2 160	112.5	50.0	594.0	1	_	—
4096 x 2160/24p	4 096 x 2 160	54.0	24.0*1	297.0	1	1	—
4096 x 2160/25p	4 096 x 2 160	56.3	25.0	297.0	1	1	_
4096 x 2160/30p	4 096 x 2 160	67.5	30.0*1	297.0	1	1	—
4096 x 2160/60p	4 096 x 2 160	135.0	60.0 <sup>*1</sup>	594.0	1	_	_
4096 x 2160/50p	4 096 x 2 160	112.5	50.0	594.0	1	_	_
640 x 480/60	640 x 480	31.5	59.9	25.2	1	1	1
1024 x 768/50	1 024 x 768	39.6	50.0	51.9	_	_	—
1024 x 768/60	1 024 x 768	48.4	60.0	65.0	1	1	1
1280 x 800/50	1 280 x 800	41.3	50.0	68.0	_	_	_
1280 x 800/60	1 280 x 800	49.7	59.8	83.5	—	_	_
1400 x 1050/50	1 400 x 1 050	54.1	50.0	99.9	—		—

Chapter 7	Appendix —	Technical	information
-----------	------------	-----------	-------------

Signal name	Resolution		ning eq.	Dot clock	Plug and play compatible signal				
(SIGNAL FORMAT)	(Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K/60p/HDR 4K/60p/SDR	4K/30p	2К		
1400 x 1050/60	1 400 x 1 050	65.2	60.0	122.6	1	✓	1		
1600 x 900/50	1 600 x 900	46.4	49.9	96.5	—	_	—		
1600 x 900/60	1 600 x 900	55.9	60.0	119.0	✓	$\checkmark$	1		
1600 x 1200/50	1 600 x 1 200	61.8	49.9	131.5	—	_	—		
1600 x 1200/60	1 600 x 1 200	75.0	60.0	162.0	✓	✓	1		
1920 x 1200/50	1 920 x 1 200	61.8	49.9	158.3	—	_	—		
1920 x 1200/60RB	1 920 x 1 200*2	74.0	60.0	154.0	—	—	—		
2560 x 1600/50	2 560 x 1 600	82.4	50.0	286.0	—	_	—		
2560 x 1600/60	2 560 x 1 600*2	98.7	60.0	268.5	<i>✓</i>	✓	_		
3840 x 2400/30	3 840 x 2 400*2	73.0	30.0	286.2	_	_	_		
3840 x 2400/60	3 840 x 2 400*2	148.1	60.0	592.5	_	—	—		
3840 x 2400/50	3 840 x 2 400*2	122.9	50.0	481.6	—	—	—		

\*1 The signal with 1/1.001x vertical scanning frequency is also supported.

\*2 VESA CVT-RB (Reduced Blanking)-compliant

#### Note

• A signal with a different resolution is converted to the number of display dots. The number of display dots is as follows.

- When the [ADVANCED MENU] menu  $\rightarrow$  [QUAD PIXEL DRIVE] is set to [ON]: 5 120 x 3 200

- When the [ADVANCED MENU] menu  $\rightarrow$  [QUAD PIXEL DRIVE] is set to [OFF]: 2 560 x 1 600

• If connecting the projector to a computer that uses an early-type chipset or graphics card compatible with DisplayPort, the projector or computer may not be operated properly when the signal output from DisplayPort on the computer is input to the projector. In such a case, switch off the projector or computer and then switch it on.

If the signal output from DisplayPort is input to the projector, use of the computer equipped with the latest chipset or graphics card is recommended.

## List of single link SDI compatible signals

The following table specifies the single link SDI signals that the projector can project.

This is the list of compatible signals including the input of the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) installed in the slot, in addition to the standard SDI input.

• The content of the 4K division column is as follows.

- SQ: Square (transmission format of Square Division)

- IL: Interleave (transmission format of 2-Sample Interleave Division)

0.1	Deschatter	Scanni	ng freq.	Dot clock	414			
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
480/60i	720 x 480i	15.7	59.9	27.0	—	SD-SDI	YC <sub>B</sub> C <sub>R</sub>	4:2:2 10bit
576/50i	720 x 576i	15.6	50.0	27.0	_	SD-SDI	YC <sub>B</sub> C <sub>R</sub>	4:2:2 10bit
720/60p	1 280 x 720	45.0	60.0 <sup>*1</sup>	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
720/50p	1 280 x 720	37.5	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080i	33.8	60.0*1	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0*1	74.3	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/60i	1 920 x 1 080i	33.8	60.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080i	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/50i	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080i	28.1	50.0	74.3	_	3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/24p	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/24sF	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	3G-SDI Level-B	RGB	4:4:4 12bit

Signal name	Decent di	Scanni	ng freq.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
	1 920 x 1 080	28.1	25.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	28.1	25.0	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	28.1	25.0	74.3	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/25p	1 920 x 1 080	28.1	25.0	74.3	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080	28.1	25.0	74.3	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	25.0	74.3		3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	25.0	74.3	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080	28.1	25.0	74.3		3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/25sF	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1000/2001	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3		3G-SDI Level-B	RGB	4:4:4 10bit
		28.1	50.0	74.3		3G-SDI Level-A	+	
	1 920 x 1 080 1 920 x 1 080	33.8	30.0 <sup>*1</sup>	74.3		HD-SDI	RGB	4:4:4 12bit
							YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1080/30p	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080	33.8	30.0*1	74.3	—	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080	33.8	60.0*1	74.3		HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/30sF	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080	33.8	60.0*1	74.3		3G-SDI Level-B	RGB	4:4:4 12bit
	1 920 x 1 080	67.5	60.0*1	148.5		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	67.5	60.0*1	148.5		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
1090/605	1 920 x 1 080*3	67.5	60.0*1	148.5	—	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1080/60p	1 920 x 1 080*3	67.5	60.0*1	148.5		6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080*3	67.5	60.0*1	148.5	—	6G-SDI Type 1	RGB	4:4:4 10bit
	1 920 x 1 080*3	67.5	60.0*1	148.5	—	6G-SDI Type 1	RGB	4:4:4 12bit
	1 920 x 1 080	56.3	50.0	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080	56.3	50.0	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
1000/70	1 920 x 1 080*3	56.3	50.0	148.5		6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1080/50p	1 920 x 1 080*3	56.3	50.0	148.5		6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080*3	56.3	50.0	148.5	_	6G-SDI Type 1	RGB	4:4:4 10bit
	1 920 x 1 080*3	56.3	50.0	148.5		6G-SDI Type 1	RGB	4:4:4 12bit

Chapter 7 Appendix — Technical information

		Scanni	ng freq.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)		Vertical	freq.	4K division	Format	Color format	Sampling
		(kHz)	(Hz)	(MHz)				
	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	27.0	24.0*1	74.3	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/24p	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-B	RGB	4:4:4 10bit
	2 048 x 1 080	27.0	24.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080 2 048 x 1 080 <sup>*2</sup>	27.0 27.0	24.0 <sup>*1</sup> 24.0 <sup>*1</sup>	74.3		3G-SDI Level-B 3G-SDI Level-A	RGB XYZ	4:4:4 12bit 4:4:4 12bit
	2 048 x 1 080 <sup>2</sup> 2 048 x 1 080 <sup>*2</sup>	27.0	24.0	74.3 74.3		3G-SDI Level-A	XYZ	4:4:4 12bit 4:4:4 12bit
	2 048 x 1 080 2 2 048 x 1 080	27.0	24.0	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080 2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	$P_{B}P_{R}$	4:4:4 10bit
	2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-B	$YP_{B}P_{R}$	4:4:4 10bit
	2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080 2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
2K/25p	2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	2 048 x 1 080 2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	RGB	4:4:4 10bit 4:4:4 12bit
	2 048 x 1 080	28.1	25.0	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080*2	28.1	25.0	74.3		3G-SDI Level-A	XYZ	4:4:4 12bit
	2 048 x 1 080 <sup>*2</sup>	28.1	25.0	74.3		3G-SDI Level-A	XYZ	4:4:4 12bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
2K/30p	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 10bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080	33.8	30.0*1	74.3		3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080*2	33.8	30.0*1	74.3		3G-SDI Level-A	XYZ	4:4:4 12bit
	2 048 x 1 080*2	33.8	30.0*1	74.3		3G-SDI Level-B	XYZ	4:4:4 12bit
	2 048 x 1 080*2	54.0	48.0*1	148.5		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
2K/48p	2 048 x 1 080*2	54.0	48.0*1	148.5		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	2 048 x 1 080	67.5	60.0*1	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	2 048 x 1 080	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	2 048 x 1 080*3	67.5	60.0*1	148.5	_	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
2K/60p	2 048 x 1 080*3	67.5	60.0 <sup>*1</sup>	148.5	_	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080*3	67.5	60.0*1	148.5	_	6G-SDI Type 1	RGB	4:4:4 10bit
	2 048 x 1 080*3	67.5	60.0*1	148.5	_	6G-SDI Type 1	RGB	4:4:4 12bit
	2 048 x 1 080	56.3	50.0	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	2 048 x 1 080	56.3	50.0	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	2 048 x 1 080*3	56.3	50.0	148.5	_	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
2K/50p	2 048 x 1 080*3	56.3	50.0	148.5	_	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080*3	56.3	50.0	148.5	_	6G-SDI Type 1	RGB	4:4:4 10bit
	2 048 x 1 080*3	56.3	50.0	148.5	_	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0 <sup>*1</sup>	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
2010 - 0160/01-	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/24p	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
			24.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit

# Chapter 7 Appendix — Technical information

Signal name		Scanni	ng freg.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)		Vertical	freq.	4K division	Format	Color format	Sampling
(SIGNAL FORMAT)	(Dots)	(kHz)	(Hz)	(MHz)	uivision			
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/25p	3 840 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
0040 X 2100/20p	3 840 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/30p	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
0040 X 2 100/00p	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit
3840 x 2160/60p	3 840 x 2 160*3	135.0	60.0*1	594.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
3040 X 2 100/00p	3 840 x 2 160*3	135.0	60.0*1	594.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
3840 x 2160/50p	3 840 x 2 160*3	112.5	50.0	594.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
3640 x 2160/30p	3 840 x 2 160*3	112.5	50.0	594.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/24p	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4090 X 2100/24p	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4006 x 2160/25c	4 096 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/25p	4 096 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit

# Chapter 7 Appendix — Technical information

Signal name	Resolution	Scanni	ng freq.	Dot clock	4K			
Signal name (SIGNAL FORMAT)	(Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	division	Format	Color format	Sampling
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 2	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4006 x 2160/20p	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/30p	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	12G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	12G-SDI Type 1	RGB	4:4:4 12bit
4006 x 2160/60~	4 096 x 2 160*3	135.0	60.0*1	594.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4096 x 2160/60p	4 096 x 2 160*3	135.0	60.0*1	594.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4006 × 2160/50~	4 096 x 2 160*3	112.5	50.0	594.0	SQ	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4096 x 2160/50p	4 096 x 2 160*3	112.5	50.0	594.0	IL	12G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit

Chapter 7 Appendix — Technical information

\*1 The signal with 1/1.001x vertical scanning frequency is also supported.
\*2 The optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is not supported.
\*3 Only the <SDI 1 IN> terminal and the <SDI 3 IN> terminal of the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) are supported.

## List of dual link SDI compatible signals

The following table specifies the dual link SDI signals that the projector can project.

This is the list of compatible signals including the input of the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) installed in the slot, in addition to the standard SDI input.

• The content of the 4K division column is as follows.

- SQ: Square (transmission format of Square Division)

- IL: Interleave (transmission format of 2-Sample Interleave Division)

o: 1		Scanni	ng freq.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
	1 920 x 1 080i	33.8	60.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/60i	1 920 x 1 080i	33.8	60.0 <sup>*1</sup>	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080i	33.8	60.0*1	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080i	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1000/701	1 920 x 1 080i	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/50i	1 920 x 1 080i	28.1	50.0	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080i	28.1	50.0	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1000/04	1 920 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/24p	1 920 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/24sF	1 920 x 1 080i	27.0	48.0*1	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080i	27.0	48.0*1	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	28.1	25.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
(	1 920 x 1 080	28.1	25.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/25p	1 920 x 1 080	28.1	25.0	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	25.0	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/25sF	1 920 x 1 080	28.1	50.0	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080	28.1	50.0	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	33.8	30.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
1000/00-	1 920 x 1 080	33.8	30.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/30p	1 920 x 1 080	33.8	30.0*1	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	30.0*1	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	33.8	60.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4000/00-5	1 920 x 1 080	33.8	60.0 <sup>*1</sup>	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/30sF	1 920 x 1 080	33.8	60.0*1	74.3	_	HD-SDI	RGB	4:4:4 10bit
	1 920 x 1 080	33.8	60.0*1	74.3	_	HD-SDI	RGB	4:4:4 12bit
	1 920 x 1 080	67.5	60.0 <sup>*1</sup>	148.5	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080*2	67.5	60.0*1	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080*2	67.5	60.0*1	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/60p	1 920 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	1 920 x 1 080*2	67.5	60.0*1	148.5	_	3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080*2	67.5	60.0*1	148.5	_	3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-B	RGB	4:4:4 12bit

Circual reserve	Deschutter	Scanni	ng freq.	Dot clock	414			
Signal name SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
	1 920 x 1 080	56.3	50.0	148.5	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	1 920 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	1 920 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
1080/50p	1 920 x 1 080*2	56.3	50.0	148.5		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
·	1 920 x 1 080*2	56.3	50.0	148.5		3G-SDI Level-A	RGB	4:4:4 10bit
	1 920 x 1 080*2	56.3	50.0	148.5		3G-SDI Level-B	RGB	4:4:4 10bit
	1 920 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	RGB	4:4:4 12bit
	1 920 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-B	RGB	4:4:4 12bit
	2 048 x 1 080	27.0	24.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	27.0	24.0*1	74.3		HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/24p	2 048 x 1 080	27.0	24.0*1	74.3		HD-SDI	RGB	4:4:4 10bit
210240	2 048 x 1 080	27.0	24.0*1	74.3		HD-SDI	RGB	4:4:4 12bit
	2 048 x 1 080*2	27.0	24.0*1	74.3		HD-SDI	XYZ	4:4:4 12bit
	2 048 x 1 080 2	28.1	25.0	74.3		HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080	28.1				HD-SDI		4:4:4 10bit 4:4:4 12bit
01/ /05 -			25.0	74.3			YP <sub>B</sub> P <sub>R</sub>	
2K/25p	2 048 x 1 080	28.1	25.0	74.3		HD-SDI	RGB	4:4:4 10bit
	2 048 x 1 080	28.1	25.0	74.3		HD-SDI	RGB	4:4:4 12bit
	2 048 x 1 080*2	28.1	25.0	74.3		HD-SDI	XYZ	4:4:4 12bit
	2 048 x 1 080	33.8	30.0*1	74.3	—	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080	33.8	30.0*1	74.3	_	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/30p	2 048 x 1 080	33.8	30.0*1	74.3		HD-SDI	RGB	4:4:4 10bit
	2 048 x 1 080	33.8	30.0*1	74.3		HD-SDI	RGB	4:4:4 12bit
	2 048 x 1 080*2	33.8	30.0*1	74.3		HD-SDI	XYZ	4:4:4 12bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/48p	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
210400	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-A	RGB	4:4:4 10bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-B	RGB	4:4:4 10bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080*2	54.0	48.0*1	148.5	—	3G-SDI Level-B	RGB	4:4:4 12bit
	2 048 x 1 080*2	56.3	50.0	148.5	—	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080*2	56.3	50.0	148.5		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/50p	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	RGB	4:4:4 10bit
	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-B	RGB	4:4:4 10bit
	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-A	RGB	4:4:4 12bit
	2 048 x 1 080*2	56.3	50.0	148.5	_	3G-SDI Level-B	RGB	4:4:4 12bit
	2 048 x 1 080*2	67.5	60.0*1	148.5	_	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5	_	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	2 048 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5		3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	2 048 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5		3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
2K/60p	2 048 x 1 080*2	67.5	60.0 <sup>*1</sup>	148.5		3G-SDI Level-A	RGB	4:4:4 10bit
21/000		67.5	60.0*1	148.5		3G-SDI Level-A	RGB	4:4:4 10bit 4:4:4 10bit
				140.3				
	2 048 x 1 080 <sup>*2</sup> 2 048 x 1 080 <sup>*2</sup>	67.5	60.0 <sup>*1</sup>	148.5		3G-SDI Level-A	RGB	4:4:4 12bit

Chapter 7 Appendix — Technical information

		Scanni	ng freq.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/24p	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/25p	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	30.0*1	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	56.3	30.0*1	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/30p	3 840 x 2 160*3	56.3	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	56.3	30.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
	3 840 x 2 160*3	135.0	60.0*1	594.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
3840 x 2160/60p	3 840 x 2 160*3	135.0	60.0 <sup>*1</sup>	594.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160*3	112.5	50.0	594.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
3840 x 2160/50p	3 840 x 2 160*3	112.5	50.0	594.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit

Chapter 7 Appendix — Technical information

0. 1	<b>D</b>	Scanni	ng freq.	Dot clock				
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/24p	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	54.0	24.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/25p	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	56.3	25.0	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	56.3	25.0	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B Dual Stream	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
4096 x 2160/30p	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 10bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	SQ	6G-SDI Type 1	RGB	4:4:4 12bit
	4 096 x 2 160*3	67.5	30.0*1	297.0	IL	6G-SDI Type 1	RGB	4:4:4 12bit
4000 0400/00	4 096 x 2 160*3	135.0	60.0*1	594.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4096 x 2160/60p	4 096 x 2 160*3	135.0	60.0 <sup>*1</sup>	594.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4000 0400/50	4 096 x 2 160*3	112.5	50.0	594.0	SQ	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
4096 x 2160/50p	4 096 x 2 160*3	112.5	50.0	594.0	IL	6G-SDI Type 1	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit

Chapter 7 Appendix — Technical information

\*1 The signal with 1/1.001x vertical scanning frequency is also supported.
\*2 The optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) is not supported.
\*3 Only the combination of the <SDI 1 IN> terminal and the <SDI 3 IN> terminal of the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is supported.

## List of quad link SDI compatible signals

The following table specifies the quad link SDI signals that the projector can project.

This is the list of compatible signals including the input of the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) installed in the slot, in addition to the standard SDI input.

• The content of the 4K division column is as follows.

- SQ: Square (transmission format of Square Division)
- IL: Interleave (transmission format of 2-Sample Interleave Division)

Circul name	Desslution	Scanni	ng freq.	Dot clock	4K			
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4N division	Format	Color format	Sampling
	3 840 x 2 160	54.0	24.0 <sup>*1</sup>	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	54.0	24.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	24.0 <sup>*1</sup>	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	24.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	24.0 <sup>*1</sup>	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
3840 x 2160/24p	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	54.0	48.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	54.0	48.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/24sF	3 840 x 2 160	54.0	48.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	54.0	48.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	54.0	48.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	54.0	48.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit

		Scanni	ng freq.	Dot clock				
Signal name	Resolution	Horizontal	Vertical	freq.	4K	Format	Color format	Sampling
(SIGNAL FORMAT)	(Dots)	(kHz)	(Hz)	(MHz)	division			
	3 840 x 2 160	56.3	25.0	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
3840 x 2160/25p	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
3840 x 2160/25sF	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	56.3	50.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
3840 x 2160/30p	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit
	3 840 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit

Chapter 7 Appendix — Technical information

		Scanning freq.		Dot clock					
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal (kHz)	Vertical (Hz)	freq. (MHz)	4K division	Format	Color format	Sampling	
	3 840 x 2 160	67.5	60.0 <sup>*1</sup>	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	3 840 x 2 160	67.5	60.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
3840 x 2160/30sF	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit	
	3 840 x 2 160	67.5	60.0 <sup>*1</sup>	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit	
	3 840 x 2 160	67.5	60.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit	
	3 840 x 2 160	135.0	60.0*1	594.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
0040 0400/00-	3 840 x 2 160	135.0	60.0*1	594.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
3840 x 2160/60p	3 840 x 2 160	135.0	60.0*1	594.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	3 840 x 2 160	135.0	60.0 <sup>*1</sup>	594.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	3 840 x 2 160	112.5	50.0	594.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	3 840 x 2 160	112.5	50.0	594.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
3840 x 2160/50p	3 840 x 2 160	112.5	50.0	594.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	3 840 x 2 160	112.5	50.0	594.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
4096 x 2160/24p	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
·	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit	
	4 096 x 2 160	54.0	24.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit	

Chapter 7 Appendix — Technical information

		Scanni	ng freq.	Dot clock					
Signal name (SIGNAL FORMAT)	Resolution (Dots)	Horizontal Vertical		freq.	4K division	Format	Color format	Sampling	
(SIGNAL FORMAT)	(Dots)	(kHz)	(Hz)	(MHz)	uivision				
	4 096 x 2 160	56.3	25.0	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
4096 x 2160/25p	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit	
	4 096 x 2 160	56.3	25.0	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	HD-SDI	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
4096 x 2160/30p	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 10bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-A	RGB	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	SQ	3G-SDI Level-B	RGB	4:4:4 12bit	
	4 096 x 2 160	67.5	30.0*1	297.0	IL	3G-SDI Level-B	RGB	4:4:4 12bit	
	4 096 x 2 160	135.0	60.0*1	594.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
4096 x 2160/60p	4 096 x 2 160	135.0	60.0*1	594.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
+000 X 2 100/00p	4 096 x 2 160	135.0	60.0*1	594.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	135.0	60.0*1	594.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	112.5	50.0	594.0	SQ	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
4006 x 2460/50c	4 096 x 2 160	112.5	50.0	594.0	IL	3G-SDI Level-A	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
4096 x 2160/50p	4 096 x 2 160	112.5	50.0	594.0	SQ	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	
	4 096 x 2 160	112.5	50.0	594.0	IL	3G-SDI Level-B	YP <sub>B</sub> P <sub>R</sub>	4:2:2 10bit	

Chapter 7 Appendix — Technical information

\*1 The signal with 1/1.001x vertical scanning frequency is also supported.

#### List of simultaneous input compatible signals

		Scanni	ng freq.		Simultaneous input compatible signal					
Signal name	Resolution	Horizontal (kHz)	Vertical (Hz)	Dot clock freq.	SDI		HDMI*1		DVI-D*2	
(SIGNAL FORMAT)	(Dots)			(MHz)	Double speed	Quadruple speed	Double speed	Quadruple speed	Double speed	Quadruple speed
1080/60p	1 920 x 1 080	67.5	60.0	148.5	✓*3	✓*4	1	1	1	1
1080/50p	1 920 x 1 080	56.3	50.0	148.5	<b>√</b> *3	✓*4	1	1	1	~
3840 x 2160/60p	3 840 x 2 160	135.0	60.0	594.0	✓*5	—	✓*6	_		_
3840 x 2160/50p	3 840 x 2 160	112.5	50.0	594.0	✓*5	—	✓*6	_		_
4096 x 2160/60p	4 096 x 2 160	135.0	60.0	594.0	✓*5	—	✓*6	_	_	
4096 x 2160/50p	4 096 x 2 160	112.5	50.0	594.0	✓*5	—	✓*6	_	_	
1366 x 768/50	1 366 x 768	39.6	49.9	69.0	_	—	1	_	1	_
1366 x 768/60	1 366 x 768	47.7	59.8	85.5	_	—	1	_	1	_
1400 x 1050/50	1 400 x 1 050	54.1	50.0	99.9	_	—	1	_	1	_
1400 x 1050/60	1 400 x 1 050	65.3	60.0	121.8	_	—	1	_	1	_
1920 x 1080/50	1 920 x 1 080	55.6	49.9	141.5	_	—	1	_	1	_
1920 x 1080/60	1 920 x 1 080*7	66.6	59.9	138.5	_	_	1		1	—
1920 x 1200/50	1 920 x 1 200	61.8	49.9	158.3	_	—	1	_	1	—
1920 x 1200/60RB	1 920 x 1 200*7	74.0	60.0	154.0	_	_	1	_	1	—

The following table specifies the simultaneous input compatible video signals that the projector can project.

\*1 This is supported when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in the slot.

\*2 This is supported when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in the slot.

\*3 In addition to the standard SDI input, this supports the input of the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) or the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) installed in the slot.

\*4 In addition to the standard SDI input, this supports the input from the optional 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G) installed in the slot.

Input of the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is not supported.

\*5 This is supported when the optional Interface Board for 12G-SDI (Model No.: ET-MDN12G10) is installed in the slot.

\*6 When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35). \*7 VESA CVT-RB (Reduced Blanking) compliant

Note

 The geometric adjustment function and the expansion function by applying the optional Upgrade Kit (Model No.: ET-UK20) cannot be used when the video signal in simultaneous format is input.

# **Specifications**

The specifications of the projector are as follows.

Power supply		PT-RQ32K, PT-RQ32KT	100 V - 120 V / 200 V - 240 V $\sim$ (100 V - 120 V / 200 V - 240 V alternating current), 50 Hz/60 Hz				
		PT-RQ32KD	200 V - 240 V $\sim$ (200 V - 240 V alternating current), 50 Hz/60 Hz				
		PT-RQ32K, PT-RQ32KT	1 210 W (12 A) / 2 950 W (16 A)				
Power consumption		PT-RQ32KD	2 950 W (16.1 A)				
Power consumption (during standby)		When [STANDBY MODE] is set to	ECO]: 0.3 W				
		When [STANDBY MODE] is set to [NORMAL]: 4 W					
Size		22.9 mm (0.9") (aspect ratio 16:10)					
DLP chip	Display system	DLP chip x 3, DLP projection system	n				
	Number of pixels	4 096 000 pixels (2 560 x 1 600 dot	s)				
Lens		Optional					
Light source		Laser x 2					
		When [OPERATING MODE] is set to [HIGH]	26 000 lm*1*3, 27 000 lm (center)*2*3				
		When [OPERATING MODE] is set to [NORMAL]	21 600 lm*1*3, 22 500 lm (center)*2*3				
Light output		When [OPERATING MODE] is set to [LONG LIFE1]	12 000 lm*1*3				
		When [OPERATING MODE] is set to [LONG LIFE2]	10 000 lm*1*3				
		When [OPERATING MODE] is set to [LONG LIFE3]	8 000 lm*1*3				
Center to con	rner zone ratio*1	90 %					
Contrast ratio	0*1	20 000:1 (when [DYNAMIC CONTRAST] is set to [3])					
Projected im	age size	1.78 m (70") to 25.40 m (1 000")*4					
Image aspec	t ratio	16:10					
Projection m	ethod	[FRONT/CEILING], [FRONT/FLOOR], [REAR/CEILING], [REAR/FLOOR]					
Power cord I	ength	3.0 m (118-1/8")					
Outer case		Fabricated metal and molded plastic					
	Width	700 mm (27-9/16")					
		418 mm (16-15/32") (with the feet at shortest position)					
Dimensions	Height	373 mm (14-11/16") (excluding the feet)					
		370 mm (14-9/16") (excluding the feet and protrusion)					
	Depth	1 070 mm (42-1/8") (excluding the p	protrusion)				
Weight		Approx. 83.0 kg (183.0 lbs.)*5					
Noise level*1		49 dB					
	Operating environment	0 °C (32 °F) to 45 °C (113 °F)*6*7					
Operating environment	temperature						
environment	Operating environment humidity	10 % to 80 % (no condensation)					
	Power supply	DC 3 V (AA/R6/LR6 battery x 2)					
Remote	Operating range		operated directly in front of signal receiver)				
control	Weight	150 g (5.3 ozs.) (including batteries					
	Dimensions						
	2	Width: 47.5 mm (1-7/8"), Height: 181.5 mm (7-5/32"), Depth: 27.5 mm (1-3/32")					

\*1 Measurement, measuring conditions, and method of notation all comply with ISO/IEC 21118:2012 international standards.
 \*2 The value of the light output at the center region of the projected image is extracted based on the light output measurement method defined by the

ISO/IEC 21118:2012 international standards.

\*3 When a projection lens other than ET-D75LE95, ET-D75LE90 is used with the power supply voltage of AC 200 V.

\*4 When the Zoom Lens (Model No.: ET-D75LE8) is used, the projected image size for the maximum projection distance will be 1.78 m (70") to 15.24 m (600"). When the Fixed-focus Lens (Model No.: ET-D75LE95, ET-D75LE90) is used, the projected image size for the maximum projection distance will be 3.05 m (120") to 15.24 m (600").

\*5 Average value. Weight varies for each product.

\*6 The operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F) if the projector is used at an altitude between 1 400 m (4 593') and 4 200 m (13 780') above sea level. When the [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F), regardless of the altitude. When the Smoke Cut Filter is used, the operating environment temperature should be between 0 °C (32 °F) and 40 °C (104 °F).

When the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], the projector cannot be used at an altitude of 2 700 m (8 858') or higher above sea level. When the Smoke Cut Filter is used, the projector cannot be used at an altitude of 1 400 m (4 593') or higher above sea level.

\*7 When the [PROJECTOR SETUP] menu → [OPÉRATION SETTING] → [OPERATING MODE] is set to [HIGH] or [NORMAL], and the operating environment temperature exceeds the following value, the light output may be reduced to protect the projector.
• When using the projector at an altitude lower than 2 700 m (8 858') above sea level: 35 °C (95 °F)

• When using the projector at an altitude between 2 700 m (8 858') and 4 200 m (13 780') above sea level: 25 °C (77 °F)

When the [PROJECTOR SETUP] menu  $\rightarrow$  [OPERATION SETTING]  $\rightarrow$  [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3], and the operating environment temperature exceeds 35 °C (95 °F), the light output may be reduced to protect the projector.

#### Note

- The light output will decrease to approximately 1/3 when using the projector with AC 100 V to AC 120 V.
- The model numbers of accessories and optional accessories are subject to change without prior notice.

#### Connecting terminal/slot

	Total 4 sets (BNC)					
	Single link SD-SDI signal	SMPTE ST 259 compliant				
	Single link HD-SDI signal	SMPTE ST 292 compliant				
	Single link 3G-SDI signal	SMPTE ST 424 compliant				
<sdi 1="" in=""> terminal <sdi 2="" in=""> terminal <sdi 3="" in=""> terminal <sdi 4="" in=""> terminal</sdi></sdi></sdi></sdi>	Dual link HD-SDI signal	SMPTE ST 372 compliant <sdi 1="" in=""> terminal: LINK-A signal/<sdi 2="" in=""> terminal: LINK-B signal/<sdi 3="" in=""> terminal: LINK-A signal/<sdi 4="" in=""> terminal: LINK-B signal</sdi></sdi></sdi></sdi>				
	Dual link 3G-SDI signal	SMPTE ST 425 compliant <sdi 1="" in=""> terminal: Link 1 signal/<sdi 2="" in=""> terminal: Link 2 signal/<sdi 3="" in=""> terminal: Link 1 signal/<sdi 4="" in=""> terminal: Link 2 signal</sdi></sdi></sdi></sdi>				
	Quad link HD-SDI signal	<sdi 1="" in=""> terminal: Link 1 signal/<sdi 2="" in=""> terminal: Link 2 signal/<sdi 3="" in=""> terminal: Link 3 signal/<sdi 4="" in=""> terminal: Link 4 signal</sdi></sdi></sdi></sdi>				
	Quad link 3G-SDI signal	SMPTE ST 425 compliant <sdi 1="" in=""> terminal: Link 1 signal/<sdi 2="" in=""> terminal: Link 2 signal/<sdi 3="" in=""> terminal: Link 3 signal/<sdi 4="" in=""> terminal: Link 4 signal</sdi></sdi></sdi></sdi>				
<multi projector="" sync<="" th=""><th>1 set (BNC)</th><th></th></multi>	1 set (BNC)					
IN> terminal	TTL high impedance					
<multi projector="" sync<="" th=""><th colspan="6">1 set (BNC)</th></multi>	1 set (BNC)					
OUT> terminal	TTL output: Maximum 10 mA					
<serial in=""> terminal <serial out=""> terminal</serial></serial>	D-Sub 9 p, 1 set each, RS-232C comp	liant, for computer control				
<remote 1="" in=""> terminal <remote 1="" out=""> terminal</remote></remote>	M3 stereo mini jack, 1 set each, for remote control (wired)/for projector connection control					
<remote 2="" in=""> terminal</remote>	1 set, D-Sub 9 p, for contact control					
<digital lan="" link=""> terminal</digital>	1 set, RJ-45, for network and DIGITAL LINK connections (HDBaseT™ compliant), PJLink compatible, 100Base-TX, Art-Net compatible, HDCP 2.2 compatible, Deep Color compatible					
<slot 1=""> <slot 2=""></slot></slot>	Total 2 sets (blank), SLOT NX specification, for installing the Interface Board					
<dc 1="" out=""> terminal <dc 2="" out=""> terminal</dc></dc>	2 sets, USB connector (type A), for pow	ver supply only (DC 5 V, maximum 900 mA for each terminal)				

#### Compatible signal

For details of the types of video signals that can be used with the projector, refer to "List of compatible signals" (→ page 255).

SDI signal input	
SD-SDI signal	
HD-SDI signal	
3G-SDI signal	
6G-SDI signal*1	
12G-SDI signal⁵¹	
DIGITAL LINK signal input	
<ul> <li>Moving image signal resolution: 480/60i<sup>*2</sup>, 576/50i<sup>*2</sup> to 4 096 x 2 160</li> </ul>	
Still image signal resolution: 640 x 400 to 3 840 x 2 400 (non-interlace)	
Dot clock frequency: 25 MHz to 297 MHz	
HDMI signal input <sup>*3</sup>	
<ul> <li>Moving image signal resolution: 480/60i<sup>2</sup>, 576/50i<sup>2</sup> to 4 096 x 2 160</li> </ul>	
Still image signal resolution: 640 x 400 to 3 840 x 2 400 (non-interlace)	
Dot clock frequency: 25 MHz to 594 MHz	
DVI-D signal input*4	
<ul> <li>Moving image signal resolution: 480/60i*2, 576/50i*2 to 2 048 x 1 080</li> </ul>	
Still image signal resolution: 640 x 400 to 1 920 x 1 200 (non-interlace)	
Dot clock frequency: 25 MHz to 162 MHz	
DisplayPort signal input⁺⁵	
<ul> <li>Moving image signal resolution: 720/60p to 4 096 x 2 160/60p</li> </ul>	
Still image signal resolution: 640 x 480 to 3 840 x 2 400 (non-interlace)	
<ul> <li>Dot clock frequency: 25 MHz to 594 MHz</li> </ul>	

\*2 Pixel-Repetition signal (dot clock frequency 27.0 MHz) only

\*3 This is supported when the optional Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) is installed in the slot.

\*4 This is supported when the optional Interface Board for DVI-D 2 input (Model No.: ET-MDNDV10) is installed in the slot.

\*5 This is supported when the optional Interface Board for DisplayPort 2 input (Model No.: ET-MDNDP10) is installed in the slot.

#### Note

• When performing the simultaneous input of the 4K image (resolution of 3 840 x 2 160 or 4 096 x 2 160) using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10), it is necessary for the firmware version of the Interface Board for HDMI 2 input to be 2.00 or later. If the version is earlier than 2.00, the simultaneous process is not performed even if corresponding signal is input. Consult your dealer regarding the version update to the latest firmware.


For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).

 To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (+ page 35).


# Dimensions

Unit: mm



\* Actual dimensions may differ depending on the product.

■ When the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached



# Attaching the Long Life Filter Unit (optional)

The optional Long Life Filter Unit (Model No.: ET-EMFU330) uses two of the same standard air filter unit attached to the projector or the Replacement Filter Unit (Model No.: ET-EMF330) (accessory/optional accessory). The interval to perform maintenance/replacement of filters is extended roughly two times by attaching the Long Life Filter Unit instead of the standard air filter unit.

When purchasing the optional Long Life Filter Unit (Model No.: ET-EMFU330), consult your dealer.

#### Attention


- Make sure to turn off the power before removing the standard air filter unit attached to the projector and attaching the optional Long Life Filter Unit. (+ page 72)
- Make sure that the projector is stable, and perform the maintenance in a safe place even if the filter falls accidentally.

#### Note

• When the optional Long Life Filter Unit (Model No.: ET-EMFU330) is attached, the eyebolts cannot be attached on that side of the projector.

## Removing the air filter unit

First, remove the standard air filter unit attached to the projector.



#### 1) Turn off the power of the projector.

 When switching off the projector, make sure to follow the procedures in "Switching off the projector" (> page 72).

#### 2) Remove the air filter cover.

- Use a Phillips screwdriver to turn the air filter cover fixing screw counterclockwise until it turns freely (Fig. 1), and open the air filter cover for approximately 90°, and then pull out in the direction of the arrow. (Fig. 2)
- Loosen the air filter cover fixing screw while holding the air filter cover with your hand.

#### 3) Remove the drop-prevention string.

• Remove the hook at the tip of the drop-prevention string attached to the air filter cover. (Fig. 3)

#### 4) Pull out the air filter unit.


- i) Pull out the air filter unit from the tabs on the projector body (c) while slightly pressing the grip on the air filter unit (a) inward as described with the arrow. (Fig. 4)
- ii) Pull out the air filter unit. (Fig. 5)
  - When pulling out, confirm that the air filter unit comes off from the tabs on the projector body (d).
  - After pulling out the air filter unit, remove large foreign objects and dust from the air filter unit compartment and the air intake port of the projector body if there are any.
  - When the air filter unit is removed, proceed to "Attaching the long life filter mount clasp" (> page 282) next.

#### Attention

- Take care not to touch the radiator fin, etc., when removing dirt or dust.
- Store the removed air filter cover in a safe place.

# Attaching the long life filter mount clasp

Attach the long life filter mount clasp in the area the standard air filter unit was removed.



#### 1) Attach the hook of the drop-prevention string to the long life filter mount clasp. (Fig. 1)

• Attach the hook on the tip of the drop-prevention string attached to the projector body to the long life filter mount clasp supplied with the Long Life Filter Unit (optional) at the position indicated in the figure.


#### 2) Attach the long life filter mount clasp to the projector body. (Fig. 2)

• Align the two hooks of the long life filter mount clasp to the position of the holes where the air filter cover was inserted, and slide it in the direction of the arrow.

#### 3) Secure the long life filter mount clasp. (Fig. 3)

- Securely fix with one long life filter mount clasp fixing screw (M4 x 10) supplied with the Long Life Filter Unit (optional).
- When the long life filter mount clasp is attached, proceed to "Attaching the air filter unit" (> page 282) next.

## Attaching the air filter unit



#### 1) Attach the two air filter units to the long life filter cover. (Fig. 1)

- Attach the two air filter units supplied with the Long Life Filter Unit (optional) to the long life filter cover. The method to attach the two air filter units is the same.
- Align the position so that the grips on the air filter unit (a) and (b) will be outside the guides on the long life filter cover (e) and (f), and push in the direction of the arrow by holding the outer frame of the air filter unit. (Fig. 2)
- When the two air filter units are attached (Fig. 3), proceed to "Attaching the long life filter cover" (> page 283) next.


Note

# 282 - ENGLISH

<sup>•</sup> Make sure that the air filter unit is properly attached before using the projector. If it is not attached, the projector will suck in dirt and dust causing a malfunction.

## Attaching the long life filter cover

Attach the long life filter cover with the air filters to the long life filter mount clasp on the projector body.



- 1) Attach the long life filter cover to the long life filter mount clasp. (Fig. 1)
  - Attach the long life filter cover (with the two air filter units attached) to the long life filter mount clasp on the projector body.
  - The long life filter has no difference between top and bottom.
- 2) Secure the long life filter cover. (Fig. 2)
  - Securely fix with the two long life filter cover fixing screws (knurled head screws) supplied with the Long Life Filter Unit (optional).
  - When the long life filter cover is secured, proceed to "Setting the filter" (→ page 283) next.

# Setting the filter

Set the type of filter, and then reset the filter runtime (counter numerical value).

- 1) Turn on the power of the projector.
- 2) Press the <MENU> button on the remote control or control panel.
   The [MAIN MENU] screen is displayed.
- 3) Press  $\blacktriangle \lor$  to select [PROJECTOR SETUP].
- 4) Press the <ENTER> button.
   The [PROJECTOR SETUP] screen is displayed.
- 5) Press  $\blacktriangle \lor$  to select [FILTER SETTING].
- 6) Press the <ENTER> button.
   The [FILTER SETTING] screen is displayed.
- 7) Press ▲▼ to select [FILTER TYPE].
- 8) Press **♦** to select [LONG LIFE].
- 9) Press ▲▼ to select [FILTER COUNTER RESET], and press the <ENTER> button.
- 10) When the confirmation screen is displayed, press <> to select [OK], and press the <ENTER> button.
   The [PROJECTOR SETUP] menu → [STATUS] → [FILTER COUNTER] is displayed as "0".

#### Attention

 When use of the Long Life Filter Unit is finished and replaced with a standard air filter unit, make sure to reset the filter counter after setting the [PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER TYPE] to [NORMAL]. When the [PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER COUNTER RESET] is executed, the filter counter is reset.

#### Note

<sup>•</sup> Continuing to use the projector with incorrect [FILTER TYPE] setting may cause failure of the projector.

<sup>•</sup> When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.

# Attaching the Smoke Cut Filter Unit (optional)

The optional Smoke Cut Filter (Model No.: ET-SFR330) is attached when using the projector in an environment generating smoke such as an event. Attach the Smoke Cut Filter instead of the standard air filter unit attached to the projector.

When purchasing the optional Smoke Cut Filter (Model No.: ET-SFR330), consult your dealer.

#### Attention


- Make sure to turn off the power before removing the standard air filter unit attached to the projector and attaching the optional Smoke Cut Filter. (+ page 72)
- Make sure that the projector is stable, and perform the maintenance in a safe place even if the filter falls accidentally.

#### Note

- The Smoke Cut Filter cannot be used at an altitude of 1 400 m (4 593') or higher and in an operating environment where the temperature exceeds 40 °C (104 °F).
- Set [OPERATING MODE] to anything other than [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when using the optional Smoke Cut Filter (Model No.: ET-SFR330).
- The Smoke Cut Filter cannot be maintained, recycled, or reused. Make sure to replace it with an unused one.

# Removing the air filter unit

First, remove the standard air filter unit attached to the projector.



#### 1) Turn off the power of the projector.

 When switching off the projector, make sure to follow the procedures in "Switching off the projector" (> page 72).

#### 2) Open the air filter cover. (Fig. 1)

- Use a Phillips screwdriver to turn the air filter cover fixing screw counterclockwise until it turns freely, and open the air filter cover for approximately 90°.
- Loosen the air filter cover fixing screw while holding the air filter cover with your hand.

#### 3) Pull out the air filter unit.


- i) Pull out the air filter unit from the tabs on the projector body (c) while slightly pressing the grip on the air filter unit (a) inward as described with the arrow. (Fig. 2)
- ii) Pull out the air filter unit. (Fig. 3)
  - When pulling out, confirm that the air filter unit comes off from the tabs on the projector body (d).
  - After pulling out the air filter unit, remove large foreign objects and dust from the air filter unit compartment and the air intake port of the projector body if there are any.
  - When the air filter unit is removed, proceed to "Attaching the Smoke Cut Filter" (> page 285) next.

#### Attention

• Take care not to touch the radiator fin, etc., when removing dirt or dust.

# Attaching the Smoke Cut Filter

Air filter unit compartment (Smoke Cut Filter compartment)



#### 1) Attach the Smoke Cut Filter to the projector body.

- Insert the Smoke Cut Filter in the direction of the arrow indicated on the Smoke Cut Filter into the air filter unit compartment (Smoke Cut Filter compartment) of the projector body. (Fig. 1)
- The Smoke Cut Filter has no difference between top and bottom, but is two-sided.
- i) Hook the Smoke Cut Filter frame at the bottom side to the tabs on the air filter unit compartment (Smoke Cut Filter compartment) of the projector body (d). (Fig. 1)
- ii) While lightly pressing inward as described with the arrow (Fig. 1), hook the center area of the Smoke Cut Filter frame at the top side to the tabs on the air filter unit compartment (Smoke Cut Filter compartment) of the projector body (c). (Fig. 2)
  - Confirm that the tabs on the air filter unit compartment (Smoke Cut Filter compartment) (c) and (d) are hooked to the Smoke Cut Filter frame.
- 2) Slide the air filter cover toward the direction of the arrow to close (Fig. 3), and tighten the air filter cover fixing screw using a Phillips screwdriver.
  - When the Smoke Cut Filter and the air filter cover are attached to the projector body, proceed to "Setting the filter" (→ page 285) next.

#### Note

• Make sure that the Smoke Cut Filter is properly attached before using the projector. If it is not attached, the projector will suck in dirt and dust causing a malfunction.

### Setting the filter

Set the type of filter, and then reset the filter runtime (counter numerical value).

- 1) Turn on the power of the projector.
- 2) Press the <MENU> button on the remote control or control panel.
  The [MAIN MENU] screen is displayed.
- 3) Press ▲▼ to select [PROJECTOR SETUP].
- 4) Press the <ENTER> button.
   The [PROJECTOR SETUP] screen is displayed.
- 5) Press  $\blacktriangle \lor$  to select [FILTER SETTING].
- 6) Press the <ENTER> button.
  - The [FILTER SETTING] screen is displayed.
- 7) Press ▲▼ to select [FILTER TYPE].
- 8) Press **♦** to select [SMOKE CUT].
- 9) Press ▲▼ to select [FILTER COUNTER RESET], and press the <ENTER> button.

#### 10) When the confirmation screen is displayed, press **♦** to select [OK], and press the **<ENTER>** button.

• The [PROJECTOR SETUP] menu  $\rightarrow$  [STATUS]  $\rightarrow$  [FILTER COUNTER] is displayed as "0".

#### Attention

When use of the Smoke Cut Filter is finished and replaced with a standard air filter unit, make sure to reset the filter counter after setting
[PROJECTOR SETUP] menu → [FILTER SETTING] → [FILTER TYPE] to [NORMAL]. When the [PROJECTOR SETUP] menu → [FILTER
SETTING] → [FILTER COUNTER RESET] is executed, the filter counter is reset.

#### Note

- [FILTER TYPE] cannot be set to [SMOKE CUT] when the [PROJECTOR SETUP] menu → [OPERATION SETTING] → [OPERATING MODE] is set to [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3]. Set [OPERATING MODE] to anything other than [LONG LIFE1], [LONG LIFE2], or [LONG LIFE3] when using the Smoke Cut Filter.
- Continuing to use the projector with incorrect [FILTER TYPE] setting may cause failure of the projector.
- When the projector is used without resetting the filter counter, the actual filter runtime (counter numeric value) will not be able to be confirmed.
- When replacing the Smoke Cut Filter, remove the used Smoke Cut Filter by performing Steps 1) and 2) in "Attaching the Smoke Cut Filter" (
   page 285) in the reverse order.
- When use of the Smoke Cut Filter is finished and replaced with the air filter unit, perform the steps in "Attaching the Smoke Cut Filter" (> page 285) and "Removing the air filter unit" (> page 284) in the reverse order to replace.

# Installing the Interface Board (optional)

This projector is equipped with two SLOT NX-specification slots.

There are four SDI input terminals and one DIGITAL LINK input terminal equipped on this projector as the standard video input terminals. The input for HDMI, DVI-D, and SDI can be added by installing the optional Interface Board in the slot.

Requesting a qualified technician to install or remove the optional Interface Board is recommended. A malfunction may occur due to static electricity. Consult your dealer.


# Before installing or removing

- Always turn off the power of the projector before installing or removing the Interface Board.
- Always follow the procedure of "Switching off the projector" (→ page 72) when turning off the power.
- Do not touch the connector section of the Interface Board directly with your hands.
- The component may be damaged by the static electricity.
- Remove the static electricity from your body by touching to surrounding metal, etc., in advance to prevent the static electricity damage.
- Take care not to get injured when installing or removing the Interface Board.
- Hands may be injured by the opening of the blank slot or the edge of the bracket of the Interface Board.
- When installing the Interface Board to the slot, insert it into the connector straight and slowly.
- It may not operate or cause malfunction if it is not correctly installed.
- To use the 3G-SDI Terminal Board with Audio (Model No.: TY-TBN03G), it is necessary for the firmware version of the 3G-SDI Terminal Board with Audio to be 2.00 or later. Consult your dealer regarding the version update to the latest firmware if the version is earlier than 2.00.

For details on how to confirm the firmware version, refer to "How to confirm the firmware version of the Interface Board (optional)" (→ page 35).

• The figure indicating the installation and removal of the Interface Board is using the Interface Board for HDMI 2 input (Model No.: ET-MDNHM10) as an example.

# How to install the Interface Board



### 1) Remove the slot cover. (Fig. 1)

- Remove the four screws fixing the slot cover by rotating counterclockwise with a Phillips screwdriver. The removed screws are used to fix the Interface Board.
- When removing the fourth screw, hold the slot cover with your hand so it will not fall.
- To replace from other Interface Board, remove the Interface Board following the procedure in "How to remove the Interface Board" (➡ page 288).

## 2) Install the Interface Board to the projector. (Fig. 2)

• Insert the guide groove of the Interface Board aligned to the salient of the slot. Insert the bracket firmly all the way in.


## 3) Fix the Interface Board. (Fig. 3)

• Tighten and fix with the four screws removed in Step 1).

#### Attention

• The removed slot cover is required when the unnecessary Interface Board is removed. Store it so it can be attached in the future.

#### How to remove the Interface Board



#### 1) Remove the Interface Board. (Fig. 1)

- Remove the four screws fixing the Interface Board by rotating counterclockwise with a Phillips screwdriver. The removed screws are used to fix the slot cover.
- Hold the handle of the Interface Board and remove it slowly.

#### 2) Attach the slot cover.

- Attach the stored slot cover, and tighten and fix with the four screws removed in Step 1).
- To replace with other Interface Board, attach the Interface Board following the procedure in "How to install the Interface Board" (→ page 287).

#### Attention

• Always attach the slot cover on the blank slot.

Store the removed Interface Board inside an antistatic bag.

# Index

Α	
Accessories	
AC INS terminal	30, 62
[AC VOLTAGE MONITOR]	
AC voltage monitor function	
Adjusting adjustable feet	
[ADVANCED MENU]	
Art-Net	
[Art-Net CHANNEL SETTING]	
[Art-Net SETUP]	
[Art-Net STATUS] [ASPECT]	
<pre><aspect> button</aspect></pre>	
Remote control	
Aspect function	
Attaching/removing the projection lens Automatic setup function	
[AUTO SETUP]	
<auto setup=""> button</auto>	
Projector body	31, 84
Remote control	
В	
[BACK COLOR]	141
[BACKUP INPUT SETTING] [BLANKING]	
[BRIGHTNESS]	
[BRIGHTNESS CONTROL]	
<b>C</b>	
C Cautions on use	20
Cautions when installing	
Cautions when transporting	17
[COLOR]	94
[COLOR MATCHING] [COLOR SPACE]	
[COLOR SFACE]	
Connecting the power cord	62
Connecting the remote control to the project	
with a cable Connection	
[CONTRAST]	
[CONTROL DEVICE PASSWORD CHANG	
[CONTROL DEVICE SETUP]	
[Crestron Connected(TM)] [CUT OFF]	
D	
[DATE AND TIME]	170
<default> button Remote control</default>	28 89
Deleting the registered signal	
IDIGITAL CINEMA REALITY1	
DIGITAL LINK	22
<digital link=""> button Projector body</digital>	31 7/
Remote control	28, 73
[DIGITAL LINK IN]	
[DIGITAL LINK MENU]	
[DIGITAL LINK MODE] [DIGITAL LINK STATUS]	
Dimensions	
Display language	91, 113
[DISPLAY OPTION]	
[DISPLAY SETTING] Disposal	
<pre>&gt;Disposal</pre>	
Remote control	
[DYNAMIC CONTRAST]	98
E	
Early Warning Software	22
[EDGE BLENDING]	
<enter> button</enter>	04
Projector body Remote control	
Expanding signal lock-in range	
F	000
Filter indicator [FILTER SETTING]	
<pre><focus> button</focus></pre>	
Remote control	28, 75
[FRAME CREATION]	
[FRAME RESPONSE] [FREEZE]	

Function button <function> button</function>	
Remote control28 [FUNCTION BUTTON]	
<b>G</b> [GAMMA] [GEOMETRY]	
H <hdmi> button Remote control</hdmi>	73
I <id all=""> button</id>	, 10
Remote control28 <id set=""> button</id>	
Remote control	181
Initial setting [INITIAL STARTUP] <input menu=""/> button	
Projector body31 Remote control	, 75
Input selection terminal indicator Installation mode Interface Board	39
	201
L [LARGE SCREEN CORRECTION] [LENS]	
<lens> button Projector body31</lens>	
[LENS CALIBRATION]	159
LENS HOME POSITION] LENS INFORMATION SETTING]	155
[LENS MEMORY]	151
[LENS TYPE] <light> button</light>	149
Remote control	28
[LIGHT OUTPUT]	
Light source indicator <light> switch</light>	222
Projector body	31
List of compatible signals	255
[LOAD ALL USER DATA] <lock> button</lock>	181
Remote control	
M	
Main menu	89
Main power switch30	
	225
	~~
<menu> button</menu>	. 88
<menu> button Projector body31 Remote control28</menu>	, 88
<menu> button Projector body31 Remote control28 Menu item</menu>	, 88 90
<menu> button Projector body</menu>	, 88 90 183 183
<menu> button Projector body31 Remote control28 Menu item</menu>	, 88 90 183 183
<menu> button Projector body</menu>	, 88 90 183 183
<menu> button Projector body</menu>	, 88 90 183 183 173
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98 168
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98 168
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 197 98 168 168 168
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98 168 168 168 , 83 139
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 197 98 168 168 , 83 139 88
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98 168 168 168 83 139 88 161
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 197 98 168 168 168 83 139 88 161
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 196 197 98 168 168 83 1.39 83 1.39 88 161 26 , 93
<menu> button Projector body</menu>	, 88 90 183 183 183 183 195 201 196 196 196 196 196 196 98 168 168 88 161 26 , 93 93
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 196 196 196 196 93 168 168 93 102
<menu> button Projector body</menu>	, 88 90 183 183 173 88 195 201 196 197 98 168 168 168 83 139 88 161 26 , 93 93 102 62

Power on button	
Projector body	31
Remote control	
Power standby button	
Projector body	
Remote control Precautions for use	
Projecting	
[PROJECTION METHOD]	
Projector body	29
[PROJECTOR ID]	
[PROJECTOR SETUP] Protecting the registered signal	.91, 148 187
Q	
[QUAD PIXEL DRIVE]	
QUAD PIXEL DRIVE	
R	
[RASTER POSITION]	
Read this first!	5
Registering new signals	
<remote 1="" in=""> terminal <remote 1="" out=""> terminal</remote></remote>	
<remote 001="" 1=""> terminal</remote>	
[REMOTE2 MODE]	
Remote control	28
Remote control operations	
Renaming the registered signal Replacing the unit	
Resetting to the factory default	231 89
[RS-232C]1	
S	
[SAVE ALL USER DATA] [SCHEDULE]	
[SCREEN SETTING]	
<sdi 1="" 2=""> button</sdi>	
Projector body	31, 74
<sdi 3="" 4=""> button</sdi>	o
Projector body	31, 74
Remote control	28 73
[SDI IN]	
Security	
[SECURITY]	92, 189
[SECURITY PASSWORD]	.92, 189 189
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE]	.92, 189 189 189
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE] Selecting the input signal	.92, 189 189 189 73
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE] Selecting the input signal Self-diagnosis display	.92, 189 189 73 .31, 235 249
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE] Selecting the input signal Self-diagnosis display	.92, 189 189 73 .31, 235 249 249
[SECURITY PASSWORD]	.92, 189 189 73 .31, 235 249 249 249 182
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE] Selecting the input signal Self-diagnosis display <serial in=""> terminal (SERIAL OUT&gt; terminal [SERVICE PASSWORD] Setting ID number of the remote control</serial>	.92, 189 189 73 .31, 235 249 249 182 86
[SECURITY PASSWORD] [SECURITY PASSWORD CHANGE] Selecting the input signal Self-diagnosis display <serial in=""> terminal <serial out=""> terminal [SERVICE PASSWORD] Setting ID number of the remote control Setting up [SHARPNESS]</serial></serial>	.92, 189 73 .31, 235 249 249 249 
[SECURITY PASSWORD]	.92, 189 73 .31, 235 249 249 249 
[SECURITY PASSWORD]         [SECURITY PASSWORD CHANGE]         Selecting the input signal         Self-diagnosis display <serial in=""> terminal         <serial out=""> terminal         [SERVICE PASSWORD]         Setting ID number of the remote control         Setting up         [SHARPNESS]         [SHIFT]         <shift> button</shift></serial></serial>	92, 189 189 189 73 31, 235 249 249 182 86 39 97 102
[SECURITY PASSWORD]	92, 189 189 189 73 31, 235 249 249 182 86 39 97 102
[SECURITY PASSWORD]	92, 189 189 189 73 31, 235 249 249 182 86 39 97 102 28, 75
[SECURITY PASSWORD]	92, 189 189 73 .31, 235 249 49 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]	92, 189 189 73 31, 235 249 249 249 249 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]         [SECURITY PASSWORD CHANGE]         Selecting the input signal         Selecting the input signal         Self-diagnosis display <serial in=""> terminal         (SERVICE PASSWORD]</serial>	92, 189 
[SECURITY PASSWORD]	92, 189 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]         [SECURITY PASSWORD CHANGE]         Selecting the input signal	92, 189 
[SECURITY PASSWORD]	92, 189 
[SECURITY PASSWORD]         [SECURITY PASSWORD CHANGE]         Selecting the input signal	92, 189 

T Temperature indicator	
U [UNIFORMITY]142 Upgrade Kit254	
W [WAVEFORM MONITOR]145	
<b>Z</b> [ZOOM]103 <zoom> button Remote control28, 75</zoom>	

# Disposal of Old Equipment and Batteries Only for European Union and countries with recycling systems



These symbols on the products, packaging, and/or accompanying documents mean that used electrical and electronic products and batteries must not be mixed with general household waste. For proper treatment, recovery and recycling of old products and used batteries, please take them to applicable collection points in accordance with your national legislation.

By disposing of them correctly, you will help to save valuable resources and prevent any potential negative effects on human health and the environment.

For more information about collection and recycling, please contact your local authority. Penalties may be applicable for incorrect disposal of this waste, in accordance with national legislation.



#### Note for the battery symbol (bottom symbol)

This symbol might be used in combination with a chemical symbol. In this case it complies with the requirement set by the Directive for the chemical involved.

### Information on Disposal in other Countries outside the European Union

These symbols are only valid in the European Union. If you wish to discard these items, please contact your local authorities or dealer and ask for the correct method of disposal.

# Product Information (for Turkey only)



Eski Ekipman ve Bataryaların İşlenmesi.

Sadece geri dönüşüm sistemleri olan Avrupa Birliği ve ülkeleri için geçerlidir.



Ürünler, ambalaj ve/veya ekli belgeler üzerindeki bu semboller kullanılmış elektrik ve elektronik ürünlerin ve pillerin genel ev atığı ile karıştırılmaması gerektiğini ifade eder. Eski ürünlerin ve pillerin toplanması ve geri kazanılması için bu atıkları lütfen yasayla belirlenmiş

olan uygun toplama merkezlerine teslim ediniz. Bu atıkların doğru işlenmesiyle, değerli kaynakların korunmasına ve insan sağlığı ve çevreye olası negatif etkilerinin engellenmesine yardımcı olabilirsiniz.



Atıkların toplanması ve geri dönüşümü için detaylı bilgi için lütfen bağlı olduğunuz yerel yönetimlerle iletişime geçiniz.

Atıkların atılmasıyla ilgili yanlış uygulamalar yasayla belirlenmiş olan cezalara sebebiyet verebilir.

# **Panasonic Corporation**

Web Site : https://panasonic.net/cns/projector/ © Panasonic Corporation 2017

# Panasonic System Solutions Company of North America

Two Riverfront Plaza, Newark, NJ 07102 TEL: (877) 803 - 8492

# Panasonic Canada Inc.

5770 Ambler Drive, Mississauga, Ontario L4W 2T3 TEL: (905) 624 - 5010